

**SECTION 08 11 13  
HOLLOW METAL DOORS AND FRAMES**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

- A. This section specifies steel doors, steel frames and related components.
- B. Terms relating to steel doors and frames as defined in ANSI A123.1 and as specified.

**1.2 RELATED WORK**

- A. Frames fabricated of structural steel: Section 05 50 00, METAL FABRICATIONS.
- B. Aluminum frames entrance work: Section 08 41 13, ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS.
- C. Overhead doors including loading docks: Section 08 33 00, COILING DOORS AND GRILLES.
- D. Door Hardware: Section 08 71 00, DOOR HARDWARE.

**1.3 TESTING**

An independent testing laboratory shall perform testing.

**1.4 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturers Literature and Data:
  - 1. Fire rated doors and frames, showing conformance with NFPA 80 and Underwriters Laboratory, Inc., or Intertek Testing Services or Factory Mutual fire rating requirements.
  - 2. Sound rated doors, including test report from Testing Laboratory.

**1.5 SHIPMENT**

- A. Prior to shipment label each door and frame to show location, size, door swing and other pertinent information.
- B. Fasten temporary steel spreaders across the bottom of each door frame.

**1.6 STORAGE AND HANDLING**

- A. Store doors and frames at the site under cover.
- B. Protect from rust and damage during storage and erection until completion.

**1.7 APPLICABLE PUBLICATIONS**

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.

- B. Federal Specifications (Fed. Spec.):
  - L-S-125B.....Screening, Insect, Nonmetallic
- C. Door and Hardware Institute (DHI):
  - A115 Series.....Steel Door and Frame Preparation for Hardware,  
Series A115.1 through A115.17 (Dates Vary)
- D. Steel Door Institute (SDI):
  - 113-01 (2006R).....Thermal Transmittance of Steel Door and Frame  
Assemblies
  - 100-(ANSI A250.8-03)....Standard Steel Doors and Frames  
(2008R)
- E. American Society for Testing and Materials (ASTM):
  - A167-99(R2004).....Stainless and Heat-Resisting Chromium-Nickel  
Steel Plate, Sheet, and Strip
  - A568/568-M-07.....Steel, Sheet, Carbon, and High-Strength, Low-  
alloy, Hot-Rolled and Cold-Rolled
  - A1008-08.....Steel, sheet, Cold-Rolled, Carbon, Structural,  
High Strength Low Alloy and High Strength Low  
Alloy with Improved Formability
  - B209/209M-07.....Aluminum and Aluminum-Alloy Sheet and Plate
  - B221/221M-08.....Aluminum and Aluminum-Alloy Extruded Bars,  
Rods, Wire, Profiles and Tubes
  - D1621-04.....Compressive Properties of Rigid Cellular  
Plastics
  - D3656-07.....Insect Screening and Louver Cloth Woven from  
Vinyl Coated Glass Yarns
- F. The National Association Architectural Metal Manufacturers (NAAMM):
  - AMP 500-06.....Metal Finishes Manual
- G. National Fire Protection Association (NFPA):
  - 80-08.....Fire Doors and Fire Windows
- H. Underwriters Laboratories, Inc. (UL):
  - Fire Resistance Directory
- I. Intertek Testing Services (ITS):
  - Certifications Listings...Latest Edition
- J. Factory Mutual System (FM):
  - Approval Guide

### **2.1 MATERIALS**

- A. Stainless Steel: ASTM A167, Type 302 or 304; finish, NAAMM Number 4.
- B. Sheet Steel: ASTM A1008, cold-rolled for panels (face sheets) of doors.
- C. Anchors, Fastenings and Accessories: Fastenings anchors, clips connecting members and sleeves from zinc coated steel.
- D. Aluminum Sheet: ASTM B209/209M.
- E. Aluminum, Extruded: ASTM B221/221M.
- F. Prime Paint: Paint that meets or exceeds the requirements of A250.8.

### **2.2 FABRICATION GENERAL**

- A. GENERAL:
  - 1. Follow ANSI A250.8 for fabrication of standard steel doors, except as specified otherwise. Doors to receive hardware specified in Section 08 71 00, DOOR HARDWARE. Tolerances as per SDI A250.8. Thickness, 44 mm (1-3/4 inches), unless otherwise shown.
  - 2. Close top edge of exterior doors flush and seal to prevent water intrusion.
  - 3. When vertical steel stiffeners are used for core construction, fill spaces between stiffeners with mineral fiber insulation.
- B. Standard Duty Doors: ANSI A250.8, Level 1, Model 2 of size and design shown. Use for interior locations only.
- C. Heavy Duty Doors: ANSI A250.8, Level 2, Model 2 of size and design shown. Core construction types a, d, or f, for interior doors, and, types b, c, e, or f, for exterior doors.
- D. Smoke Doors:
  - 1. Close top and vertical edges flush.
  - 2. Provide seamless vertical edges.
  - 3. Provide clearance at head, jamb and sill as specified in NFPA 80.
- E. Fire Rated Doors (Labeled):
  - 1. Conform to NFPA 80 when tested by Underwriters Laboratories, Inc., Inchcape Testing Services, or Factory Mutual for the class of door or door opening shown.
  - 2. Fire rated labels of metal, with raised or incised markings of approving laboratory shall be permanently attached to doors.

### **2.3 METAL FRAMES**

- A. General:
  - 1. SDI A250.8, 1.3 mm (0.053 inch) thick sheet steel, types and styles as shown or scheduled.

2. Frames for exterior doors: Fabricate from 1.7 mm (0.067 inch) thick galvanized steel conforming to ASTM A525.
  3. Frames for labeled fire rated doors.
    - a. Comply with NFPA 80. Test by Underwriters Laboratories, Inc., Inchcape Testing Services, or Factory Mutual.
    - b. Fire rated labels of approving laboratory permanently attached to frames as evidence of conformance with these requirements. Provide labels of metal or engraved stamp, with raised or incised markings.
- B. Reinforcement and Covers:
1. ANSI A250.8 for, minimum thickness of steel reinforcement welded to back of frames.
  2. Provide mortar guards securely fastened to back of hardware reinforcements
- C. Glazed Openings:
1. Integral stop on exterior, corridor, or secure side of door.
  2. Design rabbet width and depth to receive glazing material or panel shown or specified.
- D. Two piece frames:
1. One piece unequal leg finished rough buck sub-frames as shown, drilled for anchor bolts.
  2. Unequal leg finished frames formed to fit subframes and secured to subframe legs with countersunk, flat head screws, spaced 300 mm (12 inches) on center at head and jambs on each side.
  3. Preassemble at factory for alignment.
- E. Frame Anchors: ANSI A250.8
1. Two piece frames: Subframe or rough buck drilled for 6 mm (1/4 inch) bolts.
    - a. Anchors for observation windows and other continuous frames set in stud partitions.
      - 1) In addition to jamb anchors, weld clip anchors to sills and heads of continuous frames over 1200 mm (4 feet) long.
      - 2) Anchors spaced 600 mm (24 inches) on centers maximum.
    - b. Modify frame anchors to fit special frame and wall construction and provide special anchors where shown or required.

#### 2.4 LOUVERS

ANSI A2508.

ANSI A250.8.

**PART 3 - EXECUTION**

**3.1 INSTALLATION**

- A. Plumb, align and brace frames securely until permanent anchors are set.
1. Use triangular bracing near each corner on both sides of frames with temporary wood spreaders at midpoint.
  2. Use wood spreaders at bottom of frame if the shipping spreader is removed.
  3. Protect frame from accidental abuse.
  4. Where construction will permit concealment, leave the shipping spreaders in place after installation, otherwise remove the spreaders after the frames are set and anchored.
  5. Remove wood spreaders and braces only after the walls are built and jamb anchors are secured.
- B. Floor Anchors:
1. Anchor the bottom of door frames to floor with two 6 mm (1/4 inch) diameter expansion bolts. Use 9 mm (3/8 inch) bolts on lead lined frames.
  2. Power actuated drive pins may be used to secure frame anchors to concrete floors.
- C. Jamb Anchors:
1. Anchors in masonry walls: Embed anchors in mortar. Fill space between frame and masonry wall with grout or mortar as walls are built.
  2. Coat frame back with a bituminous coating prior to lining of grout filling in masonry walls.
  3. Secure anchors to sides of studs with two fasteners through anchor tabs. Use steel drill screws to steel studs.
  4. Frames set in prepared openings of masonry or concrete: Expansion bolt to wall with 6 mm (1/4 inch) expansion bolts through spacers. Where subframes or rough bucks are used, 6 mm (1/4 inch) expansion bolts on 600 mm (24 inch) centers or power activated drive pins 600 mm (24 inches) on centers. Secure two piece frames to subframe or rough buck with machine screws on both faces.
- D. Install anchors for labeled fire rated doors to provide rating as required.

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

E. Frames for Sound Rated Doors: Coordinate to line frames for sound rated doors with insulation.

F. Overhead Bracing (Lead Lined Frames): Where jamb extensions extend to structure above, anchor clip angles with not less than two, 9 mm (3/8 inch) expansion bolts or power actuated drive pins to concrete slab. Weld to steel overhead members.

### 3.2 INSTALLATION OF DOORS AND APPLICATION OF HARDWARE

Install doors and hardware as specified in Sections Section 08 11 13, HOLLOW METAL DOORS AND FRAMES Section 08 14 00, WOOD DOORS Section 08 71 00, DOOR HARDWARE.

- - - E N D - - -

**SECTION 08 14 00  
INTERIOR WOOD DOORS**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

- A. This section specifies interior flush doors and stile and rail office doors.
- B. Section includes fire rated doors, sound retardant doors, and smoke.

**1.2 RELATED WORK**

- A. Metal door frames: Section 08 11 13, HOLLOW METAL DOORS AND FRAMES.
- B. Door hardware including hardware location (height): Section 08 71 00, DOOR HARDWARE.
- C. Installation of doors and hardware: Section 08 11 13, HOLLOW METAL DOORS AND FRAMES, Section 08 14 00, WOOD DOORS, or Section 08 71 00, DOOR HARDWARE.
- D. Finish: Section 09 06 00, SCHEDULE FOR FINISHES.
- E. Metal louvers: Section 08 90 00, LOUVERS AND VENTS.

**1.3 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Samples:
  - 1. Corner section of door 300 mm (12 inches) square, showing details of construction, labeled to show grade and type number and conformance to specified standard.
- C. Shop Drawings:
  - 1. Show every door in project and schedule location in building.
  - 2. Indicate type, grade, finish and size; include detail of glazing, louvers, sound gasketing, and pertinent details.
  - 3. Provide information concerning specific requirements not included in the manufacturer's literature and data submittal.
- D. Manufacturer's Literature and Data:
  - 1. Labeled fire rated doors showing conformance with NFPA 80.
- E. Laboratory Test Reports:
  - 1. Screw holding capacity test report in accordance with WDMA T.M.10.
  - 2. Split resistance test report in accordance with WDMA T.M.5.
  - 3. Cycle/Slam test report in accordance with WDMA T.M.7.
  - 4. Hinge-Loading test report in accordance with WDMA T.M.8.

**1.4 WARRANTY**

- A. Doors are subject to terms of Article titled "Warranty of Construction", FAR clause 52.246-21, except that warranty shall be as follows:
  - 1. For interior doors, manufacturer's warranty for lifetime of original installation.

**1.5 DELIVERY AND STORAGE**

- A. Factory seal doors and accessories in minimum of 6 mill polyethylene bags or cardboard packages which shall remain unbroken during delivery and storage.
- B. Store in accordance with WDMA I.S.1-A, J-1 Job Site Information.
- C. Label package for door opening where used.

**1.6 APPLICABLE PUBLICATIONS**

Publications listed below form a part of this specification to extent referenced. Publications are referenced in text by basic designation only.

- B. Window and Door Manufacturers Association (WDMA):
  - I.S.1A-04.....Architectural Wood Flush Doors
  - I.S.4-09.....Water-Repellent Preservative Non-Pressure Treatment for Millwork
  - I.S.6A-08.....Architectural Wood Stile and Rail Doors
  - T.M.5-90(2009).....Split Resistance Test Method
  - T.M.6-08.....Adhesive (Glue Bond) Durability Test Method
  - T.M.7-08.....Cycle-Slam Test Method
  - T.M.8-08.....Hinge Loading Test Method
  - T.M.10-08.....Screwholding Test Method
- C. National Fire Protection Association (NFPA):
  - 80-07.....Protection of Buildings from Exterior Fire
  - 252-08.....Fire Tests of Door Assemblies

**PART 2 - PRODUCTS**

**2.1 FLUSH DOORS**

- A. General:
  - 1. Meet requirements of WDMA I.S.1-A, Extra Heavy Duty.
  - 2. Adhesive: Type II
  - 3. Thickness: 35 mm (1-3/8 inches) unless otherwise shown or specified.
- B. Face Veneer:

1. In accordance with WDMA I.S.1-A.
  2. One species throughout the project unless scheduled or otherwise shown.
  3. For painted finishes: Custom Grade, mill option close grained hardwood, premium or medium density overlay. Do not use Lauan.
  4. Factory sand doors for finishing.
- C. Wood for stops, louvers, muntins and moldings of flush doors required to have transparent finish:
1. Solid Wood of same species as face veneer, except maple may be used on birch doors.
  2. Glazing:
    - a. On non-labeled doors use applied wood stops nailed tight on room side and attached on opposite side with flathead, countersunk wood screws, spaced approximately 125 mm (5 inches) on centers.
    - b. Use stainless steel or dull chrome plated brass screws for exterior doors.
  3. Wood Louvers:
    - a. Door manufacturer's standard product, fabricated of solid wood sections.
    - b. Wood Slats: Not less than 5 mm (3/16 inch) thick.
    - c. Stiles routed out to receive slats.
    - d. Secure louvers in prepared cutouts with wood stops.
- D. Stiles and Rails:
1. Option for wood stiles and rails:
    - a. Composite material having screw withdrawal force greater than minimum performance level value when tested in accordance with WDMA T.M.10.
- E. Fire rated wood doors:
1. Fire Performance Rating:
    - a. "B" label, 1-1/2 hours.
    - b. "C" label, 3/4 hour.
  2. Labels:
    - a. Doors shall conform to the requirements of ASTM E2074, or NFPA 252, and, carry an identifying label from a qualified testing and inspection agency for class of door or opening shown designating fire performance rating.
    - b. Metal labels with raised or incised markings.

3. Performance Criteria for Stiles of doors utilizing standard mortise leaf hinges:
  - a. Hinge Loading: WDMA T.M.8. Average of 10 test samples for Extra Heavy Duty doors.
  - b. Direct screw withdrawal: WDMA T.M.10 for Extra Heavy Duty doors. Average of 10 test samples using a steel, fully threaded #12 wood screw.
  - c. Cycle Slam: 1,000,000 cycles with no loose hinge screws or other visible signs of failure when tested in accordance with WDMA T.M.7.
4. Additional Hardware Reinforcement:
  - a. Provide fire rated doors with hardware reinforcement blocking.
  - b. Size of lock blocks as required to secure hardware specified.
  - c. Top, bottom and intermediate rail blocks shall measure not less than 125 mm (five inches) minimum by full core width.
  - d. Reinforcement blocking in compliance with manufacturer's labeling requirements.
  - e. Mineral material similar to core is not acceptable.
5. Other Core Components: Manufacturer's standard as allowed by the labeling requirements.
6. Provide steel frame approved for use in labeled doors for vision panels.
7. Provide steel astragal on pair of doors.

## 2.2 STILE AND RAIL DOORS

- A. Meeting requirements of WDMA I.S.6A
- B. Ponderosa pine doors of size and design shown.
- C. Grade: Premium.
- D. Door Panels:
  1. Grain of face of panels parallel with longest dimensions of panel.
  2. Flat panels: Veneered composite core, not less than 6 mm (5/8 inch) thick.
  3. Raised panels: Unless otherwise shown, thickness of raised panels not less than the following:
    - a. For 35 mm (1-3/8 inch) and 45 mm (1-3/4 inch) thick doors: 28 mm (1-1/8 inch) thick
    - b. For 57 mm (2-1/4 inch) thick doors: 41 mm (1-5/8 inch) thick

4. Where armor plate is required in connection with paneled doors, provide panels with plywood fillers, glued in place, and finished.

E. Stops and Molds:

1. Solid sticking both sides, of same material as stiles and rails, coped at intersections.
2. Glazed openings applied wood stops nailed on interior side of door.

F. Louvers: Size as shown.

**2.3 IDENTIFICATION MARK:**

- A. On top edge of door.
- B. Either a stamp, brand or other indelible mark, giving manufacturer's name, door's trade name, construction of door, code date of manufacture and quality.
- C. Accompanied by either of the following additional requirements:
  1. An identification mark or a separate certification including name of inspection organization.
  2. Identification of standards for door, including glue type.
  3. Identification of veneer and quality certification.
  4. Identification of preservative treatment for stile and rail doors.

**2.4 SEALING:**

Give top and bottom edge of doors two coats of catalyzed polyurethane or water resistant sealer before sealing in shipping containers.

**PART 3 - EXECUTION**

**3.1 DOOR PREPARATION**

- A. Field, shop or factory preparation: Do not violate the qualified testing and inspection agency label requirements for fire rated doors.
- B. Clearances between Doors and Frames and Floors:
  1. Maximum 3 mm (1/8 inch) clearance at the jambs, heads, and meeting stiles, and a 19 mm (3/4 inch) clearance at bottom, except as otherwise specified.
  2. Maximum clearance at bottom of sound rated doors, light-proofed doors, doors to operating rooms, and doors designated to be fitted with mechanical seal: 10 mm (3/8 inch).
- C. Provide cutouts for special details required and specified.
- D. Rout doors for hardware using templates and location heights specified in Section, 08 71 00 DOOR HARDWARE.
- E. Fit doors to frame, bevel lock edge of doors 3 mm (1/8 inch) for each 50 mm (two inches) of door thickness.

- F. Immediately after fitting and cutting of doors for hardware, seal cut edges of doors with two coats of water resistant sealer.
- G. Finish surfaces, including both faces, top and bottom and edges of the doors smooth to touch.
- H. Apply a steel astragal on the opposite side of active door on pairs of fire rated doors.
- I. Apply a steel astragal to meeting style of active leaf of pair of doors or double egress smoke doors.

**3.2 INSTALLATION OF DOORS APPLICATION OF HARDWARE**

Install doors and hardware as specified in this Section.

**3.3 DOOR PROTECTION**

- A. As door installation is completed, place polyethylene bag or cardboard shipping container over door and tape in place.
- B. Provide protective covering over knobs and handles in addition to covering door.
- C. Maintain covering in good condition until removal is approved by Resident Engineer.

- - - E N D - - -

**SECTION 08 31 13  
ACCESS DOORS AND FRAMES**

**PART 1 - GENERAL**

**1.1 DESCRIPTION:**

Section specifies access doors or panels.

**1.2 RELATED WORK:**

- A. Wire mesh and screen access doors: Section 05 50 00, METAL FABRICATIONS.
- B. Lock Cylinders: Section 08 71 00, DOOR HARDWARE.
- C. Access doors in acoustical ceilings: Section 09 51 00, ACOUSTICAL CEILINGS.
- D. Locations of access doors for duct work cleanouts: Section 23 31 00, HVAC DUCTS AND CASINGS Section 23 37 00, AIR OUTLETS AND INLETS.

**1.3 SUBMITTALS:**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Shop Drawings: Access doors, each type, showing construction, location and installation details.
- C. Manufacturer's Literature and Data: Access doors, each type.

**1.4 APPLICABLE PUBLICATIONS**

- A. Publications listed below form a part of this specification to extent referenced. Publications are referenced in the text by basic designation only.
- B. American Society for Testing and Materials (ASTM):
  - A167-99(R-2004).....Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet and Strip
  - A1008-08.....Steel Sheet, Cold-Rolled, Carbon, Structural, High Strength Low-Alloy
- C. American Welding Society (AWS):
  - D1.3-98 (R2005).....Structural Welding Code Sheet Steel
- D. National Fire Protection Association (NFPA):
  - 80-07.....Fire Doors and Windows
- E. The National Association of Architectural Metal Manufacturers (NAAMM):
  - AMP 500 Series.....Metal Finishes Manual
- F. Underwriters Laboratories, Inc. (UL):
  - 2009.....Fire Resistance Directory

**2.1 FABRICATION, GENERAL**

- A. Fabricate components to be straight, square, flat and in same plane where required.
  - 1. Slightly round exposed edges and without burrs, snags and sharp edges.
  - 2. Exposed welds continuous and ground smooth.
  - 3. Weld in accordance with AWS D1.3.
- B. Number of locks and non-continuous hinges as required to maintain alignment of panel with frame. For fire rated doors, use hinges and locks as required by fire test.
- C. Provide anchors or make provisions in frame for anchoring to adjacent construction. Provide size, number and location of anchors on four sides to secure access door in opening. Provide anchors as required by fire test.

**2.2 ACCESS DOORS, FIRE RATED:**

- A. Shall meet requirements for "B" label 1-1/2 hours with maximum temperature rise of 120 degree C (250 degrees F).
- B. Comply with NFPA 80 and have Underwriters Laboratories Inc., or other nationally recognized laboratory label for Class B opening.
- C. Door Panel: Form of 0.9 mm (0.0359 inch) thick steel sheet, insulated sandwich type construction.
- D. Frame: Form of 1.5 mm (0.0598 inch) thick steel sheet of depth and configuration to suit material and type of construction where installed. Provide frame flange at perimeter where installed in concrete masonry or gypsum board openings.
  - 1. Weld exposed joints in flange and grind smooth.
  - 2. Provide frame flange at perimeter where installed in concrete masonry or gypsum board.
- E. Automatic Closing Device: Provide automatic closing device for door.
- F. Hinge: Continuous steel hinge with stainless steel pin.
- G. Lock:
  - 1. Self-latching, with provision for fitting flush a standard screw-in type lock cylinder. Lock cylinder specified in Section 08 71 00, DOOR HARDWARE.
  - 2. Provide latch release device operable from inside of door. Mortise case in door.

**2.3 ACCESS DOORS, FLUSH PANEL:**

A. Door Panel:

1. Form of 1.9 mm (0.0747 inch) thick steel sheet.
2. Reinforce to maintain flat surface.

B. Frame:

1. Form of 1.5 mm (0.0598 inch) thick steel sheet of depth and configuration to suit material and type of construction where installed.
2. Provide surface mounted units having frame flange at perimeter where installed in concrete, masonry, or gypsum board construction.
3. Weld exposed joints in flange and grind smooth.

C. Hinge:

1. Concealed spring hinge to allow panel to open 175 degrees.
2. Provide removable hinge pin to allow removal of panel from frame.

D. Lock:

1. Flush, screwdriver operated cam lock.

**2.4 ACCESS DOOR, RECESSED PANEL:**

A. Door Panel:

1. Form of 1.2 mm (0.0478 inch) thick steel sheet to form a 25 mm (one inch) deep recessed pan to accommodate the installation of acoustical units or other materials where shown in walls and ceiling.
2. Reinforce as required to prevent sagging.

B. Frame:

1. Form of 1.5 mm (0.0598 inch) thick steel sheet of depth and configuration to suit installation in suspension system of ceiling or wall framing.
2. Extend sides of frame to protect edge of acoustical units when panel is in open position.
3. Provide shims, bushings, clips and other devices necessary for installation.

C. Hinge: Continuous steel hinge with stainless steel pin or concealed hinge.

D. Lock:

1. Flush screwdriver operated cam lock.
2. Provide sleeve of plastic or stainless steel grommet to protect hole made in acoustical unit for screwdriver access to lock.

**2.5 FINISH:**

- A. Provide in accordance with NAAMM AMP 500 series on exposed surfaces.
- B. Steel Surfaces: Baked-on prime coat over a protective phosphate coating.
- C. Stainless Steel: No. 4 for exposed surfaces.

**2.6 SIZE:**

Minimum 600 mm (24 inches) square door unless otherwise shown or required to suit opening in suspension system of ceiling.

**PART 3 - EXECUTION**

**3.1 LOCATION:**

- A. Provide access panels or doors wherever any valves, traps, dampers, cleanouts, and other control items of mechanical, electrical and conveyor work are concealed in wall or partition, or are above ceiling of gypsum board or plaster.
- B. Use fire rated doors in fire rated partitions and ceilings.
- C. Use flush panels in partitions and gypsum board or plaster ceilings, except lay-in acoustical panel ceilings or upward access acoustical tile ceilings.

**3.2 INSTALLATION, GENERAL:**

- A. Install access doors in openings to have sides vertical in wall installations, and parallel to ceiling suspension grid or side walls when installed in ceiling.
- B. Set frames so that edge of frames without flanges will finish flush with surrounding finish surfaces.
- C. Set frames with flanges to overlap opening and so that face will be uniformly spaced from the finish surface.
- D. Set recessed panel access doors recessed so that face of surrounding materials will finish on the same plane, when finish in door is installed.

**3.3 ANCHORAGE:**

- A. Secure frames to adjacent construction using anchors attached to frames or by use of bolts or screws through the frame members.
- B. Type, size and number of anchoring device suitable for the material surrounding the opening, maintain alignment, and resist displacement during normal use of access door.
- C. Anchors for fire rated access doors shall meet requirements of applicable fire test.


Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

**3.4 ADJUSTMENT:**

- A. Adjust hardware so that door panel will open freely.
- B. Adjust door when closed so door panel is centered in the frame.

- - - E N D - - -



**SECTION 08 36 13**  
**SECTIONAL DOORS**

**PART 1 - GENERAL**

**1.1 DESCRIPTION:**

This section specifies electrically operated thermal insulated sectional overhead steel doors.

**1.2 RELATED WORK:**

- B. Lock cylinders for cylindrical locks: Section 08 71 00, DOOR HARDWARE.
- D. Electrical Installation: Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, Section 28 05 11, REQUIREMENTS FOR ELECTRONIC SAFETY AND SECURITY INSTALLATIONS.

**1.3 MANUFACTURER'S AND INSTALLER'S QUALIFICATIONS:**

- A. Manufacturer's regularly engaged in manufacturing items of type specified.
- B. Installers under direct supervision of manufacturer's representative or trained personnel.

**1.4 SUBMITTALS:**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Shop Drawings:
  - 1. Details of construction, accessories and hardware, electrical and mechanical items, supporting brackets for motors, location, and ratings of motors, and safety devices.
  - 2. Wiring diagrams for motors and controls, including wiring diagram for door, showing electrical interlock for motor with manually operated dead lock.
- C. Manufacturer's Literature and Data:
  - 1. Brochures or catalog cuts.
  - 2. Manufacturer's installation procedures and instructions.
  - 3. Maintenance instructions, parts list.
- D. Certificates:
  - 1. Attesting door, anchors and hardware will withstand the horizontal loads specified.
  - 2. Attesting door complies with thermal performance, air infiltration, and water infiltration requirements.

**1.5 APPLICABLE PUBLICATIONS:**

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.
- B. American Society for Testing and Materials (ASTM):
- A36/A36M-08.....Structural Steel
  - A227/A227M-06.....Steel Wire, Cold-Drawn for Mechanical Springs
  - A229/229M-99(R2005).....Steel Wire, Oil-Tempered for Mechanical Springs
  - A653-08.....Steel Sheet, Zinc-Coated (Galvanized) or Zinc Iron Alloy Coated (Galvanized) by the Hot Dip Process
  - C1036-06.....Flat Glass
  - E84-09.....Surface Burning Characteristics of Building Materials
  - E283-04.....Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Difference Across the Specimen
  - E330-02.....Structural Performance of Exterior Windows, Curtain Walls, and Doors by the Uniform Static Air Pressure Difference.
  - E331-00 (R2009).....Water Penetration of Exterior Windows, Curtain Walls, and Doors by the Uniform Static Air Pressure Difference.
- C. American National Standards Institute and Door and Access Systems Manufacturers Association (ANSI/DASMA):
- 102-04.....Sectional Overhead Type Doors.
- D. National Electrical Manufacturer's Association (NEMA):
- ICS 2-00 (R2005).....Industrial Control and Systems: Controllers, Contactors, and Overload Relays
  - MG 1-03 (R2004).....Motors and Generators
- E. National Fire Protection Association (NFPA):
- 70-08.....National Electrical Code
- F. National Association of Architectural Metal Manufacturers (NAAMM):
- AMP 501-88.....Metal Finishes Manual

## **PART 2 - PRODUCTS**

### **2.1 MATERIALS:**

- A. Steel: ASTM A653 for forming operations. ASTM A36 for structural sections.
- B. Hard Drawn Spring wire: ASTM A227.
- C. Oil Tempered Spring wire: ASTM A229.
- D. Glass: ASTM C1036
  - 1. Clear Glass: Type 1, Class 1, Quality q5, 6 mm (1/4 inch) thick.
  - 2. Fabricated into sealed insulating glass 25 mm (one inch) thick.
- E. Weather-strips, Gaskets, and Thermal Breaks:
  - 1. Neoprene, EPDM, PVC, silicone rubber, or other low conductance material.
  - 2. Standard with door manufacturer.

### **2.2 DESIGN REQUIREMENTS:**

- A. Wind Load: Design to withstand a horizontal or wind pressure of 960 Pa (20 pounds per square foot) of door area without damage when tested in accordance with ASTM E330.
- B. Thermal Performance: Maximum U value of 0.14 for door when tested in accordance with ASTM C236.
- C. Air Infiltration: Maximum of 0.10 cfm at 24 Km (15 miles per hour) wind speed per foot of crack between door sections and door perimeter opening when tested in accordance with ASTM E283.
- D. Water Infiltration: No infiltration when tested in accordance with ASTM E331.
- E. Comply with ANSI/NAGDM 102, for an Industrial door and specified design criteria, inside face mounted with tracks at jambs set back a sufficient distance to provide a clear opening when door is in open position.
- F. Operation-Cycle Requirements: Door components and operators to operate for not less than 10,000 cycles.

### **2.3 FABRICATION:**

- A. Steel Door Sections:
  - 1. Formed of hot-dipped galvanized steel.
  - 2. Meeting rails: interlocking joints with thermal breaks separating face sheets formed to provide weathertight closure and alignment for full width of door.

3. Height of sections: Not to exceed 600 mm (24 inches) may be varied to suit door height.
4. Install glazing panels where indicated using rubber thermal break gaskets standard with door manufacturer.
5. Insulation shall have a flame spread rating of not more than 25 and a smoke development factor of not more than 50 when tested in accordance with ASTM E 84.
6. Reinforced for hardware anchorage with not less than 10 gage galvanized steel.

B. Tracks:

1. Manufacturer's standard formed of galvanized steel.
2. Minimum of 14 gage for 50 mm (2 inch) tracks and 12 gage for 75 mm (3 inch) tracks.
3. Vertical tracks fabricated with adjustable brackets for mounting at incline to continuous steel angle wall bracket.
4. Horizontal track: Reinforce with continuous steel angle anchored to vertical steel angle wall bracket and to ceiling angle supports. Use vertical and cross or diagonal braced to obtain rigid installation of horizontal track.
5. Use not less than 13 gage galvanized steel angles.

C. Hardware:

1. Manufacturers standard hinges, brackets, rollers, locking devices and other hardware required for a complete installation.
2. Hinges and roller brackets minimum of 13 gage galvanized steel.
3. Use rollers with ball bearings and case hardened races.
4. Positive locking device to receive cylinder lock, specified in Section 08 71 00, DOOR HARDWARE, with interlocking switch to motor operator.

**2.4 ELECTRIC MOTOR OPERATORS:**

- A. Complete with electric motor, machine cut reduction gears, steel chain and sprockets, magnetic brake, overload protection, brackets, push button controls, limit switches, magnetic reversing contactor, and other accessories necessary for proper operation, including emergency manual operator.
- B. Design:
  1. Design the operator for motor removal without disturbing the limit-switch timing and without affecting the emergency manual operators.

2. Make provision for emergency manual operation of door by chain-gear mechanism in case of electrical failure.
3. Arrange the emergency manual operating mechanism to immediately be put into and out of operation from the floor with a mechanical device to disconnect the motor from the operating mechanism when the emergency manual operating mechanism is engaged and not affect the timing of the limit switches.
4. Provide interlock with motor to prevent motor from operating when manual locks are activated.

C. Motors:

1. Motor conform to NEMA MG 1, maximum operation 3600 rpm.
2. Suitable for operation on current specified in Division 26, ELECTRICAL.
3. Use high starting torque, reversible type, of sufficient horsepower and torque output to move the door in either direction from door position, and produce door travel speed range of 0.20 to 0.30 m per second (8 to 12 inches per second), without exceeding the rated capacity.
4. Single-phase motors shall not have commutation or more than one starting contact.
5. Motor Enclosures: Drip proof type or NEMA TENV type.

D. Controls:

1. Control equipment: NEMA 2.
2. Control enclosures: NEMA ICS 6, Type 12 or Type 4, except that contractor enclosures may be Type 1. Use weatherproof corrosion-resistant covers for exterior locations.
3. At door motors use an enclosed, across-the-line type, magnetic reversing contactor, thermal overload protection, solenoid operated brake, limit switches, and remote control switches at locations indicated.
4. Control switches:
  - a. Three push button type on interior, unless noted to be key activated.
  - b. Buttons marked, OPEN, CLOSE and STOP.
  - c. The OPEN and STOP buttons: Momentary pressure or contact type.
  - d. The CLOSE button: Constant pressure type.

- e. Use key activated switch on exterior requiring constant pressure to operate.
  - f. Limit switches: Manufacturers standard, position of switches readily adjustable.
5. Operation:
- a. Open door upon activation of Open switch.
  - b. Close door only when constant pressure applied.
  - c. When the door is in motion, and the STOP button is pressed, door shall stop instantly and remain in the stop position; from stop position, door may be operated in either direction by OPEN or CLOSE button.
  - d. Limit switches automatically stop doors at their fully open and closed positions.
6. Push buttons full-guarded to prevent accidental operation.
7. Transformer:
- a. Use a control transformer in power circuits to reduce the voltage on control circuits to 120 volts or less.
  - b. Conform to NEMA ST 20.
8. Electrical Components: Conform to NFPA 70.
9. Safety Device:
- a. Bottom door edge weather-strip safety device to immediately stop and reverse the door closing to full open position upon contact with an obstruction. Door is to open upon failure of device, component of device or component of control system.
  - b. The door closing circuit shall be electrically locked out and door to remain capable of manual operation until the failure or damage has been corrected.
  - c. Do not use as a limit switch.
  - d. Safety device connecting cable to motor to be flexible type SO cable with spring loaded automatic take up reel or equivalent device, as required for proper operation of the doors.

## 2.5 FINISHES:

### A. Steel:

- 1. Comply with NAAMM's Metal Finishes Manual.
- 2. Clean surfaces free of scale, rust, oil and grease.
- 3. Non-galvanized steel: Pretreatment to assure maximum paint adherence.

4. Galvanized steel: Apply phosphate treatment.
5. Apply shop prime coat of corrosion inhibitive paint on exposed surfaces after fabrication.
6. Apply finish paint on color scheduled when specified in Section 09 06 00, SCHEDULE FOR FINISHES.
7. Do not paint track, rollers, hinges, or locks.

**PART 3 - EXECUTION**

**3.1 INSTALLATION:**

- A. Install in accordance with approved shop drawings and manufacturer's instructions. For electrical work, see Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS Section 28 05 11, REQUIREMENTS FOR ELECTRONIC SAFETY AND SECURITY INSTALLATIONS.
- B. Locate anchors and inserts for tracks, brackets, motors, switches, hardware, and other accessories accurately.
- C. Securely attach tracks to adjoining construction with not less than 9 mm (3/8 inch) diameter bolts, spaced near each end and not over 600 mm (24 inches) apart.
- D. Locate control switches where shown at least five feet above the floor line so that the operator will have complete visibility of the door.
- E. Lubricate, properly adjust and demonstrate door to operate freely.
- F. Upon completion, door openings shall be weathertight and doors shall be free from warp, twists, or distortion.

**3.2 REPAIR:**

- A. Repair zinc-coated surfaces both bare and painted, by the application of galvanizing repair compound.
- B. Spot prime and apply finish paint to all repairs.

- - - E N D - - -

**SECTION 085200**

**ALUMINUM CLAD WOOD WINDOWS**

**PART 1 - GENERAL**

**1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

**1.2 SUMMARY**

- A. Section includes aluminum-clad wood windows.

**1.3 PREINSTALLATION MEETINGS**

- A. Preinstallation Conference: Conduct conference at **Project site**.
  - 1. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 2. Review, discuss, and coordinate the interrelationship of wood windows with other exterior wall components. Include provisions for anchoring, flashing, weeping, sealing perimeters, and protecting finishes.
  - 3. Review and discuss the sequence of work required to construct a watertight and weathertight exterior building envelope.
  - 4. Inspect and discuss the condition of substrate and other preparatory work performed by other trades.

**1.4 ACTION SUBMITTALS**

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, glazing and fabrication methods, dimensions of individual components and profiles, hardware, and finishes for wood windows.
- B. Shop Drawings: Include plans, elevations, sections, hardware, accessories, insect screens, operational clearances, and details of installation, including anchor, flashing, and sealant installation.
- C. Samples: For each exposed product and for each color specified, 2 by 4 inches (50 by 100 mm) in size.
- D. Samples for Initial Selection: For units with factory-applied color finishes.
  - 1. Include similar Samples of hardware and accessories involving color selection.

E. Samples for Verification: For wood windows and components required, prepared on Samples of size indicated below:

1. Exposed Finishes: 2 by 4 inches (50 by 100 mm).
2. Exposed Hardware: Full-size units.

F. Product Schedule: For wood windows. Use same designations indicated on Drawings.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For manufacturer and Installer.
- B. Product Test Reports: For each type of wood window, for tests performed by a qualified testing agency, provide WDMA Hallmark Certified written test reports showing conformance to the current AAMA 101 specified standards.
- C. Field quality-control reports.
- D. Sample Warranties: For manufacturer's warranties.

#### 1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A manufacturer capable of fabricating wood windows that meet or exceed performance requirements indicated and of documenting this performance by test reports, and calculations
- B. Installer Qualifications: An installer acceptable to wood window manufacturer for installation of units required for this Project. Must have a minimum of five years window installation experience

#### 1.7 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to repair or replace wood windows that fail in materials or workmanship within specified warranty period.
  1. Failures include, but are not limited to, the following:
    - a. Failure to meet performance requirements.
    - b. Structural failures including excessive deflection, water leakage, and air infiltration.
    - c. Faulty operation of movable sash and hardware.
    - d. Deterioration of materials and finishes beyond normal weathering.
    - e. Failure of insulating glass.
  2. Warranty Period:
    - a. Window: 10 years from date of Substantial Completion.
    - b. Glazing Units: 20 years from date of Substantial Completion.
    - c. Aluminum-Cladding Finish: 20 years from date of Substantial Completion.

**PART 2 - PRODUCTS**

**2.1 MANUFACTURERS**

- A. Basis of design is Marvin Windows and Doors - Warroad, MN
  - 1. Model: Clad Ultimate Fixed Picture Window or Equal
- B. Other manufacturers will be considered provided they meet or exceed all specifications. Requests for products to be considered as an approved equal must be submitted to the COR in writing, a minimum of 10 days prior to bid date.
- C. Source Limitations: Obtain wood windows from single source from single manufacturer.

**2.2 WINDOW PERFORMANCE REQUIREMENTS**

- A. Product Standard: Comply with AAMA/WDMA/CSA 101/I.S.2/A440-08 for definitions and minimum standards of performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.
  - 1. Window Certification: WDMA Hallmark Certified with label attached to each window.
  - 2. Windows must be tested to AAMA Minimum Gateway Test Size.  
Downsized test units will not be accepted
- B. Casement Window Minimum Performance Grade: 50
  - 1. Air leakage shall not exceed the following when tested at 6.24 according to ASTM E 283-04, 0.05 cfm per square foot of frame.
  - 2. No water penetration shall occur when units are tested at the following pressure according to ASTM E 547-00 and ASTM E 331-00: 7.5 psf.
  - 3. Window assembly shall withstand the following positive or negative uniform static air pressure difference without damage when tested according to ASTM E 330-02 Uniform Load Structural: C-CW50 at 75 psf.
  - 4. Window assembly shall not deflect in excess of L/175 when tested according to ASTM E 330-02 Uniform Load Deflection: C-CW50 at 50 psf.
- C. Thermal Transmittance: NFRC 100 maximum whole-window U-factor of 0.32 Btu/sq. ft. x h x deg F (1.83 W/sq. m x K)
- D. Forced Entry Resistance per ASTM F 588: Type A; Grade 40.

**2.3 WOOD WINDOWS**

- A. Casement Picture Windows

- B. Casement AAMA/WDMA/CSA 101/I.S.2/A440 includes requirements for wood, cladding materials, and other materials and window components. If more stringent requirements apply, insert them in this article.
- C. Frames and Sashes: Fine-grained wood lumber complying with AAMA/WDMA/CSA 101/I.S.2/A440-08; kiln dried to a moisture content of not more than 12 percent at time of fabrication; free of visible finger joints, blue stain, knots, pitch pockets, and surface checks larger than 1/32 inch (0.8 mm) deep by 2 inches (51 mm) wide; water-repellent preservative treated complying with WDMA I.S.4.
1. Casement Window Frame Thickness: 1 3/16 inches (30mm).
  2. Casement Window Frame Depth: 4 9/16 (116mm)
  3. Casement Window Frame exterior clad with minimum 0.050 inch (1.3mm) thick extruded aluminum.
  4. Casement Window Sash thickness: 1 5/8 inches (41mm) with 3/4 inch (19mm) insulated glass. For 1 inch (25mm) insulated glass sash thickness is 1 7/8 inch (48mm).
  5. Casement Window Sash exterior clad with minimum 0.050 inch (1.3mm) thick extruded aluminum.
- D. Exterior Finish: Aluminum-clad
1. Aluminum Finish: Manufacturer's standard fluoropolymer two-coat system with fluoropolymer color topcoat containing not less than 70 percent polyvinylidene fluoride resin by weight and complying with AAMA 2605-05
  2. Color: Ebony
- E. Interior Finish: Factory Primed. Paint in field per Division 09 and drawings.
- F. Insulating-Glass Units: ASTM E 2190, certified through IGCC as complying with requirements of IGCC.
1. Glass: ASTM C 1036, Type 1, Class 1, q3. Double Strength
    - a. Tint: Clear
  2. Lites: As shown on Drawings.
  3. Filling: Fill space between glass lites with argon.
  4. Low-E Coating: LoE<sup>2</sup>, Two layers sputtered on second surface
- G. Glazing System: Manufacturer's standard factory-glazing system that produces weathertight seal.
- H. Weather Stripping: Weather stripping at frame is a hollow foamed material bent around 90 degree corner to allow for seamless corner

- joints beige in color. Sash weather strip is bulb shaped glass filled material, available in beige, white or black.
- I. Fasteners: Noncorrosive and compatible with window members, trim, hardware, anchors, and other components.
1. Exposed Fasteners: Do not use exposed fasteners to the greatest extent possible. For application of hardware, use fasteners that match finish hardware being fastened.
- H. SIMULATED DIVIDED LITES (SDL)
1. 1-1/8 inch (22 mm) wide with internal spacer bars
- a. Exterior muntins: 0.055 inch (1.4 mm) thick extruded aluminum muntins adhered to glass.
- b. Interior muntins: Pine. muntins adhered to glass
- c. Pattern: Rectangular; as per elevation drawings.
- d. Finish: Match sash finish.
- J. EXTENSION JAMB
1. Field applied as required. Refer to Drawings
2. Finish: Match interior frame finish.

### **PART 3 - EXECUTION**

#### **3.1 EXAMINATION**

- A. Verification of Conditions: Before Installation, verify openings are plumb, square, and of proper dimension as required in Section 01 71 00. Report frame defects or unsuitable conditions to the General Contractor before proceeding.
- B. Acceptance of Conditions: Beginning of Installation confirms acceptance of existing conditions.

#### **3.2 INSTALLATION**

- A. Comply with Section 01 73 00.
- B. Assemble and install window unit/s according to manufacturer's instructions and reviewed shop drawings.
- C. Install sealant and related backing materials at perimeter of unit or assembly in accordance with Section 07 92 00 Joint Sealants. Do not use expansive foam sealant.
- D. Install accessory items as required.
- E. Use finish nails to apply wood trim and mouldings.

#### **3.3 CLEANING**

- A. Remove visible labels and adhesive residue according to manufacturer's instructions.

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

- B. Leave windows and glass in a clean condition. Final cleaning as required in Section 01 74 00.

**3.4 PROTECTING INSTALLED CONSTRUCTION**

- A. Comply with Section 01 76 00.
- B. Protect windows from damage by chemicals, solvents, paint, or other construction operations that may cause damage.

END OF SECTION

**SECTION 08 71 00**  
**DOOR HARDWARE**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

Door hardware and related items necessary for complete installation and operation of doors.

**1.2 RELATED WORK**

- A. Caulking: Section 07 92 00 JOINT SEALANTS.
- B. Application of Hardware: Section 08 14 00, WOOD DOORS Section 08 11 13, HOLLOW METAL DOORS AND FRAMES
- C. Finishes: Section 09 06 00, SCHEDULE FOR FINISHES.
- D. Painting: Section 09 91 00, PAINTING.
- E. Card Readers: Section 28 13 11, PHYSICAL ACCESS CONTROL SYSTEMS.

**1.3 GENERAL**

- A. All hardware shall comply with UFAS, (Uniform Federal Accessible Standards) unless specified otherwise.
- B. Hardware for Labeled Fire Doors and Exit Doors: Conform to requirements of NFPA 80 for labeled fire doors and to NFPA 101 for exit doors, as well as to other requirements specified. Provide hardware listed by UL, except where heavier materials, large size, or better grades are specified herein under paragraph HARDWARE SETS. In lieu of UL labeling and listing, test reports from a nationally recognized testing agency may be submitted showing that hardware has been tested in accordance with UL test methods and that it conforms to NFPA requirements.
- C. Deadlocks specified for psychiatric area doors are not required to have "UL" label.
- D. Hardware for application on metal and wood doors and frames shall be made to standard templates. Furnish templates to the fabricator of these items in sufficient time so as not to delay the construction.
- E. The following items shall be of the same manufacturer, if possible, except as otherwise specified:
  - 1. Mortise locksets.
  - 2. Hinges for hollow metal and wood doors.
  - 3. Surface applied overhead door closers.
  - 4. Exit devices.

**1.4 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

B. Hardware Schedule: Prepare and submit hardware schedule in the following form:

Hardware Item	Quantity	Size	Reference Publication Type No.	Finish	Mfr. Name and Catalog No.	Key Control Symbols	UL Mark (if fire rated and listed)	ANSI/BHMA Finish Designation

C. Samples and Manufacturers' Literature:

1. Samples: All hardware items (proposed for the project) that have not been previously approved by Builders Hardware Manufacturers Association shall be submitted for approval. Tag and mark all items with manufacturer's name, catalog number and project number.
2. Samples are not required for hardware listed in the specifications by manufacturer's catalog number, if the contractor proposes to use the manufacturer's product specified.

D. Certificate of Compliance and Test Reports: Submit certificates that hardware conforms to the requirements specified herein. Certificates shall be accompanied by copies of reports as referenced. The testing shall have been conducted either in the manufacturer's plant and certified by an independent testing laboratory or conducted in an independent laboratory, within four years of submittal of reports for approval.

**1.5 DELIVERY AND MARKING**

Deliver items of hardware to job site in their original containers, complete with necessary appurtenances including screws, keys, and instructions. Tag one of each different item of hardware and deliver to RE/COTR for reference purposes. Tag shall identify items by Project Specification number and manufacturer's catalog number. These items shall remain on file in RE/COTR's office until all other similar items have been installed in project, at which time the RE/COTR will deliver items on file to Contractor for installation in predetermined locations on the project.

### 1.6 INSTRUCTIONS

- A. Hardware Set Symbols on Drawings: Except for protective plates, door stops, mutes, thresholds and the like specified herein, hardware requirements for each door are indicated on drawings by symbols. Symbols for hardware sets consist of letters "HW" followed by a number. Each number designates a set of hardware items applicable to a door type.
- B. Manufacturers' Catalog Number References: Where manufacturers' products are specified herein, products of other manufacturers which are considered equivalent to those specified may be used. Manufacturers whose products are specified are identified by abbreviations as follows:

Adams-Rite	Adams Rite Mfg. Co.	Glendale, CA
Glynn Johnson	Glynn Johnson Co.	Chicago, IL
LCN	LCN Closers	Princeton, IL
Firemark	Rixon-Firemark Co.	Chicago, IL
Hager	Hager Hinge Company	Saint Louis, MO
Stanley	The Stanley Works	New Britain, CT
Trimco	Triangle Brass Mfg. Co.	Los Angeles, CA
Unican	Simplex Security Systems	Collinsville, CT
Von Duprin	Von Duprin Hardware Co.	Indianapolis, IN
Zero	Zero Weather Stripping Co.	New York, NY

- C. Keying: All cylinders shall be keyed into existing Master Key System. Provide removable core cylinders that are removable only with a special key or tool without disassembly of knob or lockset. Cylinders shall be BEST 6 or 7 pin type - *the contractor shall confirm with the VA COR actual pin type prior to submitting shop drawings and provide same to work with the cemetery's keying system.* Keying information shall be furnished at a later date by the RE/COTR.
- D. Keying: A new Great Grandmaster key shall be established for this project. The key system shall be removable core type as previously described. The manufacturer shall furnish code pattern listings so keys may be reproduced by code. The manufacturer shall design the new key system with the capacity to relock the existing station and also provide for 25 percent expansion capability beyond this requirement.

Submit a keying chart for approval showing proposed keying layout and listing expansion capacity.

1. Keying information will be furnished to the Contractor by the RE/COTR.
2. Supply information regarding key control of cylinder locks to manufacturers of equipment having cylinder type locks. Notify RE/COTR immediately when and to whom keys or keying information is supplied. Return all such keys to the RE/COTR.

#### 1.7 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. In text, hardware items are referred to by series, types, etc., listed in such specifications and standards, except as otherwise specified.
- B. American Society for Testing and Materials (ASTM):  
F883-04.....Padlocks
- C. American National Standards Institute/Builders Hardware Manufacturers Association (ANSI/BHMA):  
A156.1-06.....Butts and Hinges  
A156.2-03.....Bored and Pre-assembled Locks and Latches  
A156.3-08.....Exit Devices  
A156.4-08.....Door Controls (Closers)  
A156.5-01.....Auxiliary Locks and Associated Products  
A156.6-06.....Architectural Door Trim  
A156.8-05.....Door Controls-Overhead Stops and Holders  
A156.13-05.....Mortise Locks and Latches  
A156.15-06.....Release Devices-Closer Holder, Electromagnetic  
and Electromechanical  
A156.16-02.....American National Standard for Auxiliary  
Hardware  
A156.18-06.....Materials and Finishes  
A156.21-06.....Thresholds  
A156.22-05.....Door Gasketing and Edge Seal Systems  
A156.23-04.....Electromagnetic Locks  
A156.24-03.....Delayed Egress Locking Systems  
A156.26-06.....Continuous Hinges  
A156.31-07 .....Electric Strikes and Frame Mounted Actuators

A250.8-03.....Standard Steel Doors and Frames

D. National Fire Protection Association (NFPA):

80-07.....Fire Doors and Fire Windows

101-09.....Life Safety Code

E. Underwriters Laboratories, Inc. (UL):

Building Materials Directory (2009)

## **PART 2 - PRODUCTS**

### **2.1 BUTT HINGES**

A. ANSI A156.1. The following types of butt hinges shall be used for the types of doors listed, except where otherwise specified:

1. Exterior Doors: Type A2112 for doors 900 mm (3 feet) wide or less and Type A2111 for doors over 900 mm (3 feet) wide. Hinges for exterior doors shall have non-removable pins.
2. Interior Doors: Type 8112 for doors 900 mm (3 feet) wide or less and Type A8111 for doors over 900 mm (3 feet) wide.

B. See Articles "MISCELLANEOUS HARDWARE" and "HARDWARE SETS" for pivots and hinges other than butts specified above and continuous hinges specified below.

### **2.2 CONTINUOUS HINGES**

A. Continuous, Gear-Type Hinges: Extruded-aluminum, pinless, geared hinge leaves; joined by a continuous extruded-aluminum channel cap; with concealed, self-lubricating thrust bearings.

1. Manufacturers:

- a. Bommer Industries, Inc.
- b. Hager Companies.
- c. McKinney Products Company; an ASSA ABLOY Group company.
- d. Pemko Manufacturing Co.
- e. Select Products Limited.
- f. Zero International.

### **2.3 DOOR CLOSING DEVICES**

Closing devices shall be products of one manufacturer for each type specified.

### **2.4 OVERHEAD CLOSERS**

A. Conform to ANSI A156.4, Grade 1.

B. Closers shall conform to the following:

1. The closer shall have 50 percent adjustable closing force over minimum value for that closer and have adjustable hydraulic back check effective between 60 degrees and 85 degrees of door opening.
2. Where specified, closer shall have hold-open feature.
3. Size Requirements: Size closers in accordance with manufacturer's recommendations or provide multi-size closers, sizes 1 through 6.
4. Material of closer shall be cast aluminum.
5. Arm and brackets for closers shall be steel or malleable iron.
6. Closers shall have full size cover.
7. Closers shall have adjustable hydraulic back-check and separate valves for closing and latching speed.

## 2.5 DOOR STOPS

- A. Conform to ANSI A156.16.
- B. Provide door stops wherever an opened door or any item of hardware thereon would strike a wall, column, equipment or other parts of building construction. For concrete, masonry or quarry tile construction, use lead expansion shields for mounting door stops.
- C. Where cylindrical locks with turn pieces or pushbuttons occur, equip wall bumpers Type L02251 (rubber pads having concave face) to receive turn piece or button.
- D. Substitute floor stops Type L02141 or L02161 as appropriate, when wall bumpers would not provide an effective door stop.
- E. Where drywall partitions occur, use floor stops, Type L02141 or L02161.
- F. Provide stop Type L02011 or L02181, as applicable for exterior doors.
- G. Provide appropriate roller bumper for each set of doors (except where closet doors occur) where two doors would interfere with each other in swinging.
- H. Provide appropriate door mounted stop on doors in individual toilets where floor or wall mounted stops cannot be used.

## 2.6 FLOOR DOOR HOLDERS

Conform to ANSI Standard A156.16. Provide extension strikes for Types L01301 and L01311 holders where necessary.

## 2.7 LOCKS AND LATCHES

- A. Conform to ANSI A156.2. Locks and latches for doors 45 mm (1-3/4 inch) thick or over shall have beveled fronts. Lock cylinders shall have not less than six pins or seven pins - the contractor shall confirm with the VA COR actual pin type prior to submitting shop drawings and

provide same to work with the cemetery's keying system. Cylinders for all locksets shall be by BEST and removable core type. Cylinders shall be furnished with construction removable cores and construction master keys. Cylinder shall be removable by special key or tool. Construct all cores so that they will be interchangeable into the core housings of all mortise locks, rim locks, cylindrical locks, and any other type lock included in the Great Grand Master Key System. Disassembly of lever or lockset shall not be required to remove core from lockset. All locksets or latches on double doors with fire label shall have latch bolt with 19 mm (3/4 inch) throw. Provide temporary keying device or construction core of allow opening and closing during construction and prior to the installation of final cores.

- B. In addition to above requirements, locks and latches shall comply with following requirements:
1. Mortise Lock and Latch Sets: Conform to ANSI/BHMA A156.13. Mortise locksets shall be series 1000, minimum Grade 2. All locksets and latchsets, except on designated doors in Psychiatric (Mental Health) areas, shall have lever handles similar to Falcon S-lever Design. Lever handle shall be fabricated from wrought stainless steel. No substitute lever design or material shall be accepted. All locks and latchsets shall be furnished with curved lip strike and wrought box. Lock function F02 shall be furnished with key plates similar to Russwin's No. A70. All lock cases installed on lead lined doors shall be lead lined before applying final hardware finish. Furnish armored fronts for all mortise locks.
  2. Cylindrical Lock and Latch Sets: levers shall meet ADA (Americans with Disabilities Act) requirements. Cylindrical locksets shall be series 4000 Grade I. Knobs for series 4000 lock and latch sets shall have 57 mm (2-1/4 inch) diameters. Where two turn pieces are specified for lock F76, turn piece on inside knob shall lock and unlock inside knob, and turn piece on outside knob shall unlock outside knob when inside knob is in the locked position. (This function is intended to allow emergency entry into these rooms without an emergency key or any special tool.)
  3. Auxiliary locks shall be as specified under hardware sets and conform to ANSI A156.5.

## 2.8 KEYS

- A. Stamp all keys with change number and key set symbol. Furnish keys in quantities as follows:

Locks/Keys	Quantity
Cylinder locks	2 keys each
Cylinder lock change key blanks	10 each different key way
Master-keyed sets	6 keys each
Grand Master sets	6 keys each
Great Grand Master set	5 keys
Control key	1 key

## 2.9 ARMOR PLATES, COMBINATION KICK-MOP PLATES AND DOOR EDGING

- A. Conform to ANSI Standard A156.6.
- B. Provide protective plates and door edging as specified below:
1. Kick-mop plates and armor plates plastic or metal, Type J100 series, color as required. When wood grain plastic plates are specified in Section 09 06 00, SCHEDULE FOR FINISHES, grain plates shall run in same direction as grain of face veneer of wood doors.
  2. Provide kick-mop plates for both sides of each door, except where noted as not required. Kick-mop plates shall be 200 mm (8 inches) high. On push side of doors where jamb stop extends to floor, make combination kick-mop plates 38 mm (1-1/2 inches) less than width of door, except pairs of metal doors which shall have plates 25 mm (1 inch) less than width of each door. Extend all other combination kick-mop plates to within 6 mm (1/4 inch) of each edge of doors. Kick mop plates shall butt astragals. For jamb stop requirements, see specification sections pertaining to door frames.
  3. Kick-mop plates are not required on following door sides:
    - a. Exterior side of exterior doors;
    - b. Closet side of closet doors;
    - c. Storage side of doors to or from storage spaces; and
    - d. Both sides of aluminum entrance doors.

## 2.10 EXIT DEVICES

- A. Conform to ANSI Standard A156.3. Exit devices shall be Grade 1; type and function are specified in hardware sets. Provide flush with finished floor strikes for vertical rod exit devices in interior of building. Trim shall have lever handles similar to locksets, unless otherwise specified.

- B. Exit devices for fire doors shall comply with Underwriters Laboratories, Inc., requirements for Fire Exit Hardware. Submit proof of compliance.

**2.11 FLUSH BOLTS (LEVER EXTENSION)**

- A. Conform to ANSI A156.16. Flush bolts shall be Type L24081 unless otherwise specified. Furnish proper dustproof strikes conforming to ANSI A156.16, for flush bolts required on lower part of doors. Modify flush bolts to fit stiles of aluminum doors on double-acting doors.
- B. Face plates for cylindrical strikes shall be rectangular and not less than 25 mm by 63 mm (1 inch by 2-1/2 inches).
- C. Friction-fit cylindrical dustproof strikes with circular face plate may be used only where metal thresholds occur.

**2.12 DOOR PULLS**

Conform to ANSI A156.6. Pull plate 90 mm by 350 mm (3-1/2 inches by 14 inches), unless otherwise specified. Cut plates of door pulls for cylinders, or turn pieces where required.

**2.13 PUSH PLATES**

Conform to ANSI A156.6. Plastic, Type J302, 200 mm (8 inches) wide by 350 mm (14 inches) high. Provide plastic Type J300 plates 100 mm (4 inches wide by 350 mm (14 inches) high) where push plates are specified for doors with stiles less than 200 mm (8 inches) wide. Color shall be as specified for kick-mop plates in Section 09 06 00, SCHEDULE FOR FINISHES. Cut plates for cylinders, and turn pieces where required. When wood grain plastic plates are specified in SCHEDULE FOR FINISHES Section, grain in plates shall run in same direction as grain of face veneer of wood doors.

**2.14 COMBINATION PUSH AND PULL PLATES**

Conform to ANSI 156.6. Type J303, stainless steel 3 mm (1/8 inch) thick, 80 mm (3-1/3 inches) wide by 800 mm (16 inches) high), top and bottom edges shall be rounded. Secure plates to wood doors with 38 mm (1-1/2 inch) long No. 12 wood screws. Cut plates for turn pieces, and cylinders where required. Pull shall be mounted down.

**2.15 THRESHOLDS**

- A. Conform to ANSI A156.21, mill finish extruded aluminum, except as otherwise specified. In existing construction, thresholds shall be installed in a bed of sealant with machine screws and expansion shields. In new construction, embed aluminum anchors coated with epoxy

in concrete to secure thresholds. Furnish thresholds for the full width of the openings.

- B. For thresholds at elevators entrances see other sections of specifications.

**2.16 WEATHERSTRIPS (FOR EXTERIOR DOORS)**

Conform to ANSI A156.22. Air leakage shall not to exceed 0.50 CFM per foot of crack length (0.000774m<sup>3</sup>/s/m).

**2.17 PADLOCKS FOR VARIOUS DOORS, GATES AND HATCHES**

- A. ASTM F883, size 50 mm (2 inch) wide chain; furnish extended shackles as required by job conditions. Provide padlocks, with key cylinders, for each door in following areas as noted.

- B. Key padlocks as follows:

1. Chain Link Fence Gates
2. Roof Access and Scuttles: Engineer's set.

**2.18 FINISHES**

- A. Exposed surfaces of hardware shall have ANSI A156.18, finishes as specified below. Finishes on all hinges, pivots, closers, thresholds, etc., shall be as specified below under "Miscellaneous Finishes." For field painting (final coat) of ferrous hardware, see Section 09 91 00, PAINTING.

- B. 626 or 630: All surfaces on exterior and interior of buildings, except where other finishes are specified.

- C. Miscellaneous Finishes:

1. Hinges --exterior doors: 626 or 630.
2. Hinges --interior doors: 652.
3. Door Closers: Factory applied paint finish. Dull or Satin Aluminum color.
4. Thresholds: Mill finish aluminum.
5. Other primed steel hardware: 652.

- D. Color of Plastic Items: See Section 09 06 00, SCHEDULE FOR FINISHES. Where colors other than chocolate brown or black are specified, color of core material may be different than color of face.

**2.19 BASE METALS**

Apply specified U.S. Standard finishes on different base metals as following:

Finish	Base Metal
652	Steel

626	Brass or bronze
630	Stainless steel

**PART 3 - EXECUTION**

**3.1 HARDWARE HEIGHTS**

- A. For new buildings locate hardware on doors at heights specified below unless otherwise noted:
- B. Hardware Heights from Finished Floor:
1. Exit devices centerline of strike (where applicable) 1000 mm (40-5/16 inches).
  2. Locksets and latch sets centerline of strike 1000 mm (40-5/16 inches).
  3. Deadlocks centerline of strike 1200 mm (48 inches).
  4. Centerline of door pulls to be 1000 mm (40 inches).
  5. Push plates and push-pull shall be 1250 mm (50 inches) to top of plate.
  6. Push-pull latch to be 1000 mm (40-5/16 inches) to centerline of strike.
  7. Centerline of deadlock strike to be 840 mm (33 inches) when used with push-pull latch.
  8. Locate other hardware at standard commercial heights. Locate push and pull plates to prevent conflict with other hardware.

**3.2 INSTALLATION**

- A. Closer devices, including those with hold-open features, shall be equipped and mounted to provide maximum door opening permitted by building construction or equipment. Closers shall be mounted regular arm. Where closers are mounted on doors they shall be mounted with sex nuts and bolts; foot shall be fastened to frame with machine screws.
- B. Substitute parallel arm or top jamb mounting for regular arm mounting where the following conditions occur:
1. Where door swing, in full open position, would be limited to less than 90 degrees due to partition construction and closer location.
  2. Where door to room opens outward into corridor.
  3. Where exterior doors open outward.

C. Hinge Size Requirements:

Door Thickness	Door Width	Hinge Height
45 mm (1-3/4 inch)	900 mm (3 feet) and less	113 mm (4-1/2 inches)
45 mm (1-3/4 inch)	Over 900 mm (3 feet) but not more than 1200 mm (4 feet)	125 mm (5 inches)
35 mm (1-3/8 inch) (hollow core wood doors)	Not over 1200 mm (4 feet)	113 mm (4-1/2 inches)

D. Hinge leaves shall be sufficiently wide to allow doors to swing clear of door frame trim.

E. Where new hinges are specified for new doors in existing frames or existing doors in new frames, sizes of new hinges shall match sizes of existing hinges; or, contractor may reuse existing hinges provided hinges are restored to satisfactory operating condition as approved by RE/COTR. Existing hinges shall not be reused on door openings having new doors and new frames. Coordinate preparation for hinge cut-outs and screw-hole locations on doors and frames.

F. Hinges Required Per Door:

Doors 1500 mm (5 ft) or less in height	2 butts
Doors over 1500 mm (5 ft) high and not over 2280 mm (7 ft 6 in) high	3 butts
Doors over 2280 mm (7 feet 6 inches) high	4 butts
Dutch type doors	4 butts
Doors with spring hinges 1370 mm (4 feet 6 inches) high or less	2 butts
Doors with spring hinges over 1370 mm (4 feet 6 inches)	3 butts

G. Fastenings: Suitable size and type and shall harmonize with hardware as to material and finish. Provide machine screws and lead expansion shields to secure hardware to concrete, ceramic or quarry floor tile, or solid masonry. Fiber or rawl plugs and adhesives are not permitted. All fastenings exposed to weather shall be of nonferrous metal.

H. After locks have been installed; show in presence of RE/COTR that keys operate their respective locks in accordance with keying requirements. (All keys, Master Key level and above shall be sent Registered Mail to the Cemetery Director along with the bitting list. Also a copy of the

invoice shall be sent to the RE/COTR for his records.) Installation of locks which do not meet specified keying requirements shall be considered sufficient justification for rejection and replacement of all locks installed on project.

### 3.3 HARDWARE SETS

Following sets of hardware correspond to hardware symbols shown on drawings. Where hardware set for a single door is specified for a pair of doors; equip each leaf of such pair of doors with set noted. Only those hardware sets that are shown on drawings will be required. Disregard hardware sets listed in specifications but not shown on drawings.

- A. Following sets of hardware correspond to hardware symbols shown on drawings. Only those hardware sets that are shown on drawings will be required. Disregard hardware sets listed in specifications but not shown on drawings.
- B. Hardware Consultant working on a project will be responsible for providing additional information regarding these hardware sets. The numbers shown in the following sets come from BHMA standards.

ELECTRIC HARDWARE ABBREVIATIONS LEGEND:  
ADO = Automatic Door Operator  
EMCH = Electro-Mechanical Closer-Holder  
MHO = Magnetic Hold-Open (wall- or floor-mounted)

### INTERIOR SINGLE DOORS

HW-1

Each Door to Have:

NON-RATED

1	Continuous Hinge	
1	Door Pull w/ Plate	J401 x J302
1	Push Plate	J302
1	Kick Plate	J102
1	Mop Plate (@ Inswing Doors)	J103
1	Closer	C02011/C02021
1	Floor Stop	L02121 x 3 FASTENERS
3	Silencers	L03011

HW-2

Each Door to Have:

RATED/NON-RATED

	QUANTITY & TYPE AS REQUIRED
Hinges	
1 Keyed Privacy Indicator Lock	F13 x OCCUPANCY INDICATOR
1 Closer	C02011/C02021
1 Kick Plate	J102
1 Mop Plate (@ Inswing Doors)	J103
1 Floor Stop	L02121 x 3 FASTENERS
1 Set Self-Adhesive Seals	ROY154

STONE THRESHOLD BY OTHER TRADES.

HW-3G

Each Door to Have:

NON-RATED

	QUANTITY & TYPE AS REQUIRED
Hinges	
1 Office Lock	F04
1 Floor Stop	L02121 x 3 FASTENERS
1 Coat Hook	L03121
1 Threshold	J32300 x 57 MM WIDTH (2-1/4 INCHES)
1 Auto Door Bottom	ROY346 - HEAVY DUTY
2 Sets Self-Adhesive Seals	ROY154

HW-4J

Each Door to Have:

RATED/NON-RATED

	QUANTITY & TYPE AS REQUIRED
Hinges	
1 Utility Lock	F09
1 Closer (@ Rated Doors)	C02011/C02021
1 Kick Plate	J102
1 Floor Stop	L02121 x 3 FASTENERS
1 Threshold	J32300 x 57 MM WIDTH (2-1/4 INCHES)
1 Auto Door Bottom	ROY346 - HEAVY DUTY
2 Sets Self-Adhesive Seals	ROY154

HW-5D

Each Door to Have:

NON-RATED

Hinges	QUANTITY & TYPE AS REQUIRED
1 Storeroom Lock	F07
1 Kick Plate	J102 (@ STORAGE, EVM, & HAC ROOMS ONLY)
1 Floor Stop (@ Inswing Doors)	L02121 x 3 FASTENERS
1 Wall Stop (@ Outswing Doors)	L02101 CONVEX
3 Silencers	L03011

HW-6C

Each Door to Have:

NON-RATED/RATED

1 Continuous Hinge	x INTEGRAL HINGE GUARD CHANNEL X ADJUSTA-SCREWS
1 Exit Device	TYPE 1 F08 LEVER
1 Key Cylinder	TYPE AS REQUIRED
1 Closer	C02021
1 Kick Plate	J102
1 Edge Guard (@ Wood Doors)	J208M / J211 (VERIFY), CUT: HARDWARE
1 Floor Stop	L02121 x 3 FASTENERS
1 Threshold	J32300 x 57 MM WIDTH (2-1/4 INCHES)
1 Auto Door Bottom	ROY346 - HEAVY DUTY
2 Sets Self-Adhesive Seals	ROY154

HW-10A

Each [ADO] Pair to Have:

NON-RATED

1	Continuous Hinge	x INTEGRAL HINGE GUARD CHANNEL X ADJUSTA-SCREWS x 8--THRUWIRE TRANSFER X IN-HINGE ACCESS PANEL
1	Continuous Hinge	x INTEGRAL HINGE GUARD CHANNEL X ADJUSTA-SCREWS X 4--THRUWIRE TRANSFER X IN-HINGE ACCESS PANEL
1	Set Auto Flush Bolts	TYPE 25 LESS BOTTOM BOLT
1	Storeroom Lock	F08
1	Electric Unlatch Strike	E09321 (FAIL SECURE)
1	Power Supply	REGULATED, FILTERED, 24VDC, AMPERAGE AS REQUIRED
1	Coordinator	TYPE 21A
1	Overlapping Astragal with Self-Adhesive Seal	ROY634 x ROY154 x THRU-BOLTS
2	Armor Plates	J101 x 1.275 MM (0.050 INCH) THICKNESS
2	Edge Guard (@ Wood Doors)	J208M / J211 (VERIFY), CUT: HARDWARE
2	Floor Stops	L02121 x 3 FASTENERS
2	Auto Door Bottoms	ROY346 - HEAVY DUTY
2	Set Self-Adhesive Seals	ROY154
2	Alarm Contacts	
1	Threshold (outswing door)	J32120 x SILICONE GASKET
2	Door Sweep	ROY416
1	Set Frame Seals	ROY164
1	Drip	ROY976

POWER TRANSFER **SHARED BY ELECTRIC STRIKE AND RE-ACTIVATION SENSOR WIRING**  
(RE-ACTIVATION SENSORS PROVIDED BY SECTION 08 71 13).  
CARD READER BY DIVISION 28.

HW-11

Each Pair to Have:

RATED/NR

<u>Hinges</u>		QUANTITY & TYPE AS REQUIRED
1	Set Auto Flush Bolts	TYPE 25 LESS BOTTOM BOLT
1	Storeroom Lock	F07
1	Coordinator	TYPE 21A
1	Overlapping Astragal with Self-Adhesive Seal	R0Y634 x R0Y154 x THRU-BOLTS
2	Closers	C02011/C02021
2	Kick Plates	J102 (@ STORAGE ROOMS ONLY)
2	Floor Stops	L02121 x 3 FASTENERS
1	Set Self-Adhesive Seals	R0Y154

HW-E4

Each Door to Have:

NON-RATED

1	Continuous Hinge	
1	Anti-Vandal Pull	
1	Exit Device	TYPE 1 F03 LESS TRIM
1	Latch Protector (outswing dr.)	
1	Key Cylinder	TYPE AS REQUIRED
1	Closer	C02011
1	Kick Plate	J102
1	Floor Stop	L02121 x 3 FASTNERS
1	Threshold	J32120 x SILICONE GASKET
1	Door Sweep	R0Y416
1	Set Frame Seals	R0Y164
1	Drip	R0Y976

SECURITY HARDWARE ABBREVIATIONS LEGEND:

AC = Access Control Device (Card reader, biometric reader, keypad, etc.)  
ADO = Automatic Door Operator  
DEML = Delayed Egress Magnetic Lock  
DEPH = Delayed Egress Panic Exit Device  
DPS = Door Position Switch (Door or Alarm Contact)  
EL = Electric Lock or Electric Lever Exit Device  
PB = Push-button Combination Lock (stand-alone)  
RR = Remote Release Button  
ELR = Electric Latch Retraction Exit Device  
REX = Request-to-Exit Switch in Latching Device Inside Trim

INTERIOR SINGLE SECURITY DOORS

HW-SH-3

Each [AC, EL, REX, DPS] Door to Have:

RATED/NON-RATED

	QUANTITY & TYPE AS REQUIRED
Hinges	4-WIRE TYPE AS REQUIRED
1 Transfer Hinge	F07 (E01-REX, E06) 24VDC
1 Electrified Lock	REGULATED, FILTERED, 24VDC, AMPERAGE
1 Power Supply	AS REQUIRED
1 Closer	C02011/C02021
1 Floor Stop	L02121 x 3 FASTENERS
1 Threshold	J32300 x 57 MM WIDTH (2-1/4 INCHES)
1 Auto Door Bottom	ROY346 - HEAVY DUTY
2 Sets Self-Adhesive Seals	ROY154
1 Alarm Contact	

120VAC POWER, CONDUIT, AND WIRING BY DIVISION 26.

CARD READER BY DIVISION 28.

HW-SH-3C

Each [PB] Door to Have:

NON-RATED/RATED

1 Continuous Hinge	x INTEGRAL HINGE GUARD CHANNEL X ADJUSTA-SCREWS
1 Push-button Combination Lock	N3 - A156.13 F07 G1 E06
1 Closer	C02011/C02021
1 Armor Plate	J101 x 1.275 MM (0.050 INCH) THICKNESS
1 Edge Guard (@ Wood Doors)	J208M / J211 (VERIFY), CUT: HARDWARE
1 Floor Stop	L02121 x 3 FASTENERS
1 Set Self-Adhesive Seals	ROY154

HW-SH-4B

Each Door to Have:

RATED

1 Continuous Transfer Hinge	x INTEGRAL HINGE GUARD CHANNEL X ADJUSTA-SCREWS x 12-THRUWIRE TRANSFER X IN-HINGE ACCESS PANEL
1 Electrified Exit Device	TYPE 1 (E01-REX, E06) F13 LEVER
1 Key Cylinder	TYPE AS REQUIRED
1 Power Supply	TYPE REQUIRED BY PANIC MANUFACTURER X ADO BOARD
1 Armor Plate	J101 x 1.275 MM (0.050 INCH) THICKNESS
1 Edge Guard (@ Wood Doors)	J208M / J211 (VERIFY), CUT: HARDWARE
1 Floor Stop	L02121 x 3 FASTENERS
1 Set Self-Adhesive Seals	ROY154


1 Aluminum Threshold

2 Alarm Contacts

POWER TRANSFER **SHARED BY ELECTRIC PANIC AND** RE-ACTIVATION SENSOR WIRING  
120VAC POWER, CONDUIT, AND WIRING BY DIVISION 26.

CARD READER BY DIVISION 28.

- - - E N D - - -



**SECTION 08 80 00**  
**GLAZING**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

This section specifies glass, related glazing materials and accessories. Glazing products specified apply to factory or field glazed items.

**1.2 RELATED WORK**

A. Factory glazed by manufacturer in following units:

1. HOLLOW METAL DOORS AND FRAMES, and Section 08 14 00, WOOD DOORS.
2. Mirrors: Section 10 28 00, TOILET, BATH, AND LAUNDRY ACCESSORIES.
3. Section 08 51 13, ALUMINUM WINDOWS
4. Color of tinted (heat absorbing or light reducing) glass, and reflective (metallic coated) glass: Section 09 06 00, SCHEDULE FOR FINISHES.

**1.3 LABELS**

A. Temporary labels:

1. Provide temporary label on each light of glass and plastic material identifying manufacturer or brand and glass type, quality and nominal thickness.
2. Label in accordance with NFRC (National Fenestration Rating Council) label requirements.
3. Temporary labels shall remain intact until glass and plastic material is approved by RE/COTR.

B. Permanent labels:

1. Locate in corner for each pane.
2. Label in accordance with ANSI Z97.1 and SGCC (Safety Glass Certification Council) label requirements.
  - a. Tempered glass.
  - b. Laminated glass or have certificate for panes without permanent label.

**1.4 PERFORMANCE REQUIREMENTS**

A. Building Enclosure Vapor Retarder and Air Barrier:

1. Utilize the inner pane of multiple pane sealed units for the continuity of the air barrier and vapor retarder seal.
2. Maintain a continuous air barrier and vapor retarder throughout the glazed assembly from glass pane to heel bead of glazing sealant.

B. Glass Thickness:

1. Select thickness of exterior glass to withstand dead loads and wind loads acting normal to plane of glass at design pressures calculated in accordance with ASCE 7 applicable code.
2. Limit glass deflection to 1/200 or flexure limit of glass, whichever is less, with full recovery of glazing materials.
3. Test in accordance with ASTM E 330.
4. Thicknesses listed are minimum. Coordinate thicknesses with framing system manufacturers.

#### 1.5 SUBMITTALS

- A. In accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Certificates:
  1. Certificates stating that wire glass, meets requirements for safety glazing material as specified in ANSI Z97.1.
  2. Certificate on shading coefficient.
  3. Certificate on "R" value when value is specified.
  4. Certificate test reports confirming compliance's with specified bullet resistive rating.
  5. Certificate that blast resistant glass meets the requirements of UFC4-010-01.
- C. Warranty: Submit written guaranty, conforming to General Condition requirements, and to "Warranty of Construction" Article in this Section.
- D. Manufacturer's Literature and Data:
  1. Glass, each kind required.
  2. Insulating glass units.
  3. Elastic compound for metal sash glazing.
  4. Putty, for wood sash glazing.
  5. Glazing cushion.
  6. Sealing compound.
- E. Samples:
  1. Size: 300 mm by 300 mm (12 inches by 12 inches).
  2. All glazing types specified for the project.
- F. Preconstruction Adhesion and Compatibility Test Report: Submit glazing sealant manufacturer's test report indicating glazing sealants were tested for adhesion to glass and glazing channel substrates and for compatibility with glass and other glazing materials.

#### 1.6 DELIVERY, STORAGE AND HANDLING

- A. Delivery: Schedule delivery to coincide with glazing schedules so minimum handling of crates is required. Do not open crates except as required for inspection for shipping damage.
- B. Storage: Store cases according to printed instructions on case, in areas least subject to traffic or falling objects. Keep storage area clean and dry.
- C. Handling: Unpack cases following printed instructions on case. Stack individual windows on edge leaned slightly against upright supports with separators between each.
- D. Protect laminated security glazing units against face and edge damage during entire sequence of fabrication, handling, and delivery to installation location. Provide protective covering on exposed faces of glazing plastics, and mark inside as "INTERIOR FACE" or "PROTECTED FACE":
  - 1. Protect sealed-air-space insulating glazing units from exposure to abnormal pressure changes, as could result from substantial changes in altitude during delivery by air freight. Provide temporary breather tubes which do not nullify applicable warranties on hermetic seals.
  - 2. Temporary protections: The glass front and polycarbonate/Noviflex back of glazing shall be temporarily protected with compatible, peelable, heat-resistant film which will be peeled for inspections and re-applied and finally removed after doors and windows are installed at destination. Since many adhesives will attack polycarbonate, the film used on exposed polycarbonate surfaces shall be approved and applied by manufacturer.
  - 3. Edge protection: To cushion and protect glass clad, polycarbonate, and Noviflex edges from contamination or foreign matter, the four edges shall be sealed the depth of glazing with continuous standard-thickness Santoprene tape. Alternatively, continuous channel shaped extrusion of Santoprene shall be used, with flanges extending into face sides of glazing.

#### 1.7 PROJECT CONDITIONS

Field Measurements: Field measure openings before ordering tempered glass products. Be responsible for proper fit of field measured products.

**1.8 WARRANTY**

- A. Warranty: Conform to terms of "Warranty of Construction", FAR clause 52.246-21, except extend warranty period for the following:
1. Insulating glass units to remain sealed for 10 years.
  2. Laminated glass units to remain laminated for 5 years.
  3. Polycarbonate to remain clear and ultraviolet light stabilized for 5 years.

**1.9 APPLICABLE PUBLICATIONS**

- A. Publications listed below form a part of this specification to extent referenced. Publications are referenced in text by basic designation only.
- B. American National Standards Institute (ANSI):
- Z97.1-04.....Safety Glazing Material Used in Building -  
Safety Performance Specifications and Methods  
of Test.
- C. American Society for Testing and Materials (ASTM):
- C542-05.....Lock-Strip Gaskets.  
C716-06.....Installing Lock-Strip Gaskets and Infill  
Glazing Materials.  
C864-05.....Dense Elastomeric Compression Seal Gaskets,  
Setting Blocks, and Spacers.  
C920-08.....Elastomeric Joint Sealants.  
C1036-06.....Flat Glass.  
C1048-04.....Heat-Treated Flat Glass-Kind HS, Kind FT Coated  
and Uncoated Glass.  
C1115-06 .....Standard Specification for Dense Elastometric  
Silicone Rubber Gaskets and Accessories.  
C1172-03.....Laminated Architectural Flat Glass.  
C1184-05.....Standard Specification for Structural Silicone  
Sealants.  
C1281-03.....Standard Specification for Preformed Tape  
Sealants for Glazing Applications.  
C1349-04.....Architectural Flat Glass Clad Polycarbonate.  
C1363-05.....Thermal Performance of Building Assemblies, by  
Means of A Hot Box Apparatus  
D4802-07.....Poly (Methyl Methacrylate) Acrylic Plastic  
Sheet.

E330-02.....Structural Performance of Exterior Windows,  
Curtain Walls, and Doors by Uniform Static Air  
Pressure Difference.

E2190-08.....Insulating Glass Unit

D. Commercial Item Description (CID):

A-A-59502.....Plastic Sheet, Polycarbonate

E. Code of Federal Regulations (CFR):

16 CFR 1201 - Safety Standard for Architectural Glazing Materials;  
1977, with 1984 Revision.

F. National Fenestration Rating Council (NFRC):

Certified Products Directory (Latest Edition).

G. Safety Glazing Certification Council (SGCC):

Certified Products Directory (Issued Semi-Annually).

**PART 2 - PRODUCT**

**2.1 GLASS**

A. Use thickness stated unless specified otherwise in assemblies.

B. Clear Glass:

1. For use in interior viewing windows.
2. ASTM C1036, Type I, Class 1, Quality q4 .
3. Thickness, 6 mm (1/4 inch) or as indicated .

**2.2 HEAT-TREATED GLASS**

A. Clear Heat Strengthened Float Glass:

1. For use as exterior and interior pane of clear insulated glass unit  
and interior pane of tinted insulated glass unit.
2. ASTM C1048, Kind HS, Condition A, Type I, Class 1, Quality q3.
3. Thickness, 6 mm (1/4 inch) or as indicated .

B. Tinted Heat Strengthened Glass:

1. For use as exterior pane of insulated glass unit.
2. ASTM C1048, Kind HS, Condition A, Type I, Class 2, Quality q3.
3. Color: \_\_\_\_.
4. Thickness, 6 mm (1/4 inch) or as indicated .

C. Clear Tempered Glass:

1. For use in interior doors and sidelights.
2. ASTM C1048, Kind FT, Condition A, Type I, Class 1, Quality q3.
3. Thickness, 6 mm (1/4 inch) or as indicated .

### 2.3 INSULATING GLASS UNITS

- A. Provide preassembled units consisting of sealed lites separated by a dehydrated interspace and complying with ASTM E774 for class CBA units.
- B. Provide overall unit and individual component thickness as indicated in the Part 3 glazing schedule.
- C. Provide sealing system consisting of a dual seal with primary and secondary sealants consisting of Polyisobutylene and silicone.
- D. Provide the manufacturer's standard spacer material and construction.

### 2.6 GLAZING ACCESSORIES

- A. As required to supplement the accessories provided with the items to be glazed and to provide a complete installation. Ferrous metal accessories exposed in the finished work shall have a finish that will not corrode or stain while in service.
- B. Setting Blocks: ASTM C864:
  - 1. Channel shape; having 6 mm (1/4 inch) internal depth.
  - 2. Shore a hardness of 80 to 90 Durometer.
  - 3. Block lengths: 50 mm (two inches) except 100 to 150 mm (four to six inches) for insulating glass.
  - 4. Block width: Approximately 1.6 mm (1/16 inch) less than the full width of the rabbet.
  - 5. Block thickness: Minimum 4.8 mm (3/16 inch). Thickness sized for rabbet depth as required.
- C. Spacers: ASTM C864:
  - 1. Channel shape having a 6 mm (1/4 inch) internal depth.
  - 2. Flanges not less 2.4 mm (3/32 inch) thick and web 3 mm (1/8 inch) thick.
  - 3. Lengths: One to 25 to 76 mm (one to three inches).
  - 4. Shore a hardness of 40 to 50 Durometer.
- D. Sealing Tapes: Comply with ASTM C 1281.
- E. Glazing Gaskets: Comply with ASTM C864 or C1115:
- F. Lock-Strip Glazing Gaskets: ASTM C542, shape, size, and mounting as indicated.
- G. Glazing Sealants: ASTM C920, silicone neutral cure:
  - 1. Type S.
  - 2. Class 25
  - 3. Grade NS.

4. Shore A hardness of 25 to 30 Durometer.

H. Structural Sealant: ASTM C920 and C1184, silicone acetoxy cure:

1. Type S.
2. Class 25.
3. Grade NS.
4. Shore a hardness of 25 to 30 Durometer.

I. Color:

1. Color of glazing compounds, gaskets, and sealants used for aluminum color frames shall match color of the finished aluminum and be nonstaining.
2. Color of other glazing compounds, gaskets, and sealants which will be exposed in the finished work and unpainted shall be black, gray, or neutral color.

### **PART 3 - EXECUTION**

#### **3.1 EXAMINATION**

A. Verification of Conditions:

1. Examine openings for glass and glazing units; determine they are proper size; plumb; square; and level before installation is started.
2. Verify that glazing openings conform with details, dimensions and tolerances indicated on manufacturer's approved shop drawings.

B. Advise Contractor of conditions which may adversely affect glass and glazing unit installation, prior to commencement of installation: Do not proceed with installation until unsatisfactory conditions have been corrected.

C. Verify that wash down of adjacent masonry is completed prior to erection of glass and glazing units to prevent damage to glass and glazing units by cleaning materials.

#### **3.2 PREPARATION**

- A. For sealant glazing, prepare glazing surfaces in accordance with GANA-02 Sealant Manual.
- B. Determine glazing unit size and edge clearances by measuring the actual unit to receive the glazing.
- C. Shop fabricate and cut glass with smooth, straight edges of full size required by openings to provide GANA recommended edge clearances.
- D. Verify that components used are compatible.
- E. Clean and dry glazing surfaces.

- F. Prime surfaces scheduled to receive sealants, as determined by preconstruction sealant-substrate testing.

### 3.3 INSTALLATION - GENERAL

- A. Install in accordance with GANA-01 Glazing Manual and GANA-02 Sealant Manual unless specified otherwise.
- B. Glaze in accordance with recommendations of glazing and framing manufacturers, and as required to meet the Performance Test Requirements specified in other applicable sections of specifications.
- C. Glaze doors in a securely fixed or closed and locked position, until sealant, glazing compound, or putty has thoroughly set.
- D. Tempered Glass: Install with roller distortions in horizontal position unless otherwise directed.
- EF. Insulating Glass Units:
1. Glaze in compliance with glass manufacturer's written instructions.
  2. When glazing gaskets are used, they shall be of sufficient size and depth to cover glass seal or metal channel frame completely.
  3. Do not use putty or glazing compounds.
  4. Do not grind, nip, cut, or otherwise alter edges and corners of fused glass units after shipping from factory.
  5. Install with tape or gunnable sealant in wood sash.

### 3.4 INSTALLATION - DRY METHOD (TAPE AND GASKET SPLINE GLAZING)

- A. Cut glazing tape spline to length; install on glazing pane. Seal corners by butting and sealing junctions with butyl sealant.
- B. Place setting blocks at 1/4 points with edge block no more than 150 mm (6 inches) from corners.
- C. Rest glazing on setting blocks and push against fixed stop with sufficient pressure to attain full contact.
- D. Install removable stops without displacing glazing spline. Exert pressure for full continuous contact.
- E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- F. Trim protruding tape edge.

### 3.5 INSTALLATION - WET METHOD (SEALANT AND SEALANT)

- A. Place setting blocks at 1/4 points and install glazing pane or unit.

- B. Install removable stops with glazing centered in space by inserting spacer shims both sides at 600 mm (24 inch) intervals, 6 mm (1/4 inch) below sight line.
- C. Fill gaps between glazing and stops with S-7 type sealant to depth of bite on glazing, but not more than 9 mm (3/8 inch) below sight line to ensure full contact with glazing and continue the air and vapor seal.
- D. Apply sealant to uniform line, flush with sight line. Tool or wipe sealant surface smooth.

### 3.6 REPLACEMENT AND CLEANING

- A. Clean new glass surfaces removing temporary labels, paint spots, and defacement after approval by RE/COTR.
- B. Replace cracked, broken, and imperfect glass, or glass which has been installed improperly.
- C. Leave glass, putty, and other setting material in clean, whole, and acceptable condition.


### 3.7 PROTECTION

- A. Protect finished surfaces from damage during erection, and after completion of work. Strippable plastic coatings on colored anodized finish are not acceptable.

### 3.8 GLAZING SCHEDULE

- A. Tempered Glass: GL-1
  - 1. Use clear tempered glass on interior side lights and doors.,
- B. Clear Float Glass: GL-2
  - 1. Interior observation windows not specified otherwise.
- C. Tinted, laminated, insulated Glass: GL-3
  - 1. 1/4" Tinted Heat Strengthened Glass.
  - 2. 1/2" air space
  - 3. 1/4" Heat Strengthened Glass.
  - 4. Color: (as selected)
- D. Clear, laminated, insulated Glass: GL-4
  - 1. 1/4" Heat Strengthened Glass.
  - 2. 1/2" air space
  - 3. 1/4" Heat Strengthened Glass.
  - 4. Color: Clear

- - - E N D - - -



**SECTION 08 90 00  
LOUVERS AND VENTS**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

This section specifies fixed and operable wall louvers, door louvers and wall vents.

**1.2 RELATED WORK**

- A. Louvers in steel doors: Section 08 11 13, HOLLOW METAL DOORS AND FRAMES.
- B. Color of finish: Section 09 06 00, SCHEDULE FOR FINISHES.

**1.3 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Shop Drawings:  
Each type, showing material, finish, size of members, (operating devices, if any) method of assembly, and installation and anchorage details.
- C. Manufacturer's Literature and Data:  
Each type of louver and vent.

**1.4 APPLICABLE PUBLICATIONS**

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. The Master Painters Institute (MPI):  
Approved Product List - 2009
- C. American Society for Testing and Materials (ASTM):  
A176-99(R2004).....Stainless and Heat-Resisting Chromium - Nickel Steel Plate, Sheet, and Strip  
A1008/A1008M-08.....Steel, Sheet, Carbon, Cold Rolled, Structural, and High Strength Low-Alloy with Improved Formability  
B209/B209M-07.....Aluminum and Aluminum Alloy, Sheet and Plate  
B221-08.....Aluminum and Aluminum Alloy Extruded Bars, Rods, Wire, Shapes, and Tubes
- D. National Association of Architectural Metal Manufacturers (NAAMM):  
AMP 500-505 (1988).....Metal Finishes Manual
- E. National Fire Protection Association (NFPA):  
90A-09.....Installation of Air Conditioning and Ventilating Systems
- G. American Architectural Manufacturers Association (AAMA):

2605-05.....Performing Organic Coatings on Architectural  
Extrusions and Panels

H. Air Movement and Control Association, Inc. (AMCA):  
500-L-07.....Testing Louvers

**PART 2 - PRODUCTS**

**2.1 MATERIALS**

- A. Aluminum, Extruded: ASTM B221/B221M.
- B. Stainless Steel: ASTM A167, Type 302B.
- C. Carbon Steel: ASTM A1008/A1008M.
- D. Aluminum, Plate and Sheet: ASTM B209/B209M.
- E. Fasteners: Fasteners for securing louvers and wall vents to adjoining construction, except as otherwise specified or shown, shall be toggle or expansion bolts, of size and type as required for each specific type of installation and service condition.
  - 1. Where type, size, or spacing of fasteners is not shown or specified, submit shop drawings showing proposed fasteners, and method of installation.
  - 2. Fasteners for louvers, louver frames, and wire guards shall be of stainless steel or aluminum.
- F. Inorganic Zinc Primer: MPI No. 19.

**2.2 EXTERIOR WALL LOUVERS**

- A. General:
  - 1. Provide fixed type louvers of size and design shown.
  - 2. Heads, sills and jamb sections shall have formed caulking slots or be designed to retain caulking. Head sections shall have exterior drip lip, and sill sections an integral water stop.
  - 3. Furnish louvers with sill extension or separate sill as shown.
  - 4. Frame shall be mechanically fastened or welded construction with welds dressed smooth and flush.
- B. Performance Characteristics:
  - 1. Weather louvers shall have a minimum of 50 percent free area and shall pass 500 fpm free area velocity at a pressure drop not exceeding 0.12 inch water gage and carry not more than 0.01 ounces of water per square foot of free area for 15 minutes when tested per AMCA Standard 500-L.
  - 2. Louvers shall bear AMCA certified rating seals for air performance and water penetration ratings.
- C. Aluminum Louvers:

1. General: Frames, blades, sills and mullions (sliding interlocking type); 2 mm (0.081-inch) thick extruded aluminum. Blades shall be standard type and have reinforcing bosses.
2. Louvers, fixed: Make frame sizes 13 mm (1/2-inch) smaller than openings. Single louvers frames shall not exceed 1700 mm (66 inches) wide. When openings exceed 1700 mm (66 inches), provide twin louvers separated by mullion members.

### **2.3 CLOSURE ANGLES AND CLOSURE PLATES**

- A. Fabricate from 2 mm (0.074-inch) thick stainless steel or aluminum.
- B. Provide continuous closure angles and closure plates on inside head, jambs and sill of exterior wall louvers.
- C. Secure angles and plates to louver frames with screws, and to masonry or concrete with fasteners as specified.

### **2.4 WIRE GUARDS**

- A. Provide wire guards on outside of all exterior louvers, except on exhaust air louvers.
- B. Fabricate frames from // 2 mm (0.081-inch) thick extruded or sheet aluminum // 1.5 mm (0.059-inch) thick stainless steel // designed to retain wire mesh.
- C. Wire mesh shall be woven from not less than // 1.6 mm (0.063-inch) diameter aluminum wire // 1.3 mm (0.05-inch) diameter stainless steel wire // in 13 mm (1/2-inch) square mesh.
- D. Miter corners and join by concealed corner clips or locks extending about 57 mm (2-1/4 inches) into rails and stiles. Equip wire guards over four feet in height with a mid-rail constructed as specified for frame components.
- E. Fasten frames to outside of louvers with aluminum or stainless steel devices designed to allow removal and replacement without damage to the wire guard or the louver.

### **2.5 EXTERIOR DOOR LOUVERS**

- A. Fabricate of 1.6 mm (0.063-inch) thick extruded aluminum. Miter frames at corners and join by concealed corner brackets.
- B. Equip louvers on outside with wire guards, except omit wire guards for louvers in doors located completely below enclosed areaways.

### **2.6 INTERIOR DOOR LOUVERS**

- A. Fabricate louvers for interior doors and partitions of 1.6 mm (0.063-inch) thick extruded aluminum.
- B. Make louvers sight-proof type with stationary blades, except where light-proof louvers are required.

## 2.7 WALL VENTS

- A. Fabricate exterior wall vents from either 4.7 mm (0.187-inch) thick aluminum plate of 6 mm (1/4-inch) thick cast iron, perforated in diamond lattice pattern, with not over 19 mm (3/4-inch) openings.
- B. Vents shall have aluminum screen frame with aluminum alloy insect screening mounted on back of vent by means of 19 mm x 5 mm (3/4-inch by 3/16-inch) top and bottom bars screwed to grille.
- C. Vent Frames In Masonry: Fabricate of 45 mm x 30 mm x 5 mm (1-3/4 inch by 1-1/4 inch by 3/16-inch) steel angles bolted with 6 mm (1/4-inch) diameter expansion bolts at jambs.

## 2.8 AIR INTAKE VENTS

- A. Fabricate exterior louvered wall ventilators for fresh air intake for air conditioning units from extruded aluminum, ASTM B221. Form with integral horizontal louvers and frame, with drip extending beyond face of wall and integral water stops.

## 2.9 BRICK VENTS

- A. Vents shall be of size shown formed of approximately 3 mm (0.125 inch) thick cast aluminum, or 3 mm (0.125) inch extruded aluminum.
- B. Provide vents complete with aluminum screen frame with corrosion resistant insect screening mounted on back of vent.
- C. Provide vents with required anchors.

## 2.10 FINISH

- A. In accordance with NAAMM Metal Finishes Manual: AMP 500-505
- B. Aluminum Louvers, Air Intake Vents, Wire Guards:
  - 1. Anodized finish
    - a. AA-M1X Mill finish, as fabricated.
  - 2. Organic Finish: AAMA 605 (Fluorocarbon coating).
- C. Aluminum Wall Vents and Brick Vents: Sand blasted satin finish.
- D. Stainless Steel: Mechanical finish No. 4 in accordance with NAAMM Metal Finishes Manual.
- E. Sheet Steel: Baked-on or oven dried shop prime coat.
  - 1. Paint interior surfaces of lightproof louvers with two additional finish shop coats of baked-on flat black enamel.
  - 2. Finish painting of exposed surfaces of shop primed louvers is specified in Section 09 91 00, PAINTING.
- F. Steel: Surfaces of steel work, for which no other finish is specified, shall be cleaned free from scale, rust, oil and grease, and then given a light colored prime paint after fabrication, except ferrous metals concealed in finished work. Paint all contact surfaces of assembled work

(except welded contact surfaces) with an additional shop coat of similar paint.

#### **2.11 PROTECTION**

- A. Provide protection for aluminum against galvanic action wherever dissimilar materials are in contact, by painting the contact surfaces of the dissimilar material with a heavy coat of bituminous paint (complete coverage), or by separating the contact surfaces with a performed synthetic rubber tape having pressure sensitive adhesive coating on one side.
- B. Isolate the aluminum from plaster, concrete and masonry by coating aluminum with zinc-chromate primer.
- C. Protect finished surfaces from damage during fabrication, erection, and after completion of the work. Strippable plastic coating on colored anodized or organic finish is not approved.//

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Set work accurately, in alignment and where shown. Items shall be plumb, level, free of rack and twist, and set parallel or perpendicular as required to line and plane of surface.
- B. Furnish setting drawings and instructions for installation of anchors and for the positioning of items having anchors to be built into masonry construction. Provide temporary bracing for such items until masonry is set.
- C. Provide anchoring devices and fasteners as shown and as necessary for securing louvers and vents to building construction as specified. Power actuated drive pins may be used, except for removal items and where members would be deformed or substrate damaged by their use.
- D. Generally, set wall louvers and vents in masonry walls during progress of the work. If wall louvers and vents are not delivered to job in time for installation in prepared openings, make provision for later installation. Set in cast-in-place concrete in prepared openings.

#### **3.2 CLEANING AND ADJUSTING**

- A. After installation, all exposed prefinished and plated items and all items fabricated from stainless steel and aluminum shall be cleaned as recommended by the manufacturer and protected from damage until completion of the project.
- B. All movable parts, including hardware, shall be cleaned and adjusted to operate as designed without binding or deformation of the members, so as to be centered in the opening of frame, and where applicable, to have

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

all contact surfaces fit tight and even without forcing or warping the  
components

- - - E N D - - -

SECTION 09 06 00  
SCHEDULE FOR FINISHES

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC:  
Location: Long Island, New York  
Project No. and Name: Administration/Public Restroom Renovations and New Equipment Storage building  
#815cm3038  
Submission: CD2  
Date: May 16, 2014

SECTION 09 06 00  
SCHEDULE FOR FINISHES

**PART I - GENERAL**

**1.1 DESCRIPTION**

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

**1.2 MANUFACTURERS**

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

**1.3 SUBMITALS**

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

**1.4 APPLICABLE PUBLICATIONS**

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

**PART 2- PRODUCTS**

**2.1 COLOR BOARD**

A. Size: As required to display building finishes.

B. Labeled for:

1. Building name and Number.

Long Island National Cemetery  
 Administration / Public Restroom  
 Renovation and New Equipment Building  
 2. All finishes used.

VA Project# 815 CM 3038  
 June 16, 2014

**2.2 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES**

DESIGNER NOTES: Coordinate with Section 06 20 00, FINISH CARPENTRY for items specified there as listed and additional items added for the project which are custom fabricate under this section. Communication center counter is custom fabricated for specific locations. List locations of each counter. Rubber or vinyl base is specified in Section 09 65 13, RESILIENT BASE AND ACCESSORIES. Specify other base material.  
 Duplicate items 1,2,3,4 for individual room numbers

**A. SECTION 06 20 00, FINISH CARPENTRY**

1. Lounge/ Kitchentte					
Room No. and Name	Component	Material	Species	Finish	Color
124 Lounge/kitchenette	Countertop	SS-1	Corian		Linon
	Vertical Surface(s)	PL-1	Laminate	STANDARD	WILSONART Amazon D478-60
	Base	RB-1	Rubber wall base	Roppe	124 Taupe

--	--	--	--	--	--

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

2. Kitchentte					
Room No. and Name	Component	Material Tag	Material	Manufacturer	Color
112 kitchenette	Countertop	SS-1	Corian	Corian	Linen
	Vertical Surface(s)	PL-1	Laminate	Wilsonart	Amazon D478-60
	Base	RB-1	Rubber wall base	Roppe	124 Taupe

3. Reception Desk					
Room No. and Name	Component	Material Tag	Material	Manufacturer	Color
116 Reception	Countertop	SS-1	Corian	Corian	Linen
	Vertical Surface(s)	PL-1	Laminate	Wilsonart	Amazon D478-60
	Base	RB-1	Rubber wall base	Roppe	124 Taupe

2.3 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

--

Long Island National Cemetery  
 Administration / Public Restroom  
 Renovation and New Equipment Building

VA Project# 815 CM 3038  
 June 16, 2014

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door

Component	Color of Paint Type and Gloss
Door	Wood
Frame	Wood
Window frame	Wood

B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	P-5
Frames	P-5

C. WINDOW SILLS

Room No. and Name	Material	Finish
See Drawings	Wood	P-5

DESIGNER NOTES: Coordinate with Section 08 71 00, DOOR HARDWARE for preferred finishes, specified par 2.28. List only items deviating from Section 08 71 00, par 2.28.

D. SECTION 08 80 00, GLAZING: See Drawings

2.4 DIVISION 09 - FINISHES

A. SECTION 09 30 13, CERAMIC TILING

1. CERAMIC MOSAIC TILE (CT)
-----------------------------

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

Finish Code	Size	Shape	Pattern	Manufacturer/ Style	Mfg. Color Name/No.
PT-1	18" X 18"	Square	None	Stonepeak Ceramics, Raja Series	Vijay Sand USG1818139
PT-2	12" x 24"	Rectangular	See Drawings	Stonepeak Ceramics, The Standard	Crème, USH1224052
PT-3	6"x 12"	Sanitary Cove Base	See Drawings	Stonepeak Ceramics, Raja Series	Vijay sand, USG612C139
PT-4	12" x 12"	Mosaic	See drawings	Stonepeak Ceramics, Raja Series	Vijay Sand, USG12MO139

2. SECTION 09 30 13, GROUT

Finish Code	Location	Manufacturer	Mfg. Color Name/No
GR-1	Restrooms	Laticete	23 Antique White

B. SECTION 09 66 16, TERRAZZO TILE (TT)

Size	Manufacturer	Color Pattern/Name/No.
24" x 24"	Fritztile	Natural Quarry Collection, Tejas QI60571

C. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
At-1	Exposed Suspension System	Cirrus Haze	Armstrong	584 Haze

D. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.

LVT-1	120 x 20 cm	Forbo	Allura Wood w60101
-------	-------------	-------	--------------------

E. SECTION 09 30 13, MARBLE THRESHOLDS

Marble Type	Manufacturer	Mfg. Color Name/No.
Polished	Daltile	Chiario Beige M710

F. SECTION 09 67 23, EPOXY RESINOUS FLOORING (ERF)

Finish code	Manufacturer	Mfg. Color Name/No.
RES-1	Key Resin Company	100 Light Gray/ Key Lastic ME2 with Key #520 topcoat

G. SECTION 09 68 00, CARPET MODULES (CFT)

Finish Code	Size	Pattern direction	Manufacturer	Mfg. Color Name/No.
CPT-1	24" X 24"	Quarter turn	Bentley	Building plan 882030/ Euro Modern loop
CPT-2	24" X 24"	Monolithic	Tandus	Bocote 43708/ Artisian 03579

1. SECTION 09 68 00, CARPET EDGE STRIP

Finish Code	Material	Manufacturer	Mfg. Color Name/No.
TS-1	Vinyl	Roppe	124 Taupe/ #50 tile carpet joiner

2. SECTION 09 68 00, CARPET BASE MOLDING

--	--	--	--

Material	Manufacturer	Mfg. Color Name/No.
Vinyl	Roppe	124 Taupe/ Pinnacle Standard

H. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

Gloss Level 1	a traditional matte finish-flat	Gloss @60	Sheen @85
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 5 units, and max 10 units, and	max 10 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	10-35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	min. 35 units
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P-1	Level 3	Sherwin Williams	Network Gray SW7073
P-2	Level 3	PPG Paints	Ostrich Feather 413-3
P-3	Level 3	PPG Paints	Prairie Dust 413-4

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038  
June 16, 2014

P-4	Level 1	Sherwin Williams	Alabaster SW7008
P-5	Level 5	Benjamin Moore	Beigewood 1007

I. SECTION 09 72 16, VINYL COATED FABRIC WALLCOVERING (W)

Finish Code	Manufacturer Color & Design	Mfg. Color Name/No.
W-1	Laurel Leaf Tile	cd2-lltt-03 buff
W-2	D.L. Couch	lanark Villa R2-VI-15 Espresso
W-3	Versa	Bristol Stripe A145-350 , Espresso

J. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS: Refer to Spec section 101405

K. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

DESIGNER NOTES: Use Section 10 28 00, TOILET, BATH, AND LAUNDRY ACCESSORIES for colored accessories. Not required for aluminum or stainless steel items.

L. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
Privacy Partitions	Bio Prism	InPro Corporation	Buff P9071

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	Term	Abbreviation
Acoustical Ceiling	AT	
Carpet Module Tile	CPT	
Existing	E	

Acoustical Ceiling	AT
Carpet Module Tile	CPT
Existing	E

Long Island National Cemetery  
 Administration / Public Restroom  
 Renovation and New Equipment Building

VA Project# 815 CM 3038  
 June 16, 2014

Floor Transition	TS
Gypsum Wallboard	GWB
Marble	MB
Paint	P
Plastic Laminate	PL
Porcelain Paver Tile	PT
Resinous Epoxy	RES
Rubber Base	RB

Solid Surface	SS
Terazzo Tile	TT
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	LVT
Wood	WD

3.2 ROOM FINISH SCHEDULE

A. Match adjoining or existing similar surfaces colors, textures or patterns where disturbed or damaged by alterations or new work when not scheduled.

B. ROOM FINISH SCHEDULE: See architectural Drawing A 1.5- Room finish schedule

--- E N D ---

**SECTION 09 22 16  
NON-STRUCTURAL METAL FRAMING**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

This section specifies steel studs wall systems, ceiling or soffit suspended or furred framing, wall furring, fasteners, and accessories for the screw attachment of gypsum board, plaster bases or other building boards.

**1.2 RELATED WORK**

- A. Load bearing framing: Section 05 40 00, COLD-FORMED METAL FRAMING.
- B. Ceiling suspension systems for acoustical tile or panels and lay in gypsum board panels: Section 09 51 00, ACOUSTICAL CEILINGS Section 09 29 00, GYPSUM BOARD.

**1.3 TERMINOLOGY**

- A. Description of terms shall be in accordance with ASTM C754, ASTM C11, ASTM C841 and as specified.
- B. Underside of Structure Overhead: In spaces where steel trusses or bar joists are shown, the underside of structure overhead shall be the underside of the floor or roof construction supported by beams, trusses, or bar joists.
- C. Thickness of steel specified is the minimum bare (uncoated) steel thickness.

**1.4 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Studs, runners and accessories.
  - 2. Hanger inserts.
  - 3. Channels (Rolled steel).
  - 4. Furring channels.
  - 5. Screws, clips and other fasteners.
- C. Shop Drawings:
  - 1. Typical ceiling suspension system.
  - 2. Typical metal stud and furring construction system including details around openings and corner details.

**1.5 DELIVERY, IDENTIFICATION, HANDLING AND STORAGE**

In accordance with the requirements of ASTM C754.

**1.6 APPLICABLE PUBLICATIONS**

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society For Testing And Materials (ASTM)
  - A123-09.....Zinc (Hot-dip Galvanized) Coatings on Iron and Steel Products
  - A653/A653M-08.....Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process
  - A641-09.....Zinc-Coated (Galvanized) Carbon Steel Wire
  - C11-08.....Terminology Relating to Gypsum and Related Building Materials and Systems
  - C635-07.....Manufacture, Performance, and Testing of Metal Suspension System for Acoustical Tile and Lay-in Panel Ceilings
  - C636-08.....Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels
  - C645-08.....Non-Structural Steel Framing Members
  - C754-08.....Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products
  - C841-03(R2008).....Installation of Interior Lathing and Furring
  - C954-07.....Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
  - C1002-07.....Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs
  - E580-08.....Application of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Requiring Moderate Seismic Restraint.

**PART 2 - PRODUCTS**

**2.1 STEEL STUDS AND RUNNERS (TRACK)**

- A. ASTM C645, with flange edges of studs bent back 90 degrees and doubled over to for 3/16 inch wide minimum lip (return) and complying with the following requirements for minimum thickness of base (uncoated) metal and for depth:

- 1. Minimum base metal thickness: 0.8 mm (0.0329 inch) (33 mil) (20 Gauge).

2. Depth: As indicated
3. Perforated metal studs of a lighter gauge will not be accepted.

## **2.2 FASTENERS, CLIPS, AND OTHER METAL ACCESSORIES**

- A. Provide fasteners of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel framing and furring members securely to substrates involved; complying with the recommendations of gypsum board manufacturers for applications indicated.

## **2.3 SUSPENDED CEILING SYSTEM FOR GYPSUM BOARD (OPTION)**

- A. Conform to ASTM C635 and C754. For materials and sizes
- B. Conform to ASTM C641 for wire hangers.

## **PART 3 - EXECUTION**

### **3.1 INSTALLATION CRITERIA**

- A. Examine substrates to which gypsum board assemblies attach or abut, installed hollow metal frames, cast-in-anchors, and structural framing, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of assemblies specified in this section.

### **3.2 INSTALLING STUDS**

- A. Install studs in accordance with ASTM C754, except as otherwise shown or specified.
- B. Install runners (tracks) at floors, ceilings, and structural walls and columns where gypsum board stud assemblies abut other construction.
  1. Extend partition framing full height to structural supports or substrates above suspended ceilings, except where otherwise indicated. Continue framing over frames of doors and openings and frame around ducts penetrating partitions above ceiling to provide support for gypsum board.
- C. Install steel studs and furring in sizes and at spacing indicated.
- D. Install steel studs so flanges point in the same direction and leading edge or end of each gypsum board panel can be attached to open (unsupported) edges of stud flanges first.
- E. Frame door openings to comply with GA-219, and with applicable published recommendations of gypsum board manufacturer, unless otherwise indicated. Attach vertical studs at jambs with screws either directly to frames or to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
  1. Install two (2) studs at each jamb, unless otherwise indicated.

- F. Frame openings other than door openings to comply with details indicated or, if none indicated, as required for door openings. Install framing below sills of openings to match framing required above door heads.

### 3.3 INSTALLING FURRED AND SUSPENDED CEILING OR SOFFITS

- A. Install furred and suspended ceilings or soffits in accordance with ASTM C754 or ASTM C841 except as otherwise specified or shown for screw attached gypsum board ceilings and for plaster ceilings or soffits.
- B. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or ceiling suspension system. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, counter splaying, or other equally effective means.
- C. Where width of ducts and other construction within ceiling plenum produces hanger spacing that interfere with the location of hangers required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.
- D. Secure wire hangers by looping and wire-tying, either directly to structures or to inserts, eyescrews, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause them to deteriorate or otherwise fail.
- E. Install suspended steel framing components in sizes and at spacing indicated, but not less than that required by the referenced steel framing installation standard.
  - 1. Wire Hangers: 48 inches o.c.
  - 2. Carrying Channels (Main Runners): 48 inches o.c.
  - 3. Furring Channels (Furring Members): 16 inches o.c
- F. Installation Tolerances: Install steel framing components for suspended ceilings so that cross-furring or grid suspension members are level to within 1/8 inch in 12 feet as measured both lengthwise on each member and transversely between parallel members.
- G. Wire-tie or clip furring members to main runners and to other structural supports as indicated.
- H. Grid Suspension System: Attach perimeter wall track or angle where grid suspension system meets vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track

Long Island National Cemetery  
Administration / Public Restroom  
Renovation and New Equipment Building

VA Project# 815 CM 3038

June 16, 2014

**3.7 TOLERANCES**

- A. Fastening surface for application of subsequent materials shall not vary more than 3 mm (1/8-inch) from the layout line.
- B. Plumb and align vertical members within 3 mm (1/8-inch.)
- C. Level or align ceilings within 3 mm (1/8-inch.)

- - - E N D - - -