

## DEMOLITION PLAN GENERAL NOTES - RESTROOMS, LOCKER ROOMS, AND SHOWER STALLS

1. REMOVE FLUORESCENT TROFFERS. REFER TO ELECTRICAL DRAWINGS.
2. REMOVE WALL-MOUNTED LIGHT FIXTURES. REFER TO ELECTRICAL DRAWINGS.
3. REMOVE PLUMBING FIXTURES. REFER TO PLUMBING DRAWINGS.
4. EXISTING SPRINKLER HEADS AND PIPING TO REMAIN. REFER TO FIRE PROTECTION DRAWINGS.
5. SUSPENDED ACOUSTICAL TILE CEILING GRID TO REMAIN. REMOVE CEILING TILES. REMOVE, SALVAGE AND REPLACE GRID AS REQUIRED TO INSTALL LIGHT FIXTURES. GRID DAMAGED DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE GOVERNMENT.
6. VENT GRILLS, SUPPLY DIFFUSERS AND RETURN REGISTERS SHALL REMAIN. WASH AND CLEAN ALL GRILLS, DIFFUSERS, AND REGISTERS IN THE CONSTRUCTION AREAS.
7. REMOVE AND SALVAGE TOILET PARTITIONS, URINAL SCREENS AND TOILET ACCESSORIES FOR REINSTALLATION. REPLACE MOUNTING AND DOOR HARDWARE. REFER TO EXISTING TOILET ACCESSORY SCHEDULE. REFER TO SHEET A601.
8. REMOVE 18" X 24" MIRRORS. REFER TO EXISTING TOILET ACCESSORY SCHEDULE. REFER TO SHEET A601.
9. REMOVE CERAMIC TILE WAINSCOT IN ALL ROOMS INCLUDING: A107, A108, A109, A110, B102, B103, B117, B119, B120, B220A, B313, B317, B319, B401, B402, B408, C203, C205, C317, C318, C319A, D110, D111, E104, E105, E120, E131, AND E514. FIELD VERIFY EXISTING CONDITIONS.
10. REMOVE THIN-SET CERAMIC TILE FLOORING AND CERAMIC TILE BASE IN RESTROOMS C317, C318, AND C319A.
11. REMOVE THICKSET CERAMIC FLOOR TILE, MUD BASE, AND CERAMIC WALL BASE TILE IN RESTROOM B408.
12. REMOVE VINYL COMPOSITION TILE AND CERAMIC TILE BASE IN RESTROOMS A107, A108, A109, A110, B401, B408, B408, C203 AND C205. FIELD VERIFY EXISTING CONDITIONS.
13. REMOVE VINYL COMPOSITION TILE AND RUBBER BASE RESTROOMS B102, B103, B117, B119, B220A, B313, B317, B319, D110, D111, E104, E105, E120, AND E514. FIELD VERIFY EXISTING CONDITIONS.

### NOTES:

CHANGES TO NOTES OCCUR ON SHEETS AD101, AD102, AD103, AD104, AD105, AD111, AD112, AD113, AD114, AND AD115.

ADDENDUM 1



**TOLAND  
MIZELL  
MOLNAR**

CORPORATE OFFICE  
590 Means St. NW, Ste. 200  
Atlanta, GA 30318  
404.214.9774

PROJECT TITLE: UPGRADE RESTROOMS AND INTERIOR FINISHES  
VIERA OUTPATIENT CLINIC  
PROJECT NO.: 675-13-151

DATE: 04/13/2015

