ALL WORK SHALL BE PERFORMED IN PHASES:

NO MORE THAN ONE ELEVATOR SHALL BE OUT OF SERVICE AT ANY GIVEN TIME. ORDER AND METHOD OF PHASING SHALL BE COORDINATED WITH FACILITY STAFF AND PROJECT MANAGEMENT [CONTRACTING OFFICER'S REPRESENTATIVE (COR)] PRIOR TO START OF WORK.

ELEVATOR MODERNIZATION NOTES:

CONTRACTOR SHALL VERIFY ALL EXISTING ELEVATOR COMPONENTS WITH THE PROJECT SPECIFICATIONS PRIOR TO SUBMISSION OF A BID. ALL EXISTING ITEMS SHALL BE VERIFIED, INCLUDING ITEMS NOTED AS "REUSE EXISTING". "REUSE OF EXISTING" COMPONENTS SHALL NOT EXCLUDE THE ITEMS FROM MODERNIZATION. THE SCOPE OF ELEVATOR MODERNIZATION SHOULD INCLUDE, BUT NOT BE LIMITED TO:
(CONTRACTOR SHALL VERIFY ALL STATEMENTS BELOW)

	ELEVATOR F-1	ELEVATORS P-2, P-3, & S-4
MACHINE	NEW	NEW
HOIST MOTOR	NEW	NEW
DEFLECTOR SHEAVE	REUSE EXISTING	REUSE EXISTING
CONTROL SYSTEM	NEW	NEW
DESTINATION DISPATCH	-	-
SELECTOR SYSTEM	NEW	NEW
DRIVE SYSTEM	NEW	NEW
GOVERNOR	NEW	NEW
HOIST & GOVERNOR CABLES	NEW	NEW
TRAVELING CABLES & WIRING	NEW	NEW
CAR FRAME	REUSE EXISTING	REUSE EXISTING
CAR PLATFORM	REUSE EXISTING	REUSE EXISTING
CAR GUIDE SHOES	REUSE EXISTING	REUSE EXISTING
GUIDE RAILS	REUSE EXISTING	REUSE EXISTING
BUFFERS	REUSE EXISTING	REUSE EXISTING
ENTRANCE FRAMES	NEW	NEW
ENTRANCE DOOR PANELS	NEW	NEW
HOISTWAY SILLS	REUSE EXISTING	REUSE EXISTING
DOOR OPERATOR	NEW	NEW
CAR DOOR PANEL	NEW	NEW
CAR SILL	REUSE EXISTING	REUSE EXISTING
DOOR DETECTORS	NEW	NEW
CAR ENCLOSURE	NEW	NEW
FLOORING	NEW	NEW
SIGNALS	NEW	NEW
ROAM ALERT CONTROLLER (PACS)	NEW	NEW



ENLARGED PLAN -
PASSENGER AND SERVICE ELEVATORS
@ SUB-BASEMENT LEVEL

1 — 1/4" = 1'-0"



ENLARGED PLAN:
PASSENGER AND SERVICE ELEVATORS
@ TYPICAL FLOOR PLAN

2 — 1/4" = 1'-0"

4TH FLOOR SHOWN: BASEMENT, 1ST - 3RD, AND 5TH - 7TH SIMILAR (8TH FLOOR SIMILAR, NO STOPS @ 8TH FLOOR)



ENLARGED PLAN
PASSENGER AND SERVICE ELEVATORS
@ ELEVATOR PENTHOUSE LEVEL

3 — 1/4" = 1'-0"

NORTH

FULLY SPRINKLERED CONSTRUCTION DOCUMENTS

Revisions:	Date

CONSULTANTS:

SEAL



ARCHITECTS/ENGINEERS:

AE WORKS

6587 Hamilton Avenue
Pittsburgh, Pennsylvania 15206
Ph: 412.287.7333 Fax: 412.287.7334
www.ae-works.com

AE Works Project Number: 13036

Drawing Title: ENLARGED PLANS - PASSENGER AND SERVICE ELEVATORS 'P-2' 'P-3' AND 'S-4'

Approved: Project Director

Project Title: ERIE VAMC - REPLACE ELEVATORS

Location: 135 EAST 38TH STREET, ERIE, PA 16504

Date: MAY 4, 2015 | **Checked:** JRD | **Drawn:** JDB

Project Number: 562-14-113

Building Number: 01

Drawing Number: 01-A410

Dwg. 6 **of** 16

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231