

Salient Characteristics

Krug Bali Guest Chair, Or Equal

1. General

Upholstered front of seat and back, with wood arm, back and seat shell, located in 1st floor Canteen Dining Area. Plywood shell flexes and provides lumbar support for comfort.

2. Warranty Requirements

- a. Manufacturer must offer a 10 year warranty that product is free from defects of materials and workmanship (includes shipping parts and labor for the repair or replacement of defective items).
- b. Seat must be warranted to support a minimum of 200 lbs.

3. Technical Specification and Code Requirements

- a. Chair must meet or exceed all ANSI/BIFMA X5.1 American National Standard for Office Furnishings-General Purpose Office Chairs.
- b. Chair padding materials, foam wrap, and fabric shall contain no halogenated fire retardants. Avoid TB177-2013 and TB-133.
- c. Testing of fabric abrasion, stain resistance, and durability must be documented and available upon request.

4. Environmental Features

- a. Chair must be designed and constructed of materials that do not present environmental or human health risk such as PVC, CFC, solvent based adhesives, heavy metals (lead and mercury) and benzene.
- b. Must be constructed free of environmentally hazardous processes such as those that produce VOC's and deplete ozone.
- c. Shipping packing materials shall be reusable and/or recyclable.

5. Dimensions and Features

- a. Dimensions:
 - i. Overall: Minimum 23"D, 23.25"W, 34.25"H
 - ii. Seat: 18"D, 19.5"W 17.5"H
- b. Stacks 6 high without caddie and 12 high with caddie.
- c. Steel support frame and back legs.

6. Surface Materials

- a. Chrome metal rear legs.
- b. Wood finish shall be available in a wide selection of stains.
- c. Upholstery shall be available in a wide variety of graded-in and COM (Customer's own material)
- d. All selected finishes must be approved by VA Interior Designer

7. Miscellaneous

- a. Manufacturer must have been in business for minimum of 10 years.
- b. Product must be guaranteed in writing to be available for a minimum of 10 years after first order entry.
- c. Product must ship with an option of boxed or blanket wrapped shipment.