

## **Salient Characteristics**

---

### **Coalesse Enea Lotus Stool, Or Equal**

#### **1. General**

Stool with rounded polypropylene shell, upholstered seat, counter-height post base, with chrome foot ring to be located in 1<sup>st</sup> floor Patient Information Resource Center.

#### **2. Warranty Requirements**

- a. Manufacturer must offer a minimum of 10 year limited warranty that product is free from defects of materials and workmanship (includes shipping parts and labor for the repair or replacement of defective items).
- b. Chair must be warranted to support a minimum of 300 lbs.

#### **3. Technical Specification and Code Requirements**

- a. Stool must meet or exceed all ANSI/BIFMA X5.1 American National Standard for Office Furnishings-General Purpose Office Chairs.
- b. Chair padding materials, foam wrap, and fabric shall contain no halogenated fire retardants. Avoid TB177-2013 and TB-133.
- c. Testing of fabric abrasion, stain resistance, and durability must be documented and available upon request.

#### **4. Environmental Features**

- a. Stool must meet SCS Indoor advantage Gold Certified and Level 1 ANSI/BIFMA 33 standard
- b. Stool must be designed and constructed of materials that do not present environmental or human health risk such as PVC, CFC, solvent based adhesives, heavy metals (lead and mercury) and benzene.
- c. Must be constructed free of environmentally hazardous processes such as those that produce VOC's and deplete ozone.
- d. Must be constructed of 20% recycled content and be 100% recyclable components.
- e. Shipping packing materials shall be reusable and/or recyclable.

#### **5. Dimensions and Features**

- a. Dimensions:
  - i. Overall: Minimum 19.75"D, 19.75"W, 34 1/2"H
  - ii. Seat: 26 1/4"H
- b. Steel frame and post base with trivalent chrome foot rest
- c. Polypropylene seat and back with upholstered seat insert

#### **6. Surface Materials**

- a. Polypropylene shell must be available in a wide range of colors
- b. Powder coat paint for base and frame must be available in minimum of 5 colors
- c. Upholstery shall be available in a wide variety of graded-in and COM (Customer's own material)
- d. All selected finishes must be approved by VA Interior Designer

#### **7. Miscellaneous**

- a. Manufacturer must have been in business for minimum of 10 years.
- b. Product must be guaranteed in writing to be available for a minimum of 10 years after first order entry.
- c. Product must ship fully assembled with an option of boxed or blanket wrapped shipment.