

Salient Characteristics

Krug Zola Freestanding Bariatric 2 seat Bench, Or Equal

1. General

Upholstered bariatric freestanding full depth 2 seat bench with metal base, located in 1st, 2nd, and 3rd floors Waiting Areas.

System is available with components that are inter-changeable, reconfigurable, and replaceable with metal to metal bracketry.

2. Warranty Requirements

- a. Manufacturer must offer a minimum of 10 year warranty that product is free from defects of materials and workmanship (includes shipping parts and labor for the repair or replacement of defective items).
- b. Seat must be warranted to support a minimum of 525 lbs.

3. Technical Specification and Code Requirements

- a. Chair must meet or exceed all ANSI/BIFMA X5.1 American National Standard for Office Furnishings- General Purpose Office Chairs.
- b. Chair padding materials, foam wrap, and fabric shall contain no halogenated fire retardants. Avoid TB177-2013 and TB-133.
- c. Testing of fabric abrasion, stain resistance, and durability must be documented and available upon request.

4. Environmental Features

- a. Chair must be designed and constructed of materials that do not present environmental or human health risk such as PVC, CFC, solvent based adhesives, heavy metals (chrome, lead and mercury) and benzene.
- b. Must contain at least 18% recycled content and be 35% recyclable at end of useful life.
- c. Must be constructed free of environmentally hazardous processes such as those that produce VOC's and deplete ozone.
- d. Shipping packing materials shall be reusable and/or recyclable.

5. Dimensions and Features

- a. Dimensions:
 - i. Overall: Minimum 26"D, 46"W, 18.5"H
 - ii. Overall: Minimum 26"D, 23"W, 18.5"H
- b. Comes with attaching tables. All components can be changed out, replaced, or repaired if damaged without replacing the entire unit. Linking bracket fastens with metal to metal connection
- c. Metal legs come standard with glides adjustable up to 1.25" for leveling.
- d. Removable upholstery covers that are field replacable are available.

6. Surface Materials

- a. Silver metal legs.
- b. Upholstery shall be available in a wide variety of graded-in and COM (Customer's own material)
- c. All selected finishes must be approved by VA Interior Designer

7. Miscellaneous

- a. Manufacturer must have been in business for minimum of 10 years.
- b. Product must be guaranteed in writing to be available for a minimum of 10 years after first order entry.
- c. Product must ship with an option of boxed or blanket wrapped shipment.