Izzy Harter Shapes Fixed Base Square Dining Table, or Equal

1. General

Square Izzy Harter Shapes dining table with located at 1st floor Canteen Dinning Area.

2. Warranty and Testing Requirements

- a. Manufacturer must offer a lifetime warranty that product is free from defects in materials and workmanship (includes shipping, parts and labor for the repair or replacement of defective item.)
- b. Manufacturer certifies that products meet or exceed applicable ANSI/BIFMA standards and testing

3. Environmental Features

- a. Product must be designed and constructed of materials that do not present a significant environmental and human health risk.
- b. Frames are made with recycled steel and are recyclable
- c. Painted components must use powder coat paint, which results in minimal waste and emits no VOCs
- d. Meets BIFMA e3 Sustainable Standards and Level 1 rating.

4. <u>Dimensions and Features</u>

a. Overall

Height: 29" Square: 36" OR Square: 30"

- b. Table top: Options for Laminate and Resin tops
- c. Base: Options for Disc, Dome and X base
- d. Manufacturer to offer table transport

5. Surface Materials

- a. **Tops**: Laminate, linoleum and veneer surfaces are applied to a 1" particle board core, then edged and backed with moisture-resistant coverings to form a completely sealed outside surface. Tops are shipped pre-drilled for easy assembly to bases. When selecting a laminate top with an ApplePly edge, the entire core of the table is ApplePly. The ½" thick laminated glass tops consist of a tough protective interlayer of vinyl (which creates the color) bonded together between two panes of glass under heat and pressure. The edges are rounded and polished.
- b. **Disc Base**: 3/8" thick laser cut steel plate with non-adjustable rubber glides.
- c. **Dome Base**: cast iron with an 18 gauge steel cover and adjustable glides.
- d. **X Base**: 2" O.D. x 14 gauge steel tubing with adjustable glides. The Disc and Dome bases are available in standard 29" height and 42" café height.

6. Miscellaneous

- a. Product is guaranteed to be available for a minimum of 5 years after first order entry
- b. Simple styling coordinates with other outdoor furniture