

## **Salient Characteristics**

---

### **Steelcase Tava Single Seat Armchair, Or Equal**

#### **1. General**

Open arms chair with upholstered seat and back, with wood arms and legs, located in Consult Rooms.

#### **2. Warranty Requirements**

- a. Manufacturer must offer a 15 year warranty that product is free from defects of materials and workmanship (includes shipping parts and labor for the repair or replacement of defective items).
- b. Chair must be warranted to support users a minimum of 250 lbs.

#### **3. Technical Specification and Code Requirements**

- a. Chair must meet or exceed all ANSI/BIFMA X5.1 American National Standard for Office Furnishings-General Purpose Office Chairs.
- b. Chair padding materials and fabric shall contain no halogenated fire retardants. Avoid TB177-2013 and TB-133.
- c. Testing of fabric abrasion, stain resistance, and durability must be documented and available upon request.

#### **4. Environmental Features**

- a. Chair must be designed and constructed of materials that do not present environmental or human health risk such as PVC, CFC, solvent based adhesives, heavy metals (chrome, lead and mercury) and benzene.
- b. Must contain at least 16% recycled content, and be 48% recyclable at end of life
- c. Must be have SCS Indoor Advantage Certification for indoor air quality
- d. Must be constructed free of environmentally hazardous processes such as those that produce VOC's and deplete ozone.
- e. Shipping packing materials shall be reusable and/or recyclable.

#### **5. Dimensions and Features**

- a. Dimensions:
  - i. Overall: Minimum 23.75"D, 24"W, 31"H
- b. Fully upholstered seat and back
- c. Clean-out design between seat and back
- d. Durable spring back construction.
- e. Moisture barrier available
- f. Black glides

#### **6. Surface Materials**

- a. Solid kiln dried ash frame available in a variety of stain finishes.
- b. Seat and Back: Upholstery shall be available in a wide variety of graded-in and COM (Customer's own material)
- c. All selected finishes must be approved by VA Interior Designer

#### **7. Miscellaneous**

- a. Manufacturer must have been in business for minimum of 10 years.
- b. Product must be guaranteed in writing to be available for a minimum of 10 years after first order entry.
- c. Product must ship fully assembled with an option of boxed or blanket wrapped shipment.