

## **Salient Characteristics**

---

### **Versteel TOD Tilt-Nest Tables, or Equal**

#### **1. General**

Rectangular tilt-top nesting tables with casters for Conference / Classrooms and Group Rooms

#### **2. Warranty Requirements**

a. Manufacturer must offer a lifetime warranty that product is free from defects in materials and workmanship (includes shipping, parts and labor for the repair or replacement of defective item.) Exceptions with certain table components may apply.

#### **3. Technical Specification and Code Requirements**

a. Meets or exceeds ANSI / BIFMA 5.5 2008

#### **4. Environmental Features**

a. Minimum 70% recycled content (pre and post-consumer)  
b. Certified as Level 2 (Gold) in BIFMA e3

#### **5. Dimensions and Features**

a. Over-all Height: 29"  
b. Width: 24"  
c. Length: 48" and 60"  
d. Laminate tops have matching PVC edges  
e. Tilt-nest base has upside-down "Y" shape with casters and integral modesty panel  
f. Bases are powder coated steel

#### **6. Construction Method**

a. Heavy welded construction  
b. Bases:  
i. Mounting Brackets: Heavy gauge cold rolled steel  
ii. Leg Tubes: 14 gauge formed hot-rolled steel  
iii. Integral modesty panel: 16 gauge cold rolled steel  
c. Casters  
i. Dual-wheel casters are 50 mm nylon  
d. Tops:  
i. 7/8" thick lightweight plywood core  
ii. High Pressure plastic laminate top surface  
iii. Finished solid wood edge on user side with sloped 'ergo' profile

#### **7. Surface Materials**

a. High Pressure Plastic Laminate, available in a variety of wood grain finishes  
b. Wood veneer over solid stock wood in species matching plastic laminate  
c. Powder coated steel, available in a variety of metallic finishes

#### **8. Miscellaneous**

a. Shipped partially assembled, with legs folded for ease of shipment