PLUMBING FIXTURE SCHEDULE						
PLAN MARK	DESCRIPTION	HOT WATER	COLD WATER	SANITARY	VENT	NOTES
AD-1	AREA DRAIN			4"		
EEW-1	Wall-Mount Eyewash Unit					1/2" TEPID WATER TO TMV-2
EEWS-1	EMERGENCY SHOWER AND EYEWASH					1" TEPID WATER TO TMV-1
OB-1	OUTLET BOX		1/2"			
P804	HOSE BIBB		3/4"			
P3100	HAND WASH LAVATORY	1/2"	1/2"	1 1/2"	1 1/2"	
P4700	MOP BASIN	1/2"	1/2"	3"	2"	
P8150	URINAL		3/4"	2"	2"	
P9050	WALL HUNG WATER CLOSET		1 1/4"	4"	2"	
P9180	WALL HUNG LAVATORY - ADA	1/2"	1/2"	1 1/2"	1 1/2"	
RH-1	ROOF HYDRANT		1"			DRAINLESS, FREEZE RESISTANT.
TMV-1	EMERGENCY TEMPERING VALVE	1"	1"			1" TEPID WATER TO EEWS-1
TMV-2	EMERGENCY TEMPERING VALVE	1/2"	1/2"			1/2" TEPID WATER TO EEW-1

PLUMBING-CIRCULATING PUMP SCHEDULE				
PLAN MARK	GPM (EACH)	FT. HEAD (EACH)	ELECTRICAL DATA HP	NOTES
HWRP-1	3	17	0.166	

PLUMBING-WATER SOFTENER SCHEDULE								
PLAN MARK	CONTROL VALVE SIZE	TYPE	LOCATION ROOM NAME	LOCATION ROOM NUMBER	GRAINS CAPACITY	FLOW RATE CONT.	FLOW RATE PEAK	NOTES
HWS-1	2"	ION	WATER TREATMENT	49C	210000	58	76	BACK WASH 8 GPM RATE ALTERNATING DUPLEX.

PLUMBING-WATER HEATER SCHEDULE										
PLAN MARK	LOCATION ROOM NAME	LOCATION ROOM NUMBER	STORAGE (GAL.)	ELEMENT	ELECTRICAL DATA VOLTAGE	ELECTRICAL DATA PHASE	Hz	FUEL SOURCE	NOTES
DWH-1	WATER TREATMENT	49C	5	1	120	1	60	ELECTRIC	SEE SPECIFICATIONS

PLUMBING-SUMP PUMP SCHEDULE								
PLAN MARK	Description	MAX. GPM	MAX. FT HEAD	ELECTRICAL DATA HP	ELECTRICAL DATA VOLTAGE	ELECTRICAL DATA PHASE	CYCLE	NOTES
SP-1	DUPLEX SUMP PUMP SYSTEM	40	19	0.5	110	1	60 A	TO HAVE CONTROL PANEL WITH ALTERNATING SWITCH, CONTROLS FOR LEVEL CONTROLLER, HIGH WATER ALARM. SEE DETAIL #7 ON SHEET PP-401.

100% CONSTRUCTION DOCUMENTS
FULLY SPRINKLERED

Revisions:	Date

VA

VA NORTHERN INDIANA
HEALTH CARE SYSTEM,
FORT WAYNE
2121 Lake Ave. Fort
Wayne, IN 46805

ARCHITECT/EDITORS:

AMERICAN STRUCTUREPOINT INC.
7260 SHADELAND STATION
INDIANAPOLIS, IN 46256-3957
TEL 317.547.5580 FAX 317.543.0270
www.structurepoint.com

Ross&Baruzzini
8250 Haverstick Road
Suite 285
Indianapolis, IN 46240
317.638.8383

CONSULTANTS:

JEFFREY R. CRAWFORD REGISTERED PE 10404134 STATE OF INDIANA PROFESSIONAL ENGINEER
08/15/14

Drawing Title: PLUMBING SCHEDULES

Approved: Project Director

Project Title: SPS BASEMENT ADDITION
VA PROJECT # 610A4-12-400

Location: 2121 Lake Ave. Fort Wayne, IN 46805

Date: 08/15/2014 | Checked: JDB | Drawn: BLB

Project Number: 2010.00629.0005

Building Number: 01

Drawing Number: PP-501

Office of Construction and Facilities Management

VA Department of Veterans Affairs

C:\Users\bbrooks\Documents\1724-03_Plumbing Central_bbrooks.rvt
8/13/2014 11:33:16 AM

VA FORM 08-6231