

three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
three eighths inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot  
one sixteenth inch = one foot

GENERAL NOTES - DEMOLITION

- A. EXISTING EQUIPMENT SHOWN IS TAKEN FROM AS-BUILT DRAWINGS. UNLESS NOTED OTHERWISE, REMOVE ALL EQUIPMENT WHETHER SHOWN OR NOT. CUT/CAP CONDUITS AT THE AREA OF WORK PERIMETER AND REMOVE CONDUIT WITHIN THE WORK AREA AND REMOVE WIRING COMPLETELY FROM THE ABANDONED CONDUITS.
- B. REMOVE ALL ACCESSIBLE ABANDONED WIRING OR CAP AND LABEL IN JUNCTION BOX FOR RE-USE, IN COMPLIANCE WITH THE NATIONAL ELECTRIC CODE. RAISE ALL EXISTING BOXES AND CONDUITS TO COORDINATE WITH NEW WORK.
- C. MAINTAIN AND RESTORE, IF INTERRUPTED, ALL CONDUITS AND CONDUCTORS PASSING THROUGH RENOVATED AREAS AND SERVICING UNDISTURBED AREAS.
- D. REVIEW EACH RELOCATED SYSTEM WITH VA BEFORE RELOCATING. TEST FOR PROPER OPERATION OF ALL COMPONENTS AND REPORT ANY MALFUNCTIONING COMPONENTS BEFORE RELOCATIONS. CONTRACTOR IS RESPONSIBLE FOR SYSTEMS BEING RESTORED TO PRECONSTRUCTION CONDITION AT COMPLETION OF PROJECT.
- E. COORDINATE WITH VA FOR SHUTDOWN OF EACH REMOVED SYSTEM OR DEVICE.
- F. DETAIL SCHEDULE ALL WORK AREAS FOR SHUT DOWNS AND RELOCATIONS MINIMUM TWO WEEKS IN ADVANCE. PROVIDE CPM SCHEDULE TO COORDINATE WITH PHASING.
- G. EXISTING FIRE ALARM SYSTEM IN WORK AREAS SHALL STAY ACTIVE THROUGHOUT PROJECT UNTIL NEW DEVICES OR TEMPORARY DEVICES ARE INSTALLED AND TESTED. SHUTDOWNS FOR WORK THE THE SYSTEM SHALL BE SCHEDULED WITH THE VA TWO WEEKS IN ADVANCE AND THE SYSTEM RESTORED TO SERVICE AT THE END OF EACH WORK DAY IN ACCORDANCE WITH NFPA 241.
- H. AUDIOLOGY AREA IS ABOVE ON 5TH FLOOR. COORDINATE NOISE PRODUCING WORK WITH THE COR.
- I. EXISTING DEVICES THAT ARE IN LOCATIONS TO BE REUSED SHALL BE REPLACED WITH NEW UNLESS NOTED OTHERWISE. TURN OVER UNUSED REMOVED DEVICES TO OWNER.

FIRE ALARM DEMOLITION LEGEND

- PA SPEAKER
- SYSTEM SMOKE DETECTOR
- FIRE ALARM SPEAKER
- FIRE ALARM STROBE
- FIRE ALARM PULL STATION
- FIRE ALARM COMBINATION SPEAKER STROBE



1 4TH FLOOR FIRE ALARM DEMOLITION PLAN - WING B  
F1.31 SCALE: 1/8" = 1'-0"

CONSULTANTS:		ARCHITECT/ENGINEERS:		Drawing Title		Project Title		Project Number		Office of Construction and Facilities Management	
Hyman Hayes		Sigma Psi Consulting		4th FLOOR FIRE ALARM DEMOLITION PLAN - WING B		Renovate 4B for Community Living Center (CLC)		VA 528A8-12-890		Department of Veterans Affairs	
6 WEMBLEY COURT, ALBANY, NEW YORK 12205 (518) 452-3470		4 Collamer Road, Malta, NY 12020 PH (518) 581-9428 FX (518) 580-9325		Approved Project Director		Stratton VA Medical Center		Building Number 1			
1511 Route 22 - Suite C-24 Brewster, New York 10899 p: 845.278.7710 f: 845.278.7750 adelaidelc.com				Date 10-22-2014		Location Albany, New York		Drawing Number F1.31			
Revised Per Comments				Checked -		Drawn -		Dwg. 40 of 79			
100% SUBMISSION											
Date 10/22/14											
Revisions:											