


three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot

GENERAL NOTES - DEMOLITION

- A. EXISTING EQUIPMENT SHOWN IS TAKEN FROM AS-BUILT DRAWINGS. UNLESS NOTED OTHERWISE, REMOVE ALL EQUIPMENT WHETHER SHOWN OR NOT. CUT/CAP CONDUITS AT THE AREA OF WORK PERIMETER AND REMOVE CONDUIT WITHIN THE WORK AREA AND REMOVE WIRING COMPLETELY FROM THE ABANDONED CONDUITS.
- B. REMOVE ALL ACCESSIBLE ABANDONED WIRING OR CAP AND LABEL IN JUNCTION BOX FOR RE-USE, IN COMPLIANCE WITH THE NATIONAL ELECTRIC CODE. RAISE ALL EXISTING BOXES AND CONDUITS TO COORDINATE WITH NEW WORK.
- C. MAINTAIN AND RESTORE, IF INTERRUPTED, ALL CONDUITS AND CONDUCTORS PASSING THROUGH RENOVATED AREAS AND SERVICING UNDISTURBED AREAS.
- D. REVIEW EACH RELOCATED SYSTEM WITH VA BEFORE RELOCATING. TEST FOR PROPER OPERATION OF ALL COMPONENTS AND REPORT ANY MALFUNCTIONING COMPONENTS BEFORE RELOCATIONS. CONTRACTOR IS RESPONSIBLE FOR SYSTEMS BEING RESTORED TO PRECONSTRUCTION CONDITION AT COMPLETION OF PROJECT.
- E. COORDINATE WITH VA FOR SHUTDOWN OF EACH REMOVED SYSTEM OR DEVICE.
- F. DETAIL SCHEDULE ALL WORK AREAS FOR SHUT DOWNS AND RELOCATIONS MINIMUM TWO WEEKS IN ADVANCE. PROVIDE CPM SCHEDULE TO COORDINATE WITH PHASING.
- G. EXISTING FIRE ALARM SYSTEM IN WORK AREAS SHALL STAY ACTIVE THROUGHOUT PROJECT UNTIL NEW DEVICES OR TEMPORARY DEVICES ARE INSTALLED AND TESTED. SHUTDOWNS FOR WORK THE THE SYSTEM SHALL BE SCHEDULED WITH THE VA TWO WEEKS IN ADVANCE AND THE SYSTEM RESTORED TO SERVICE AT THE END OF EACH WORK DAY IN ACCORDANCE WITH NFPA 241.
- H. EXISTING DEVICES THAT ARE IN LOCATIONS TO BE REUSED SHALL BE REPLACED WITH NEW UNLESS NOTED OTHERWISE. TURN OVER UNUSED REMOVED DEVICES TO OWNER.



1 4TH FLOOR FIRE ALARM DEMOLITION PLAN - CORE
F1.4 SCALE: 1/8" = 1'-0"

REVISIONS	DATE
REVISD PER COMMENTS	03/26/15
REVISD PER COMMENTS	12/11/14
100% SUBMISSION	10/22/14

CONSULTANTS:

Hyman Hayes

6 WENDLEY COURT, ALBANY, NEW YORK 12205
(518) 432-3410

Adelaide
Environmental Health Associates, Inc.

1511 Route 22 - Suite C-24
Brewster, New York 10509
p: 845.278.7710 f: 845.278.7750
adelaidelic.com

ENGINEERING VENTURES PC

208 Flynn Avenue, Suite 2A, Burlington, VT 05401
tel: 802.863.6222 • fax: 802.863.6360
85 Mechanic Street, Suite 350A, Lebanon, NH 03766
tel: 603.442.9331 • fax: 603.442.9331



ARCHITECT/ENGINEERS:

Sigma Psi Consulting
Mechanical, Electrical, Plumbing Engineers, PLLC

4 Collamer Road, Malta, NY 12020 PH (518) 581-9428 FX (518) 580-9325

Drawing Title
4th FLOOR FIRE ALARM DEMOLITION PLAN
- CORE

Approved Project Director
Chris J. J...

Project Title
Renovate 4A for Community Living
Center (CLC)
Stratton VA Medical Center

Location
Albany, New York

Date
10-22-2014

Checked
-

Drawn
-

Project Number
VA 528A8-12-801

Building Number
1

Drawing Number
F1.4

Page 63 of 17

Office of
Construction
and Facilities
Management

Department of
Veterans Affairs