

Principals:

Mark D. Fellenzer, P.E., LEED AP
John D. Fellenzer, P.E., MBA

Founder:

Archie D. Fellenzer, Jr., P.E.
(1924 - 2014)

May 28, 2015

FE Project 13-251

BIDDING RFI's – PHASE 4

Questions and Responses

1. Bid Drawing E105 (Building 1 phase 4 BID OPTION 2 Switchboard A New Plan: Indicate provision of Temporary switchboard T1 during replacement of existing switchboard A sections A & B with respective new Switchboard A sections. Please provide us the detailed drawing & specification of this temporary switchboard T1.

Response: Temporary switchboards are to be as required to provide continued electrical service and circuit protection to all loads and feeder served by each switchboard as shown on drawings, indicated in the specifications and in accordance with the temporary power plan developed by the contractor in coordination with the VA COR. See individual switchboard replacement drawings for specific information for each switchboard.

2. Building E108 (Building 1 phase 4 base bid switchboard D New Plan: Indicate provision of Temporary switchboard during replacement of existing switchboard D sections A & B with respective new Switchboard D sections. Please provide us the detailed drawing & specification of this temporary switchboard.

Response: See response to Question 1.

3. Bid Drawing E-602 (Electrical new one line diagram) Keyed Note 2: Please provide us the sizes of all new conduits in new chases.

Response: Conduit sizes are indicated on Drawing E-606.

4. Bid Drawing E-606: Keyed notes 1, C, D, F, L & LO: No conduit & wire sizes indicated for these keyed notes. Please provide the feeder sizes.

Response: See conduit schedule on Drawing E-001 for schedule of wire and conduit for all feeders not otherwise identified on each drawing.