

17 NOTES

- ALL NEW CEILING HEIGHT SHALL MATCH EXISTING CEILING HEIGHT, UNLESS OTHERWISE NOTED. EXISTING CEILING HEIGHT IS 9'-0"; VERIFY EXACT CEILING HEIGHT IN FIELD.
- LAYOUT CEILING TILE FROM CENTER OF ROOMS, BOTH DIRECTIONS, UNLESS OTHERWISE NOTED.
- MODIFY EXISTING FINISHED CEILING SYSTEM AND PROVIDE NEW SUPPORTS AND BRACINGS AS REQUIRED. LOCATE BRACINGS TO AVOID INTERFERENCES WITH DUCTWORK, PIPES, AND CONDUITS, ETC.
- ALL CEILING FIXTURES INCLUDING LIGHTING FIXTURE, FIRE SPRINKLER, SMOKE DETECTOR, AND OTHER CEILING MOUNTED FIXTURES SHALL BE LOCATED AT THE CENTER OF THE CEILING TILE, UNLESS OTHERWISE NOTED.
- PROVIDE ACCESS DOORS AS REQUIRED FOR ACCESS TO UTILITIES, SMOKE FIRE DAMPERS, CONTROLS, EQUIPMENT AND AS REQUIRED BY CODES. ACCESS DOOR LOCATIONS ARE NOT ALL SHOWN ON REFLECTED CEILING PLAN.
- PROVIDE SEISMIC BRACINGS PER DETAILS AND SPECIFICATIONS (LOCATIONS NOT SHOWN). LOCATE BRACING TO AVOID INTERFERENCES WITH DUCTWORK, PIPES, CONDUITS, ETC.
- COORDINATE ALL NEW DUCTWORK TO AVOID INTERFERENCE WITH CEILING SUPPORT SYSTEM. IF ANY INTERFERENCE OCCURS, CONTRACTOR SHALL BE RESPONSIBLE TO MAKE ALL NECESSARY CORRECTION WITHOUT INCREASE TO THE CONTRACT SUM.
- EXIT SIGN, SPRINKLER HEADS, AND OTHER CEILING ACCESSORIES SHOWN ARE AT CRITICAL LOCATIONS ONLY. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR AREAS WHERE THE ABOVE ITEMS ARE NOT SHOWN. PROVIDE SPRINKLER HEADS AT LOCATIONS PER CODE REQUIREMENTS AND APPROVED SHOP DRAWINGS.
- ADJUST SPRINKLER HEAD LOCATIONS TO CLEAR OTHER CEILING FIXTURES AND ELEMENTS AS REQUIRED. PROVIDE ADDITIONAL SPRINKLER HEADS AS REQUIRED.
- REFER TO MECHANICAL DRAWINGS FOR LOCATIONS OF MECHANICAL SYSTEMS, MECHANICAL DUCTS AND SYSTEMS SHOWN ARE DIAGRAMMATIC AND FOR REFERENCE ONLY.
- ADJUST LOCATIONS OF ALL SUPPORT MEMBERS INCLUDING STUDS, UNISTRUTS, BRACES, ETC. TO LAYOUT ALL OVERHEAD UTILITIES PRIOR TO THE INSTALLATION OF CEILING AND PARTITIONS FRAMING WORK. FRAMING DETAILS SHOWN ARE MINIMUM STUD SIZES AND MAXIMUM SPACING REQUIREMENTS. RECONFIGURE FRAMING DETAILS AND/OR PROVIDE ADDITIONAL FRAMING MEMBERS AS REQUIRED TO RECONCILE FIELD CONDITIONS AS REQUIRED.
- ALL REMOVAL, MODIFICATION, ADJUSTMENT AND RE-INSTALLATION OF THE EXISTING WINDOW SHADE SYSTEM SHALL BE PERFORMED BY EXISTING WINDOW SHADE MANUFACTURERS AUTHORIZED INSTALLER AND ALL MODIFICATIONS AND ADJUSTMENTS TO THE EXISTING SHADE SYSTEM SHALL NOT VOID EXISTING WARRANTY OF THE WINDOW SHADE SYSTEM. CONTRACTOR SHALL REPLACE EXISTING SHADE WITH NEW SHADE SYSTEM AT NO ADDITIONAL COST TO THE CONTRACT IF THERE IS ANY DAMAGE TO THE EXISTING SHADE SYSTEM AS A RESULT OF THE CONTRACTOR'S WORK IN THIS CONTRACT. REPLACEMENT SHADE SHALL MATCH EXISTING SHADE SYSTEM IN TYPE, CONSTRUCTION, MATERIAL, SIZE AND FINISH.
- NO ACCESS PANEL SHALL BE ALLOWED IN ALL LINEAR WOOD CEILING AND SOFFIT AREA. COORDINATE ALL MECHANICAL, PLUMBING, ELECTRICAL AND ALL OTHER OVERHEAD UTILITIES FOR ACCESS AT ACoustical CEILING TILE AREA ONLY.




4 PARTIAL ENLARGED THIRD FLOOR REFLECTED CEILING PLAN
1/4" = 1'-0"

FULLY SPRINKLERED CONSTRUCTION DOCUMENTS - BID SET

Revisions:	Date
1 AMENDMENT NO.5	5-29-2015

CONSULTANTS:



ARCHITECT/ENGINEERS:

MEL
architecture + interiors

239 9TH STREET, SUITE 201
SAN FRANCISCO, CA 94103
T (415) 682-7330 F (415) 682-7330
www.melarch.com

11-30-13
RENEWAL DATA
MEL/MEI CHAN
C-20950
LICENSED ARCHITECT
STATE OF CALIFORNIA

Drawing Title
PARTIAL ENLARGED THIRD FLOOR REFLECTED CEILING PLAN

Approved: Project Director

Project Title
RENOVATE SLEEP ROOMS FOR CLINICAL SUPPORT SERVICES BUILDING 101

Project Number
640-12-117P

Building Number
BLDG. 101/3RD FLR.

Location
VAPAHCS - PALO ALTO

Date
SEPTEMBER 30, 2013

Checked
MMC

Drawn
TW

Drawing Number
AS6-1
Dwg. -- of --

Office of Facilities Management

Department of Veterans Affairs