

Request for Information Questions and Answers

Solicitation VA251-15-B-0263

Amendment A00004

Q1: Provide latest results of fire pump test.

A1: Test results are available on drawing LS-002.

Q2: While the fire main is moved should the new lead in to the building for new fire pump be roughed in?

A2: No.

Q3: Specifications included in section 23 25 00 cover hydronic water treatment. Does the VA have a preferred water treatment purveyor?

A3: The contractor is not required to use any specific vendor for chemical water treatment. The site's current vendor for chemical water treatment is HPE, 702 Incentive Drive, Fort Wayne, IN 46825, E-mail: hpe@hpewater.com; Telephone: (260) 497-9500; Fax: (260) 497-9511.

Q4: Is water treatment to be included in the Division 23 scope of work?

A4: All work indicated on the plans and specifications are the responsibility of the resultant contractor, who shall assign work to their subcontractor at their discretion.

Q5: On drawing E002, note 23, states: "Install (8) 4" C underslab from east elec room wall and stubbed out for future electrical service". On drawing EP100, note 21, it states: "Area for (12) 4" C stub-ups". How many conduits are intended to be installed in this location?

A5: Use EP100, note 21, provide (12) 4" C.

Q6: General note 1 on page EP100 states that the SPS equipment will be terminated by the equipment provider. Please confirm that we are not required to supply the whip/flex and wire from the disconnect, junction box to the equipment.

A6: According to Steris Equipment Installation Project Manager, Steris no longer provides the final electrical connection. Steris will only provide final plumbing connections. Therefore, the electrical subcontractor shall be required to provide final connections whip/flex and other required components to all Steris equipment.