SECTION 09 06 00 SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

Section contains coordinated color systems in which requirements for materials specified in other sections of the Specification and/or shown on the Drawings are identified by color codes and/or paint finishes.

1.2 MANUFACTURERS

· Manufacturers' trade names and numbers used herein identify colors, finishes, textures and patterns. Subject to approval of the Contracting Officer, products of other manufacturers will be considered, provided they are equivalent to the color, finishes, textures and patterns of the manufacturers listed, and meet the requirements of the technical Specifications and Drawings, unless otherwise stated.

1.3 COLOR SELECTIONS

• It is the intent of this section to define the majority of materials selected. However, the Architect/Interior Designer will make final selections from submittals of manufacturers' standard or premium colors as defined in the section and assemble a color board to be reviewed by the VA Interiors Department and Resident Engineer. A final Approved Color Schedule will then be given to the General Contractor.

1.4 SUBMITTALS

• In accordance with SECTION 01 33 23, SAMPLES AND SHOP DRAWINGS, furnish quadruplicate samples for color approval of all materials, colors and textures specified in this section.

1.5 INDEX AND SPECIFICATION REFERENCE

2.1 PAINT:

2.1.A Painting

09 91 00 2.2 FLOORING: 2.2.ACeramic Porcelain Tile 09 65 13 Resilient Sheet Flooring and Accessories 2.2.B 09 30 13 2.2.C Rubber and Vinyl Tile 09 65 19 2.2.D Entryway System 12 48 13 2.2.E Resilient Stair Treads, Risers, and Skirting 09 65 13 2.3 WALLS: 2.3.A Resilient Base and Accessories 09 65 13 2.3.B Ceramic Base Tiles 09 30 13

Replace VA Dom B203 Final Submittal 4 August 2014 2.3.C Doors and Frames 1. Interior Flush Wood Doors 08 14 13 2. Impact-resistant Doors 08 14 00 3. Hollow Metal Doors and Frames 08 11 13 4. Access Doors and Frames 08 31 33 5.Aluminum-Framed Entrances & Storefronts 08 41 13 2.3.D Wall Protection 1. Corner Guards 10 26 00 2. Wall Guards, Crash Rails, and 10 26 00 Handrails Rigid Sheet Wall Covering Wainscot 3. 09 72 00 System High Impact Wall Covering (FRP) 4. 10 26 00 2.3.E Door Kick Plates 08 71 00 2.3.F Vinyl-Coated Fabric Wall Coverings 09 72 16 2.4 CEILINGS: 2.4.A Acoustical Ceilings 09 51 00 2.4.B. Gypsum Board 09 29 00 2.5 CASEWORK AND MILLWORK: 2.5.A Plastic Laminate - Bathroom Lavatory Tops 12 34 00 2.5.B Wood Millwork/Trim 06 20 00 Plastic Laminate Window Sills 2.5.C 06 20 00 Manufactured Plastic Casework 2.5.D 12 34 00 2.6 LIGHT FIXTURES 2.6.A Interior 26 51 00 2.6.BExterior 26 56 00 2.7 MISCELLANEOUS ITEMS: 2.7.A Miscellaneous Wood and Metal requiring paint 1. Fire Extinguisher Cabinets 10 44 13 2. Metal Handrails 05 50 00

3. Supply and Return Grills

23 37 00

2.8 EXTERIOR MATERIALS:

2.8.A		rior Materials Unit Masonry			
		-	04	20	00
		Vinyl Windows	08	53	13
	3.	Asphalt Shingle Roofing	07	31	13
	4.	Glass	0.8	80	0.0
	5.	Sealants			
	6.	Flashing and Sheet Metal	0 /	92	00
	7.	Siding and Trim	07	60	00
		-	07	40	00
	8.	Aluminum Glazing Systems	08	41	13
	9.	Louvers and Wall Vents	08	90	00
	0.00				

PART II - PRODUCTS

2.1 PAINT

A. Painting: Provide paint materials in the following color ways

Code	Mfr.	Color No./Name	General Location
			(See Color Group Schedule)
P-1	Rodda Paint	8459 Travertine Trail	All walls throughout, unless otherwise indicated on Drawings
P-2	Rodda Paint	8457 Bamboo Beach	All hollow metal door frames throughout
P-3	Rodda Paint	8265 Brookview	2 nd Floor Corridor Accent Color at Residential Wing Entries of Connecting Corridors
P-4	Rodda Paint	OW 108 Birch Bay	All gypsum board ceilings throughout, except in Connecting Corridors
P-5	Rodda Paint	8263 Romantic Mood	Handrails in Staircases
P-6	Rodda Paint	8574 Burnished	Below chair rail in TV

		Caramel	Rooms and Break Room 174
P-7	Rodda Paint	OW 136 Pebble Bluff	Above wainscot system and at soffits in Connecting Corridors

B. Paint Finishes:

- Typical wall paint finish: Eggshell (Gloss Level 3).
- Bathrooms wall paint finish: Epoxy (Gloss Level 5).
- Typical trim paint finish: Satin (Gloss Level 5).
- Typical ceiling paint finish: Matte (Gloss Level 1/Gloss Level 2).
- Rodda Vapor Block primer on interior side of all exterior walls and underside of roof structure.

C. See Section 07 21 13, THERMAL INSULATION.

D. See Section 09 91 00, PAINTING for requirements for Green Globe Credits

2.2 FLOORING - INTERIOR

A. Ceramic Floor Tile (CT):

- Glazed porcelain tile with a slip resistant finish to meet ANSI A137.1 Section 6.2.2.1.10, required for level of performance ≥.45 (DCOF wet condition) for level bathing areas, matching 6" X 12" coved base, and 1" X 6" outside corners.
 - 2. Tile:

Code	Mfr.	Style	Color	Size	Location
CT	Daltile	Colour Scheme	B932 Suede Gray Speckle	12″X 12″	Bathrooms

3. Grout: Laticrete SpectraLOCK-1200 Series 3/16" grout joints.

Color: 24 Natural Gray 4. Waterproofing Membrane: Custom Building Products RedGard Waterproofing and Crack Prevention Membrane -F122-09 (Tile Council of North America) 5. Installation Method: First Floor (plywood subfloor) -F144-09 (Tile Council Of North Amercica) First Floor (concrete subfloor)-F122-09 Second Floor - F121-09

B. Resilient Sheet Flooring and Accessories

1. Welded Sheet Flooring:

Code	Mfr.	Style	Color	Location
------	------	-------	-------	----------

4 August 20				
WSF-1	Mannington Commercial	Primus Framework	ALL 101 Bark	Accent color in Connecting Corridors C1/C12
WSF-2A	Mannington Commercial	Primus Lacosta	ALL 131 Suede	Connecting Corridors C1/C1A/C1B/C2/C2A, ST1C/ST2C,Storage 275
WSF-2B	Mannington Commercial	Primus Lacosta	ALL 134 Cherry Wood	Accent color in Connecting Corridors
WSF-3	Mannington Commercial	Assurance II	16306 Toasted Sesame	Housekeeping 119,151,223,251 Storage 120,172,224

 Welding Rods: Mannington Commercial - match color to field

vinyl.

3. Sheet Vinyl to Ceramic Tile Transition Strips: Burke Flooring #365 "Cerco-Edge T", 1-1/2" or #940 Standard Edge T, 1-1/8" (size as appropriate for field conditions). Snap-s in molding with metal track - vinyl color #660 Rocky (Slate).

C. Vinyl and Rubber Tile and Accessories 1. Vinyl Tile

Code	Mfr.	Color	Size	Location
VT-1	Amtico Collection	Wood Norwegian Maple AROW8030	6″x36″	Bedrooms, TV Rooms
VT-2	Amtico Collection	Stone Riverstone Quarry AROSRS43	18″x18″	Residential Corridors C1N/C1S/C2N/C2S, SSA Office 102/202, Office 103, Office 121, IT Office 122, Break 174,Office 213/263, ST1N/E/S ST2/N/E/S
VT-3	Amtico Collection	Stone Stria Basalt AROSMS43	18″x18″	Laundry 104,Electric 124/226,Storage 201

Vinyl tiles 18" x 18" to be installed in a diagonal stack bond pattern;
6" x 36" strips to run parallel to outside wall.

2. Welding Rods: Mannington Commercial - match color to field or accent vinyl where appropriate.

Replace VA Dom B203 Final Submittal 4 August 2014 3. Rubber Tile

Code	Mfr.	Style	Color	Location
RT	Roppe	SafeTCork Rubber #994 Raised Square 12"x12"	150 DARK GRAY	Stairwell Intermediate Landings ST1N/ST1E/ST1S

D. Entryway System

Mfr.	Style	Color	Location
CS Group	GridLine G6P ¾″ Angle Frame	Standard Type 304 Stainless Steel	Exterior
CS Group	PediTred LP G3G3MHCLB	Frame: Standard Mill Insert: #9322 Slate	Interior
	CS Group	CS Group CS Group CS Group CS Group PediTred LP	CS Group GridLine G6P %" Angle Frame CS Group PediTred LP Frame: Standard Mill

E. Resilient Stair Treads, Risers, and Skirting:

Code	Mfr.	Style	Color	Location
RST	Roppe	SafeTCork Rubber Treads #994 Raised Square	P150 DARK GRAY	Stairwells STIC/STIN/STIE/STIS

2.3 WALLS

A. Resilient Base and Accessories:Resilient Cove Base:

Code	Mfr.	Color	Size	Location
RB-1	Forbo Wall Base	C-77 Silver Birch	4″	All locations except stair landings
RB-2	Roppe	150 Dark Gray	4″	Stairwell landings

B. Ceramic Base Tiles:

- Dal Tile color B906 Suede Gray. Provide special cove base with out-corners (#PC-C9TB) and bull nose top, where required.
- Finish size: 6" X 12" cove base with bull nose top Dal Tile #PC-36C9TB.
- Grout to match floor grout.

C. Doors and Frames:

Door & Frame System	Description	Type of Finish
White Birch Doors	Premium Grade, Rotary Select Cut	Factory finish (FACT), select from manufacturer's finishes
Impact- resistant Doors	C/S Acrovyn FD5-60PP and FSC PC5-20PP	C/S Avrovyn PVC-free laminate: Chameleon Faux Wood, #372 Classic Maple
Hollow Metal Frames	Shop Finished, Field Spray Paint	See Color Group Schedule
Wood and Steel Painted Doors	Field Paint	Paint to match wall - see Color Group
Access Doors and Frames	Factory Primed, Field Spray Paint	Schedule
Aluminum Doors	Clear Anodized	See Sheet A3.2 Door Schedule and product specification

D. Wall Protection: 1. Corner Guards:

	Manufacturer	Style	Color	Location
CG-1	C/S Acrovyn	SM-20N 3" X 3" X 36", 90 degrees	Acrovyn 4000 103 Beige	Corridors,C1A, C1N, C2, C2S TV Rooms, Bedrooms, SSA Offices 102, 202, Office 121, IT Office 122, Storage 172, Break 174, Storage 224, Stairs ST1N, ST1S
CG-2	C/S Acrovyn	VA-034N Tape-on Corner Guards - 3/4" X 3/4" X 36" - Field Trim	Acrovyn 4000 103 Beige	Corridors C1S, C1N, C2S, C2N

2. Wall Guards (Crash Rails and Handrail/Wall Guard):

Code	Manf.	Style	Color	Location
WG-1	C/S Acrovyn	SCR-40N 4" Crash Rail	Acrovyn 4000	Corridors C1S, C1N, C2S, C2N

4 August 2	-014			
			#103 Beige	
WG-2	C/S Acrovyn	SCR-40N 4" Crash Rail	Acrovyn 4000 Chameleon Collection #372 Classic Maple	TV Rooms 118/152/222/252 Corridors C1,C1A,C1B,C2,C2A Recycle area
WG-3	C/S Acrovyn	FR-125N 1-1/8" Crash Rail	Acrovyn 4000 Chameleon Collection #372 Classic Maple	Corridors C1A, C1B,C1S, C1N, C2A, C2S, C2N
HR	C/S Acrovyn	P-RSA Platform Handrail w/Acrovyn Crash Rail	Handrail: Stainless Steel Brackets: 008 Weathered Iron Crash Rail: Chameleon Collection #372 Classic Maple	Corridors C1,C1A,C1B, C2, C2A

3. Rigid Sheet Wall Covering Wainscot System (RSWS): a. Glued-up Rigid Sheet Wall Covering -CS/Acrovyn, .040" Rigid Acrovyn 4000 Sheet, #513 Khaki Brown. b. 2" X 3/8" Vertical and Horizontal Engineered Moldings from Acrovyn's "Saratoga" Wainscot System -CS/Acrovyn,#196 Fawn. Provide manufacturer's pre-fabricated outside corners where needed. c. Locations: Connecting Corridors C1, C1A, C1B, C2, C2A, at conditions specified where no handrail occurs.

4. High Impact Wall Covering (FRP):

Manufacturer	Material	Color	Location
Crane Composites (Kemlite)	Glasbord	Pebbled Embossed Finish, Colonial White 83.	Housekeeping 119, 151, 223, 251

E. Door Kickplates:

Manufacturer	Material	Location
Ives	Stainless Steel	Public Zones
	.060" thick	

	.060" thick	
	Brown self-	Residential Zones
Ives	adhesive	90-minute wood doors
	mounted	3-hour metal doors
	plastic	

Ives	.125" thick Brown self- adhesive mounted plastic	Residential Zones Non-rated
------	--	--------------------------------

F. Vinyl Coated Fabric Wallcovering:

See elevations and plans for exact locations of each Wall Covering.

Code	Manufacturer	Style	Color	Location
WC-1	Bolta	Hayfield	BB-HF-03 4495 Oatmeal	Wainscot in Corridors C1S/C1N/C2S/C2N
WC-2A	Bolta	Hayfield	BB-HF-24 Slate	Corridor side of
WC-2B	Bolta	Hayfield	BB-HF-07 Twine	Resident Entries - see F2.1 and
WC-2C	Bolta	Hayfield	BB-HF-14 Pecan	F2.2 for location of each color
WC-2D	Bolta	Hayfield	BB-HF-12 4495 MAPLE SUGAR	00101

2.4 CEILINGS

- A. Acoustical Lay-in Ceiling:
 - Manufacturer: Armstrong Cirrus Second Look II #513
 - Size: 2' X 4' X ¾" Scored for 2' X 2' appearance, Beveled Tegular Edge.
 - Color: White
 - Suspension System: Armstrong Prelude #XL HRC 15/16"
- B. Gypsum Board Ceilings:

All locations as shown on drawings: Painted per COLOR GROUP SCHEDULE, unless otherwise noted.

2.5 CASEWORK AND MILLWORK

A. Plastic Laminate - see drawings for plastic laminate casework.

Code	Manufacturer	Color	Location
HPDL	Formica	7708-58 Flax Gauze	All Resident Bathrooms and 123, 225 Staff Toilet, Laundry 104, Break 174

	HPDL	Pionite	WX041 Suede Anigre	TV Room 118/222/252 , SSA Office 102/202, IT Office 122,
--	------	---------	--------------------	--

B. Wood Molding/Trim

Code	Style	Finish	Location
WT-1	Crown Molding: Westgate Hardwoods #CR-11	Solid Birch or maple -finish to match VA B205	Crown Molding at Resident Corridors C1S, C1N, C2S, C2N

Additional Wood Trim: Above Chair Rail in C1S, C1N, C2S, C2N and Top Cap on low walls of Stairwells - Solid birch or maple, clear finish.

- C. Windows:
 - MechoSystems ThermoVeil Vertical Privacy Weave Shades, color 0901 White/White.
 - Trim: Gypsum Board returns to window frames no trim.
 Sill: Solid Surface

Code	Manufacturer	Color/Finish	Location
SO-1	InPro Corporation	BioPrism Sandbar P9016	Window sills in Residential wings and Offices
SO-2	InPro Corporation	BioPrism White Sand P9002	Window sills in Connecting Corridors

D. Manufactured Plastic Casework (MVL):

- 1. Plastic Laminate: Pionite "Anigre" WX041, suede.
- 2. Hardware: 3 $\frac{1}{2}''$ Wire Pulls for all drawers and doors.

3. Tackboards: Guilford of Maine, "Belgrade" Style 4052, color 097 Wheat. OTHER CONTRACT.

2.6 LIGHT FIXTURES

A. Interior

Туре	Manufacturer	Number	Color
A	Lithonia Lighting	2AV-G-2-32-MDR-SMD- 120-GEB10IS	White
В	Lithonia Lighting	UNS-2-32-120-GEB10IS- HC36-WGCUN	White

+ August 20	17		
С	Lithonia Lighting	20GTL-4-40L-LP840- N80EMG	White
D	Lithonia Lighting	LB-2-32-120-GEB10IS	Factory Finish
Fl	Kenall	MedMaster Auracyl Sconce MAS813-S-OL-CS-1- 26QD	Finish: Cool Satin Lens: Oyster Linen
F2	Kenall	MedMaster Auracyl Sconce MAS813- S-OL-CS-1- 13QD	Finish: Cool Satin Lens: Oyster Linen
G	Gotham	EVO-41/10-6AR-MVOLT WITH NSP5-D-ER-KIT	Factory Finish
J	Lithonia Lighting	11928-WH-120-GEB10IS	White
K	Alkco Lighting	HZN2T8-11-120-SWH-LS	Soft White
L2	Lithonia Lighting	STL4-40L-D40-LP840- N80EMG	White
М	Lithonia Lighting	FMSATL-13-148-40-BZA	Antique Bronze
M2	Lithonia Lighting	FMSATL-16-208-40-BZA	Antique Bronze
Q1	Lithonia Lighting	WL2-12L-D13-LP840- N100EMG-DIM10	White
Q2	Lithonia Lighting	WL4-41L-D43-LP840- N80EMG-DIM10	White
U	Lithonia Lighting	UCLD-24-WH	White
X	Lithonia Lighting	LE-S-BZ-1-G-120	Dark Bronze

B. Exterior

Туре	Manufacturer	Number	Color
Н	Lithonia Lighting	VGR1-32TRT-120-DDBT- LPI	White
N	Performance in Lighting	Kyro 1 LED head with 12' pole	Matte Gray

Р	Lithonia	TWS 42TRT 120	Dark Bronze
	Lighting		

2.7 MISCELLANEOUS ITEMS

A. Miscellaneous Wood and Metal Requiring Paint: Grilles, access panels, pipes, except specific colors required by Section 09 91 00, and conduits (ferrous and nonferrous), heating, ventilating, and air conditioning units and connections, etc. - color to match adjoining surface. Semigloss texture.

- 1. Fire Extinguisher Cabinets Stainless Steel finish.
- 2. Interior Staircase Metal Handrails P-5

3. Supply and Return Grilles - match to wall or ceiling paint on which grilles occur.

2.8 EXTERIOR/GROUNDS

A. Masonry Units:

1. Face Brick: Mutual Materials, blend to match Building 204.

- 25% Autumn Blend Cross Set
- 57% Columbia Red
- 15% Ruby
- 3% Burnt
- Mortar: Tint mortar to match Building 216 ("Davis Brown").
- B. Vinyl Window Frames:

Milgard Classic Series: "White".

C. Roofing:

IKO Marathon Green (Match adjacent Building 216).

- D. Glass:
 - a. Insulated glass at all exterior locations.
 - b. PPG (Pittsburgh Glass) clear, outer lite.
 - c. Low-E inner lite; coating in No. 3 position.
- E. Sealant
 - 1. At Brick: Tremco "Redwood/Tan".

2. At Siding: GE "White".

- F. Flashing and Sheet Metal:
 - 1. Hanging Gutters: Low Gloss White.

- 2. Downspouts: Match hanging gutter color.
- 3. Valley flashing and other flashing next to the shingle roof:
 - a. Green (70% PVDF).
- G. Cement Board Siding and Soffits:
 - 1. Field paint to match adjacent buildings (white).
- H. Exterior Trim:
 - 1. AZEK Cellular PVC: "White"
- I. Aluminum Glazing System:
 - 1. Doors: Clear Anodized finish
 - 2. All other exposed extrusions: Clear Anodized finish
- J. Steel Exterior Crawlspace Access Doors: Galvanized finish
- Metal Railings finish Match to dark green Campus standard
- Bicycle Rack: Galvanized
- Metal Louvers: Match adjacent wall color.

PART III - REFERENCE

• FINISH SCHEDULE ABBREVIATIONS AND SYMBOLS

• Finish Schedule Abbreviations:

	Description
С	Concrete
CG	Corner Guard
CPT	Carpet Tile
СТ	Ceramic Tile (Floor and Base)
ES	Entryway System
FACT	Factory Finish
FRP	Fiberglass Reinforced Plastic Panels
G	Grout
GL	Glass
GWB	Gypsum Wallboard
HPDL	Plastic Laminate
HR	Handrail
ICB	Integral Cove Base

2014	
MAT	Material
MVL	Manufactured Plastic Casework
NF	Natural Finish
P	Paint
PLWD	Plywood
RB	Resilient Base
RST	Resilient Stair Tread and Accessories
RT	Rubber Tile
SO	Solid Surfacing
SUSAC	Suspended Acoustical Ceiling
W	Wood
WC	Wall Covering
WG	Wall Guard
WSF	Vinyl Sheet Flooring (Welded System)
WT	Wood Trim

3.2 INTERIOR FINISHES - COLOR GROUP SCHEDULE

General Finishes Notes:

- For all ceramic tiles, sheet vinyl floors, vinyl tile floors, and entryway systems review the Floor Finishes Plans (F1.1/F1.2) for locations and patterns.
- For all paint, review the Specification Reference 2.1.A and Wall Finishes Plans (F2.1/F2.2) for paint locations.
- For all wall coverings, review the Wall Finishes Plans (F2.1/F2.2) and Specification Reference 2.3.F.
- Confirm location and type of casework (built-in and modular) in Interior Elevations
 (A8.1/A8.2/A8.3/A8.4) and Enlarged Floor Plan
 (A2.10/A2.12), which take precedence over casework
 descriptions in this schedule.
- Verify existence and location of corner guards, wall guards and chair rails, handrails, wainscot system, and high-impact wall covering (FRP) on Wall Finishes Plans (F2.1/F2.2) and Interior Elevations (A8.1/A8.2/A8.3/A8.4), which take precedence over listings in this schedule.
- Verify type and location of doors and door frames on Door Schedule A3.2 which takes precedence over listings in this schedule.

GROUP #1 - RESIDENT CORRIDORS

Location	C1S/C1N and C2S/C2N
Doors	Premium grade of white Birch door skins, FACT, at all Bedroom and TV entrances
	Impact-resistant doors at entries to stairs and at Housekeeping rooms
Door Frame	P-2
Flooring	VT-2
Base	RB-1
	WG-3 Crash Rail above
Chair Rail	WG-1 with WT Wood trim above
Wainscot Wall Covering	WC-1
Corner Guard	CG-1 and CG-2 where indicated on Wall Finishes Plan
Walls	P-1 above Wainscot
	WC-1 where indicated on Wall Finishes Plan
Wall Covering at Resident Entries	WC-2A/WC-2B/WC-2C/WC2D as shown on Wall Finishes Plans F2.1 and F2.2
Ceilings	SUSAC

GROUP #2 - CONNECTING CORRIDORS

Location	C1/C1A/C1B and C2/C2A
Doors	Impact-resistant for all interior doors Exit doors and trim - FACT
Interior Door Frames	P-2
Flooring	WSF-1/WSF-2B and WSF-2A- See Sheets F1.1 and F1.2 for location of accent patterns
Base	ICB with hardwood trim
Handrail	HR where shown on Drawings
Walls	P-7 above HR RSWS below HR, WG-2 where indicated in Notes
Ceiling	SUSAC and GWB (P-7)
Window Sills	SO-2
RECYCLE	Floor: VT-3 Walls: RSWS, WG-2, P-7 soffit, P-7 on GWB

GROUP #3 - RESIDENT BEDROOMS

Location	All Resident Bedrooms - 1^{st} and 2^{nd} Floors
Doors	Premium grade of white Birch door skins, FACT
Door Frames	P-2
Flooring	VT-1
Base	RB-1
Walls	P-1
Ceilings	P-4 on GWB
Window Sill	SO-1
Casework	MVL-1A or MVL-1B, MVL-2A or MVL-2C, MVL-2B, MVL-3, plus accessories

GROUP #4 - RESIDENT BATHROOMS AND STAFF TOILETS

Location	All Resident Baths, Staff Toilet 123/225
Doors	Resident - Premium grade of white Birch door skins, FACT - Staff - Impact-resistant
Door Frames	P-2
Flooring	CT Glazed Porcelain Tile
Base	6" Cove Base matching Glazed Porcelain Tile with outside corners
Walls	P-1
Ceilings	P-4 on GWB
Countertop and Backsplash	HPDL

group #5 - tv rooms

Location	118/152 and 222/252
Doors	Premium grade of white Birch door skins, FACT
Door Frames	P-2
Flooring	VT-1
Base	RB-1
Walls	WG-2 as chair rail as shown on Elevations P-1 above wall guard, P-6 below
Ceiling	P-4 on GWB @ entry SUSAC in room

Tragaot 2014	
Corner Guards	1 each of CG-1
Window Sills	SO-1
Casework	1 each of MLV-5

GROUP #6 - HOUSEKEEPING AND LAUNDRY

Location	104, 119/151, 223/251,
Doors	Impact-resistant
Door Frames	P-2
Flooring	WSF-3 - Housekeeping VT-3 Laundry
Base	ICB for WSF-3 RB-2 for VT-3
Walls	P-1 FRP wainscot as shown on drawings in Housekeeping Rooms
Casework	3 each of MVL-4 in Housekeeping, see drawing A8.3 for Laundry

GROUP #7 - OFFICES AND BREAK ROOM

Location	102/103/121/122/174/202/213/263	
Doors	Impact-Resistant	
Door Frames	P-2	
Flooring	VT-2	
Base	RB-1	
Walls	P-1	
Corner Guards	1 each of CG-1 in 102/121/122/174/202	
Window Sills	SO-1	
Casework	3 each of MVL-4 in Offices 102, see drawings A8.3/A8.4 for 102/202,122,174	

GROUP #8 - FIRST FLOOR STAIRS

Location	ST1N/ST1E/ST1S/ST1C
Doors and Door Trim	Impact-resistant Doors P-2 trim on corridor doors. Exit doors and trim - FACT
Flooring	ES Entryway System at Exits. VT-2 between ES and Stairs. WSF-2A between ES Stair ST1C

Base	RB-1
Walls	P-1
Corner Guards	CG-1
Ceilings	P-4 on GWB
Metal Handrail	P-5
Window Sills	SO-1

GROUP #9 - SECOND FLOOR STAIRS

Location	ST2N/ST2E/ST2S/ST2W/ST2C
Doors	Impact-resistant
Door Frames	P-2
Flooring	RST w/matching risers and skirting on stairs. RT on intermediate landings. VT-2 @ top landing entry to Residential Corridor WSF-2A @ entry to Stair ST2C
Base	RB-1 RB-2 @ intermediate landings with RT
Walls	P-1
Ceilings	P-4 on GWB
Metal Handrail	P-5
Window Sills	SO-1

GROUP #10 - ELECTRICAL AND STORAGE

Location	Electrical 124/226, Storage 120/172/201/224/275
Doors	Impact-resistant
Door Frames	P-2
Flooring	VT-3 - Storage 201, Electrical 124/226 WSF-2A - Storage 275 WSF-3 - Storage 120/172/224
Corner Guards	CG-1 Storage 224
Base	RB-1
Walls	P-1
Ceilings	P-4 on GWB

Location	Sprinkler 101
Doors, Access Doors, and Door Frames	P-2
Ladders	P-2
Flooring	Sealed Concrete
Base	B-1
Walls	P-1
Ceilings	P-4 on GWB

GROUP #11 - SPRINKLER ROOM

- - - E N D - - -

THIS PAGE INTENTIONALLY LEFT BLANK