
\_\_\_\_ \_\_\_\_\_ \_\_\_\_\_



	SE
TY001	SECL
TY100	SECU
TY101	SECU
TY102	SECU
TY102B	SECU
TY102C	SECU
TY102D	SECL
TY103	SECL
TY301	SECL
TY401	SECU
TY402	SECU
	C
	J
A.C.P.	
A.F.F.	
F.O.V.	

I.A.P.

N/A

RECP

S.O.C.

SH

T.B.D.

TW

U.O.N.

V.I.F.

WP

# one eighth inch = one foot 0 4 8 16 0 16

\_\_\_\_\_

Revisions:	Date

# CONSULTANTS:

GUIDEPOST SOLUTIONS LLC

388 17th Street, Suite 230 Oakland, CA 94612 Office: (510) 268-8373 Website: www.guidepostsolutions.com

3	4		5


## **SECURITY SHEET LIST** URITY - SYMBOLS LEGEND AND SHEET INDEX

- URITY SITE PLAN
- JRITY GROUND FLOOR URITY - SECOND FLOOR
- JRITY SECOND FLOOR DEDUCTIVE ALTERNATE #13A FLOOR PLAN JRITY - 2ND FLOOR - DEDUCTIVE ALTERNATE #14 FLOOR PLAN
- URITY DEDUCTIVE ALTERNATE #15 FLOOR PLANS URITY - ROOF
- URITY RISER DIAGRAM (TYPICAL)
- URITY DETAIL SHEET URITY DETAIL SHEET

# SECURITY ABBREVIATIONS

- ACCESS CONTROL PANEL
- ABOVE FINISHED FLOOR
- FIELD OF VIEW
- INTRUSION ALARM PANEL NOT APPLICABLE
- RECEPTION
- SECURITY OPERATIONS CENTER
- SHIELDED
- TO BE DETERMINED
- TWISTED
- UNLESS OTHERWISE NOTED
- VERIFY IN FIELD
- WEATHER PROOF

	SCOPE OF WORK
ELECTRIC	AL
1	PROVIDE AND INSTALL ALL CONDUIT, BACK BOXES, PULL POWER BOXES AS SHOWN ON DRAWINGS.
HARDWAR	E CONTRACTOR
1	PROVIDE AND INSTALL ELECTRIFIED HARDWARE, ELECTRIC TRANSFER HINGES AND POWER BOOSTERS FOR PANIC HARDWARE AS REQUIRED. COORDINATE WITH THE SECURITY CONTRACTOR TO CONNECT THE HARDWARE TO THE SECURITY SYSTEM.
OWNERS I	Т
1	THE OWNER WILL PROVIDE APPROPRIATE NETWORK CONNECTS AND TELEPHONE JACKS AT LOCATIONS AS SHOWN ON THE DRAWINGS. THE OWNER WILL ALSO PROVIDE PC'S FOR WORKSTATIONS AND OTHER CONVENTIONAL COMPUTER EQUIPMENT REQUIRED FOR THE ACCESS CONTROL AND CCTV SYSTEMS. REVIEW THE PROJECT SPECIFICATIONS AND DRAWING NOTES FOR SPECIFIC SCOPES OF WORK AND EQUIPMENT TO BE PROVIDED.
SECURITY	
1	SECURITY CONTRACTOR SHALL PROVIDE, INSTALL AND PROGRAM A COMPLETELY FUNCTIONAL AND OPERATIONAL SYSTEM AS SHOWN ON DRAWINGS AND SPECIFICATIONS.
2	THE SECURITY CONTRACTOR SHALL PROVIDE A PHASED INSTALLATION OF THE ELECTRONIC SECURITY BASED ON THE OWNER AND GENERAL CONTRACTOR'S SCHEDULE
3	SECURITY CONTRACTOR SHALL PROVIDE AND INSTALL ALL WIRING, DEVICES, CONNECTIONS, PROGRAMMING, AND COORDINATION REQUIRED FOR A COMPLETELY FUNCTIONAL AND OPERATIONAL SYSTEM. SECURITY CONTRACTOR SHALL PROVIDE ANY CUSTOM BACKBOXES REQUIRED.
4	INCLUDE FINAL CONNECTION, PROGRAMMING, TRAINING, AND TESTING OF THE WORK TO THE HEAD-END EQUIPMENT.PER THE OWNER'S, SECURITY CONSULTANT AND SPECIFICATION REQUIREMENTS.
5	ATTENDANCE AT CONSTRUCTION COORDINATION MEETINGS PER THE GENERAL CONTRACTORS SCHEDULE AND REQUIREMENTS.
6	COORDINATION OF WORK WITH OTHER DESIGN AND INSTALLATION TRADES.
7	INSTALL END-OF-LINE (EOL) RESISTORS AS REQUIRED. EOL'S SHALL BE INSTALLED AT THE INDIVIDUAL POINTS OF PROTECTION NOT AT THE PANEL OR POPIT MODULES.



6 7 8
SECURITY GENERAL NOTES
ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE AND ALL APPLICABLE LOCAL CODES. THE CONTRACTOR SHALL NOT INTERMIX ANY LINE VOLTAGE POWER WIRES (120VAC) WITH ANY LOW VOLTAGE SIGNAL OR CONTROL WIRES IN ANY CONDUIT.
VERIFY ALL FIELD DIMENSIONS AND CONDITIONS, NOTIFY ARCHITECT OF ANY DISCREPANCIES FOUND. VERIFY DIMENSIONS OF ALL OWNER FURNISHED EQUIPMENT & SERVICES TO ENSURE PROPER COORDINATION WITH CONSTRUCTION.
SCHEDULE ALL WORK, INCLUDING CONSTRUCTION ACCESS AND STORAGE, WITH THE OWNER OR THOSE DESIGNATED BY THE OWNER. THE CONSTRUCTION SCHEDULE SHALL BE APPROVED BY THE OWNER PRIOR TO THE START OF CONSTRUCTION.
ALL UTILITIES REQUIRED FOR THE CONTINUOUS OPERATION OF ALL EXISTING FACILITIES MUST BE MAINTAINED IN SERVICE AT ALL TIMES (IF APPLICABLE).
CONTRACTOR SHALL PROVIDE DUST PROTECTION AS REQUIRED TO CONTAIN DUST AND DEBRIS WITHIN CONSTRUCTION AREA, BROOM CLEAN ALL AREAS EACH DAY.
COORDINATE WITH THE OWNER TO DETERMINE IF REMOVED ITEMS (IF APPLICABLE) WILL BE KEPT BY THE OWNER. COORDINATE A STORAGE LOCATION AND DELIVER AS DIRECTED BY THE OWNER. DISPOSAL OF OLD EQUIPMENT SHALL BE IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL LAWS.
WORK SHALL BE EXECUTED IN A CAREFUL AND ORDERLY MANNER WITH THE LEAST POSSIBLE DISTURBANCE TO THE PUBLIC AND OCCUPANTS OF EXISTING BUILDINGS. INTERRUPTING PERSONNEL AT WORK AS A RESULT OF THIS UNDERTAKING SHALL ALWAYS BE KEPT TO A MINIMUM. CONTRACTOR SHALL PROVIDE TRAFFIC AND SAFETY SIGNS AND BARRIERS WHERE NECESSARY. NO POWER LINE IN THE BUILDING SHALL BE SHUT DOWN UNLESS REQUESTED AND APPROVED BY THE OWNER IN ADVANCE.
THE CONTRACTORS AND SUBCONTRACTORS PERFORMING WORK ON PREMISES SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING AND SUPERVISING A REASONABLE AND PRUDENT SAFETY PROGRAM INCLUDING, BUT NOT LIMITED TO, THE ISOLATION OF WORK AREAS AND THE PROMPT REMOVAL OF ANY DEBRIS OR TOOLS WHICH MIGHT ENDANGER VISITORS OR EMPLOYEES OF THE FACILITY. ALL ROADS AND WALKWAYS SHALL REMAIN CLEAR AND UNOBSTRUCTED. WHEN NECESSARY ALTERNATE ROUTES MUST BE MAINTAINED, SHOULD UNSAFE CONDITIONS OCCUR.
COORDINATION WITH OTHER CONTRACTORS: IF ANY PART OF THE CONTRACTOR'S WORK DEPENDS UPON THE WORK OF A SEPARATE CONTRACTOR, THIS CONTRACTOR SHALL INSPECT SUCH OTHER WORK AND PROMPTLY REPORT IN WRITING TO THE PROJECT ARCHITECT ANY DEFECTS IN SUCH OTHER WORK THAT RENDER IT UNSUITABLE TO RECEIVE THE WORK OF THIS CONTRACTOR, FAILURE TO INSPECT AND REPORT SHALL CONSTITUTE AN ACCEPTANCE OF THE OTHER CONTRACTOR'S WORK EXCEPT AS TO DEFECTS WHICH DEVELOP IN OTHER CONTRACTOR'S WORK AFTER EXECUTION OF THIS CONTRACTOR'S WORK.
THE CONTRACTOR SHALL ALWAYS MAINTAIN, AT THE JOB SITE, UPDATED "RECORD" DRAWINGS. THESE DRAWINGS SHALL BE AVAILABLE TO THE ARCHITECTS, INSPECTORS OR THE OWNERS UPON REQUEST.
NO CABLE RUN SHALL BE SPLICED UNLESS TWO OR MORE DEVICES ARE CONNECTED TO THE SAME CIRCUIT OR THE DEVICE IS PROVIDED FROM THE FACTORY WITH PIGTAIL WIRES. WHERE SPLICING IS REQUIRED, THE SPLICE SHALL BE SOLDERED AND TAPED, IT SHALL BE DONE IN EITHER A SPECIAL TERMINAL BOX, AT THE BACK BOX OR AT THE DEVICE TERMINAL LUGS. ALL SPLICE BOXES MUST BE IN ACCESSIBLE AREAS AND CLEARLY MARKED ON THE RECORD DRAWINGS.
ALL WIRES SHALL BE COLOR CODED AND SHALL BE CONNECTED IN A UNIFORM MANNER. TRANSPOSING OR CHANGING OF COLOR CODES SHALL NOT BE PERMITTED. WIRE AND CABLE SIZES, NUMBER OF CONDUCTORS, SHIELDING OR OTHER ITEMS LISTED ON THESE DRAWINGS ARE A GUIDE TO THE CORRECT PRODUCT REQUIRED TO ACHIEVE A WORKING SYSTEM AND REPRESENT THE MINIMUM ACCEPTABLE STANDARDS. CONTRACTOR SHALL CONSULT MANUFACTURER'S RECOMMENDATION FOR CABLING AND USE WHICHEVER IS GREATER IN QUALITY, QUANTITY, GAUGE, SHIELDING AND NUMBER OF CONDUCTORS.
ALL WIRING, INCLUDING SHIELDS, MUST BE FREE OF SHORTS, GROUNDS AND STRAY VOLTAGES. ALL EXPOSED SURFACE MOUNTED CABLE UNDER 12' A.F.F. SHALL BE IN CONDUIT WHERE INSTALLED IN AREAS WITHOUT CEILINGS.
ALL CABLE SHALL BE PLENUM RATED ON J-HOOKS. UNDER GROUND CABLE SHALL BE RATED FOR WET APPLICATIONS. ALL EXTERIOR CABLE SHALL BE IN CONDUIT.
A PRE PRINTED VINYL MATERIAL MARKER WRAPPED IN ADHESIVE CLEAR PLASTIC SHALL BE PROVIDED TO THE FOLLOWING:
A.CABLES WITHIN 6" UPON ENTRY AT ANY SECURITY PANEL, TERMINATION OR SPLICE BOX. B.ALL WIRE LEADS WITHIN 2" FROM ANY TERMINAL BLOCK. C.THE CONTRACTOR SHALL SUBMIT SAMPLES OF MARKERS AND ANY NUMBERING OR MARKING SYSTEM FOR REVIEW PRIOR TO IMPLEMENTATION.
ALL NEW ELECTRICAL POWER SUPPLIED TO SECURITY EQUIPMENT OR DEVICES SHALL BE ON AN EMERGENCY SYSTEM INCLUDING UPS WHERE AVAILABLE. ALL CONDUCTORS AND CIRCUIT BREAKERS SHALL BE SIZED IN ACCORDANCE WITH THEIR CONNECTED LOADS (20 AMP MINIMUM). ALL CIRCUITS SHALL BE DEDICATED. A GROUND CONDUCTOR SHALL ALWAYS BE INSTALLED IN ANY POWER WIRING. ALL SECURITY EQUIPMENT UTILIZING ELECTRICAL POWER SHALL ALSO BE ADEQUATELY GROUNDED.
WHERE A NEW CIRCUIT FOR SECURITY IS TAKEN FROM A PANEL BOARD UTILIZED FOR OTHER ELECTRICAL PURPOSES, THE BRANCH CIRCUIT BREAKER FOR SECURITY EQUIPMENT SHALL BE CLEARLY LABELED TO PREVENT ANY ACCIDENTAL SWITCH-OFF. NO SECURITY CIRCUIT IS TO BE SHARED WITH NON SECURITY EQUIPMENT UNLESS OTHERWISE NOTED ON THE DRAWINGS.
THE CONTRACTOR SHALL PROPERLY SEAL ALL CONDUIT OR SLEEVE PENETRATIONS THROUGH ALL WALLS, FLOORS AND CEILINGS USING APPROVED FIRE STOPPING MATERIALS AND SEALANTS REGARDLESS OF RATING AND AS PER APPLICABLE BUILDING CODES.
ALL ROUTING OF WIRING AND ANY RELATED CONDUIT IS DIAGRAMMATIC. CONTRACTOR SHALL FIELD VERIFY EXACT ROUTING PRIOR TO INSTALLATION.
PROVIDE PULL STRINGS IN ALL CONDUITS. PROVIDE BLANK COVERS ON ALL JUNCTION AND PULL BOXES.

ALL CONDUITS AND CABLE PATHS SHALL RUN PARALLEL WITH OR AT RIGHT ANGLES TO THE WALLS, IF MORE THAN THREE 90 DEGREE BENDS ARE TO BE USED IN THE CONDUIT RUN, INSERT A PULL BOX. CONTRACTOR SHALL SIZE THE BOX ACCORDINGLY. CONDUITS SHALL BE SIZED AS INDICATED ON THE DRAWINGS OR LARGER AS REQUIRED TO COMPLY WITH CODE. MINIMUM ALLOWABLE CONDUIT SIZE SHALL BE 3/4".

THE CONTRACTOR SHALL CLEAN AND THOROUGHLY CHECK ALL INSTALLED WORK PRIOR TO CONCEALING OF ARCHITECTURAL FINISHING, CLEAN ALL EXPOSED SURFACES AND NEW EQUIPMENT AFTER COMPLETION. THE CONTRACTOR SHALL ALSO REPAIR OR CLEAN ALL SOILED SURFACES, PAINTED SURFACES OR DAMAGED ARCHITECTURAL FINISHES TO MATCH THE ADJACENT AREA. WHERE REQUIRED, CLEANING, PATCHING OR PAINTING TO BRING THE AFFECTED SURFACE OR FINISH BACK TO ITS ORIGINAL CONDITION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. 23 ALL SECURITY DEVICES AND EQUIPMENT SHALL BE INSTALLED WITH CONSIDERATION TO BARRIER FREE ACCESSIBILITY.

WHERE THE CONTRACTOR HAS TO CHANGE ANY DEVICE TYPE OR MOUNTING TO SUIT ACTUAL CONDITIONS, THIS SHALL BE DONE WITHOUT EXTRA COST TO THE OWNERS. THIS INCLUDES ANY ADDITIONAL PART TO BE SUPPLIED BY THE CONTRACTOR TO ACCOMPLISH PROPER MOUNTING OF A DEVICE. HOWEVER, IT SHALL BE REQUESTED, SUBMITTED AND APPROVED IN WRITING BEFORE COMMENCING THE WORK.

25 COORDINATE ALL TELEPHONE AND DATA (LAN/WAN) INSTALLATION AND CONNECTION REQUIREMENTS WITH THE OWNERS IT DEPARTMENT REPRESENTATIVE AND THE GENERAL CONTRACTOR VIA THE COTR. 26 THE CONTRACTOR SHALL UNDERTAKE THIS WORK IN ITS ENTIRETY IN ACCORDANCE WITH ITS DESIGN AND PURPOSE. ALL WORK SHALL BE CARRIED OUT IN A PROFESSIONAL MANNER WITH MAXIMUM

27 THE CONTRACTOR SHALL INCLUDE ANY COORDINATION, RELAYS, TIMERS, NETWORK CARDS, TERMINAL STRIPS, ETC.. REQUIRED FOR A COMPLETELY FUNCTIONAL INTERFACE WITH ELEVATOR CONTROLLERS, FIRE ALARM SYSTEMS, DOOR HARDWARE AND AUTOMATIC DOOR OPERATORS. WHICH EVER IS APPLICABLE.

28 ALL EXIT DOORS TO REMAIN FREE OPENING FROM EXIT SIDE. U. O. N.

EFFICIENCY AND EXCELLENT WORKMANSHIP.

29 IN THE EVENT OF A DISCREPANCY BETWEEN THE SPECIFICATIONS AND THE DRAWINGS, WHICHEVER IS MORE STRINGENT OR CALLS FOR THE HIGHEST QUANTITY OR QUALITY OF MATERIALS HAS PRECEDENCE.

THE USE OF THE WORD "PROVIDE" IN CONNECTION WITH ANY ITEM SPECIFIED, IS INTENDED TO MEAN THAT SUCH SHALL BE FURNISHED, INSTALLED AND CONNECTED, WHERE SO REQUIRED, EXCEPT AS NOTED OTHERWISE.

31 PRIOR TO SUBMITTAL OF BID, NOTIFY, IN WRITING, SPECIFIED MATERIALS OR EQUIPMENT WHICH ARE EITHER UNAVAILABLE OR WILL CAUSE A DELAY IN CONSTRUCTION COMPLETION SCHEDULE.

32 SEE ARCHITECTURAL PLAN FOR EXITING.

33 SEE ELECTRICAL PLANS FOR J-HOOK DETAILS AND ROUTING.

ELECTRICAL CIRCUITS SHOWN IN THIS SET ARE FOR REFERENCE ONLY AND PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. SEE ELECTRICAL SHEETS FOR CIRCUIT NUMBERS, CIRCUITING AND PANEL LOCATIONS.

35 WHERE CONCRETE FLOORS ARE TO BE CORED, AN X-RAY MACHINE SHALL BE USED TO INSURE THAT NO STRUCTURAL ELEMENTS (E.G. REBAR) WILL BE COMPROMISED OR DAMAGED.

PENETRATIONS THROUGH THE FIRE RATED FLOORS AND WALLS SHALL BE PROTECTED IN ACCORDANCE WITH CBC SECTIONS 709.6 AND 710.1. SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURE'S INSTALLATIONS INSTRUCTIONS AND APPROVED LISTING. MANUFACTURE'S INSTALLATION INSTRUCTIONS AND APPROVED LISTINGS SHALL BE PROVIDED FOR REVIEW BY INSPECTION AUTHORITIES. SUBSTITUTIONS OF OR REVISIONS OR ADDITIONS TO APPROVED SYSTEMS SHALL BE SUBMITTED TO THE OSHPD FIRE MARSHAL (IF REQUIRED) AND THE INSPECTOR OF RECORD FOR REVIEW AND APPROVAL. REFER TO DETAILS FOR FLOOR AND WALL PENETRATION DETAILS.

Project Title	Project Number
NEUROCOG TBI RESEARCH BUILDING	PROJECT NUMBER
	Building Number

Drawn

AW

Approved: Project Director


SECURITY - SYMBOLS LEGEND AND SHEET INDEX

ocation	
50 MUIR ROAD, MARTINI	EZ, CA 94553
) ata	Checked
Date	Checked


Drawing Number

Drawing Title







Office of Construction and Facilities Management Department of Veterans Affairs




Office of Construction and Facilities Management







Office of Construction and Facilities Management Department of Veterans Affairs




Δ


7




Office of Construction and Facilities Management









Office of Construction and Facilities Management Department of Veterans Affairs





100% CONSTRUCTION DOCUMENT SUBMISSION APRIL 20, 2015

SHEET NOTES



100% CONSTRUCTION DOCUMENT SUBMISSION


Drawing Title SECURITY - DEDUCTIVE ALTERNATE #15 FLOOR PLANS

Approved: Project Director


Location 150 MUIR ROAD, MARTINEZ, CA 94553 Checked Drawn Date 04/20/2015 СМ AW

NEUROCOG TBI RESEARCH BUILDING

Project Title




SHEET NOTES




z 4





Office of Construction and Facilities Management Department of Veterans Affairs




	E20334	POLYTECH ASSOCIATES INC	235 Pine Street, 17th Floor San Francisco, CA 94104 TEL (415) 397-3117 FAX (415) 397-1517	
3	4		5	

SECURITY RISER DIAGRAM (TYPICAL)	Project Title NEUROCOG TBI RESEARCH BUILDING			
Approved: Project Director	Location 150 MUIR ROAD, M	Location 150 MUIR ROAD, MARTINEZ, CA 94553		
	<b>Date</b> 04/20/2015	Checked CM	<b>Drawn</b> AW	

Project Number






Office of Construction and Facilities Management Department of Veterans Affairs

100% CONSTRUCTION DOCUMENT SUBMISSION APRIL 20, 2015

SHEET NOTES

1

CONNECT ACCESS CONTROL, INTRUSION ALARM PANEL AND CCTV CAMERAS TO THE VA MARTINEZ CAMPUS POLICE OFFICE IN BUILDING 19.




Drawing Title	Project Title			Project Nu	
SECURITY DETAIL SHEET	NEUROCOG TBI R	NEUROCOG TBI RESEARCH BUILDING		PROJEC	
				Building N	
Approved: Project Director	Location 150 MUIR ROAD, M	IARTINEZ, CA 94553		Drawing N	
	<b>Date</b> 04/20/2015	Checked CM	<b>Drawn</b> AW	T	
	SECURITY DETAIL SHEET	SECURITY DETAIL SHEET NEUROCOG TBI R           Approved: Project Director         Location           150 MUIR ROAD, N         Date	SECURITY DETAIL SHEET NEUROCOG TBI RESEARCH BUILDING          Approved: Project Director       Location         150 MUIR ROAD, MARTINEZ, CA 94553         Date	SECURITY DETAIL SHEET NEUROCOG TBI RESEARCH BUILDING Approved: Project Director Director Dote Checked Drawn	











PROFESSIONA

E20334 -



ARCHITECT

POLYTECH ASSOCIATES INC.



AIL SHEET Project Title Project Title Project Title Project Title Project Title PROKEN PR			
			Building Number
Location 150 MUIR ROAD, M	ARTINEZ, CA 94553		Drawing Number
<b>Date</b> 04/20/2015	Checked CM	<b>Drawn</b> AW	TY402
	Location 150 MUIR ROAD, M Date	Location 150 MUIR ROAD, MARTINEZ, CA 94553 Date Checked	Location 150 MUIR ROAD, MARTINEZ, CA 94553 Date Checked Drawn



Number Number Y402

