




1. CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO EXCAVATING, ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE.
2. CONTRACTOR SHALL SPREAD 4" TOPSOIL & INSTALL SOD & FERTILIZER ON ALL DISTURBED EARTH SURFACES RESULTING FROM THE CONTRACTOR'S OPERATIONS, UNLESS SHOWN OTHERWISE.
3. MAXIMUM GRADE SLOPE SHALL BE 3:1 IN LAWN AREAS UNLESS OTHERWISE SHOWN.



| | |
|----------------|--|
| Project Number | |
|----------------|--|
