BASEMENT & FOUNDATION PLAN

SCALE 1/8"=1'-0"

NOTE: ELEVATIONS SHOWN THUS 000.00 INDICATE BOTTOM OF WALL FOOTING OR SPREAD FOOTING.

FIN. FL. ELEV. 526.2
5"-1" SLAB, 6"x12"OC. EA WAY

PIPE BASEMENT

PIPE BASEMENT

DOWEL SLAB TO WALL WITH 3"x3"x¼" LG ANGLES WELDED 12"OC.

DOWEL SLAB TO WALL WITH 3"x3"x¼" LG ANGLES WELDED LEAD 1'-0" OC.

EXCAVATE TO ELEV. 524.0

SEE DETAIL "4"

WALL & FOOTING REINF. SAME AS FOR WALL SHOWN IN SECT. A-A

20'-8" OPENING

2'-0"x2'-0" OPENING

TELEPHONE DUCT

Estimated quantity of specification rock to be removed for Building No. 7 covered under Item III of the Bid Form is as follows:

(a) General Excavation	0 cu. Yds.
(b) Footing, Pit & Trench	15. Cu. Yds.

SECT. "A-A"

SCALE ⅜"=1'-0"

SIDES, BOTTOM & BAFFLE WALL POURED INTEGRALLY. CONC. TO BE TYPE C MIX.

END OF BAFFLE WALL

DOTTED LINE INDICATES BOTTOM OF SLAB BEHIND SECTION.

SEE SECT. B-B FOR END WALL REINF.

FIN. BSMT. FL. ELEV. 524.2

SECT. "B-B"

SCALE ⅜"=1'-0"

DOTTED LINE INDICATES CONST. OF BAFFLE WALL IS OMITTED

FIN. BSMT. FL. ELEV. 524.2

SEE DETAIL "3"

SECT. "C-C"

SCALE ⅜"=1'-0"

DETAIL "3"

SCALE 12"=1'-0"

SECT. "D-D"

SCALE ⅜"=1'-0"

SECT. "E-E"

SCALE ⅜"=1'-0"

SECT. "R-R"

SCALE ⅜"=1'-0"

TOP OF CROSS BEAM

SLOPE TOPPING ¼" TO TRENCH

MEMBRANE WATERPROOFING

LOW POINT OF TRENCH. SLOPE FLOOR OF TRENCH TO HIGH POINT.

BOTT. OF CROSS BEAM

SECT. "P-P"

SCALE ⅜"=1'-0"

MEMBRANE WATERPROOFING

SECT. "Q-Q"

SCALE ⅜"=1'-0"

SECT. "H-H"

SCALE ⅜"=1'-0"

SECT. "K-K"
SECT. "K'-K'" (OPP. HAND)

SCALE ⅜"=1'-0"

EXTEND OUTSIDE VERT. BARS 3'-0" INTO SLAB.

2'-6" CANTILEVER BARS. HORIZ. BARS EXTEND 2'-0" INTO WALL.

OPEN

SECT. "F-F"

SCALE ⅜"=1'-0"

SECT. "F'-F'"

SCALE ⅜"=1'-0"

SECT. "G-G"

SCALE ⅜"=1'-0"

SECT. "I-I"

SCALE ⅜"=1'-0"

EXTENSION OF SLAB 3'-0" REINF.

EXTEND 3'-0" INTO SLAB

SECT. "I'-I'"

SCALE ⅜"=1'-0"

FIRST FLOOR FRAMING PLAN

FIN. FL. ELEV. 536.7

SCALE ⅛"=1'-0"

BAND A 6 SPAN

BAND B 12 SPAN

BAND C 6 SPAN

10'-2" OPENING

EXTEND SEE BARS OF 5-10 AND HOOK

EXTEND SEE BARS TO B.S. WALL AND HOOK

8'-3" ac (min)

NOTES:
GENERAL NOTES ON DWG. NO. 11-3A APPLY TO THIS BLDG EXCEPT AS OTHERWISE NOTED OR SHOWN.
ALL CONCRETE TO BE TYPE B MIX UNLESS OTHERWISE NOTED.
ALL FOOTINGS ARE DESIGNED FOR A SOIL PRESSURE OF 4,000 LBS. PER SQ. FT. AND FOOTINGS ARE TO BE CARRIED DOWN TO A STRATA CAPABLE OF SUSTAINING SAID PRESSURE.
FOR SOIL BORING DATA SEE DWG. NO. 19.

struct 3

1-5-2-0162

FOUNDATION & 1ST. FLOOR PLANS & DETAILS.

VETERANS ADMINISTRATION
WASHINGTON, D. C.

APPROVED
ASSISTANT ADMINISTRATOR
DIRECTOR OF CONSTRUCTION
CHIEF, DESIGN DIVISION

LAUNDRY BUILDING NO. 7
VETERANS ADMINISTRATION
LEBANON, PA.

		REVISIONS	NUMBER
Drawn	T.L.		7-3
Traced	T.L.		SHEET 3 OF 8
Unit Chf.	G.N.H.		
Date	11-25-48		
Section Chief	John M. Kerr		Proj. No. 29/9

6940

U. S. GOVERNMENT PRINTING OFFICE 685/28

FILE FOLDER NO. 4