

July 28, 2015

AMENDMENT NO. 5

VA Health Care System
Remodel and Expand Urgent Care
Fargo, ND Image 1205.13 / VAHCS 437-312

- A. Refer to the SPECIFICATIONS of the above project and make the following additions, deletions, corrections and/or interpretations.
1. Refer to Specification Section 27 52 40 REAL TIME LOCATION SYSTEMS: DELETE specification in its entirety.
- B. Refer to the DRAWINGS of the above project and make the following additions, deletions, corrections and/or interpretations.
1. Refer to Drawing Sheet E4 BASEMENT AND FIRST FLOOR DEMOLITION PLANS - ELECTRICAL, Plan Notes 24 and 25: The existing Centrak RTLS equipment shall be removed and turned over to the Owner. The Contractor is not responsible for reinstallation of this equipment.
 2. Refer to Drawing Sheet E10 FIRST FLOOR REMODELING PLAN - SYSTEMS: The Contractor shall be responsible for installing a new Category 6e cable from IRM 1B-121A to each RTLS POE Access Point shown on this sheet. Terminate and test per Section 27 01 05. Provide a 20 foot service loop at each location coiled in ceiling space, and coordinate the exact location of the RTLS POE Access Points with the Owner prior to installation. All other work associated with RTLS equipment shown on this sheet shall be by Others.

END OF AMENDMENT NO. 5