

**SECTION 10 21 13
TOILET COMPARTMENTS**

PART 1 - GENERAL

1.1 DESCRIPTION

This section specifies metal toilet partitions, and urinal screens.

1.2 RELATED WORK

- A. Overhead structural steel supports for ceiling hung pilasters which are nonbearing partition: Section 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS.
- B. Color of baked enamel finish: Section 09 06 00, SCHEDULE FOR FINISHES.
- C. Grab bars and toilet tissue holders: Section 10 28 00, TOILET, BATH, AND LAUNDRY ACCESSORIES.

1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
 - B. Samples: Prime coat of paint on 150 mm (six-inch) square of metal panel with baked enamel finish coat over half of panel.
 - C. Manufacturer's Literature and Data: Specified items indicating all hardware and fittings, material, finish, and latching.
 - D. Shop Drawings: Construction details at 1/2 scale, showing installation details, anchoring and leveling devices.
 - E. Manufacturer's certificate, attesting that zinc-coatings conform to specified requirements.
 - F. LEED Submittals: Submit in accordance with Section 01 81 13, SUSTAINABLE DESIGN REQUIREMENTS.
1. Product Data for MR 4: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating cost for each product having recycled content.

1.4 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.
- B. Federal Specifications (Fed. Spec.):
FF-B-575C.....Bolt, Hexagon and Square

C. Code of Federal Regulations (CFR):

40 CFR 247.....Comprehensive Procurement Guidelines for
Products Containing Recovered Materials

D. Commercial Item Descriptions (CID):

A-A-1925.....Shield, Expansion (Nail Anchors)

A-A-60003.....Partitions, Toilet, Complete

PART 2 - PRODUCTS

2.1 LEED REQUIREMENTS

A. MR 4: Provide products that contain recycled content.

2.2 TOILET PARTITIONS:

A. Painted Steel.

B. Conform to Fed. CID A-A-60003, except as modified herein.

C. Fabricate to dimensions shown or specified.

D. Toilet Enclosures:

1. Type 1, Style B (Ceiling hung).

2. Reinforce panels shown to receive toilet tissue holders or grab bars.

3. Upper pivots and lower hinges adjustable to hold doors open 30
degrees.

4. Latching devices and hinges for handicap compartments shall comply
with ADA requirements.

5. Keeper:

a. U-slot to engage bar of throw latch.

b. Combined with rubber bumper stop.

6. Wheelchair Toilets:

a. Upper pivots and lower hinges to hold out swinging doors in closed
position.

b. Provide U-type doors pulls, approximately 100 mm (four inches)
long on pull side.

7. Finish:

a. Finish 1 (baked enamel) on steel doors, pilasters, and enclosure
panels except those adjacent to urinals and as specified.

E. Urinal Screens:

1. Type III, Style E (wall hung), finish 2 or 3.

a. With integral flanges and continuous, full height wall anchor
plate.

b. Option: Full height U-Type bracket.

- c. Wall anchor plate drilled for 4 anchors on both sides of screen.
2. Screen 600 mm (24 inches) wide and 1060 mm (42 inches high).

2.3 FASTENERS

- A. Partition Fasteners: CID A-A-60003.
- B. Use expansion bolts, CID A-A-60003, for anchoring to solid masonry or concrete.
- C. Use toggle bolts, CID A-A-60003, for anchoring to hollow masonry or stud framed walls.
- D. Use steel bolts FS-B-575, for anchoring pilasters to overhead steel supports.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General:
 1. Install in rigid manner, straight, plumb and with all horizontal lines level.
 2. Conceal evidence of drilling, cutting and fitting in finish work.
 3. Use hex-bolts for through-bolting.
 4. Adjust hardware and leave in freely working order.
 5. Clean finished surfaces and leave free of imperfections.
- B. Panels and Pilasters:
 1. Support panels, except urinal screens, and pilaster abutting building walls near top and bottom by stirrup supports secured to partitions with through-bolts.
 2. Secure stirrups to walls with two suitable anchoring devices for each stirrup.
 3. Secure panels to faces of pilaster near top and bottom with stirrup supports, through-bolted to panels and machine screwed to each pilaster.
 4. Secure edges of panels to edges of pilasters near top and bottom with "U" shaped brackets.
- C. Urinal Screens:
 1. Anchor urinal screen flange to walls with minimum of four bolts both side of panel.
 2. Space anchors at top and bottom and equally in between.

- - - E N D - - -