

ADDENDUM #1

VA Iowa City – Reconfigure Domestic Water distribution system for legionella prevention.
VA Project # 636A8-14-001
Date – 08-03-15

ARCHITECTURAL:

DRAWING ITEMS

Item A1: Drawing 1-GI001: Replace Phasing Requirements, Phasing General Note #3 to read:

“EACH FLOOR OF THE BUILDING’S WINGS (EAST, WEST, OR SOUTH) CAN BE VACATED FOR WORK TO BE PERFORMED AT A TIME, UNLESS NOTED OTHERWISE. AS AN EXAMPLE, 7E (SEVENTH FLOOR EAST WING) CAN BE VACATED.”

No supplemental sketch issued.

END OF ARCHITECTURAL ADDENDUM #1

-Kyle Miller

MECHANICAL:

SPECIFICATION ITEMS

Item M1: Section 23 09 23: Delete section 2.9 – C: Water Flow sensors.

DRAWING ITEMS

Item M1: Drawing **1-P0**: Delete General Notes #19 and #20. All ceiling work and wall work is by G.C. If the P.C. has additional work required for installation/removal of piping, not shown on the architectural drawings, the P.C. shall coordinate work with G.C. No supplemental sketch issued.

Item M2: Drawing **1-M4**: Reroute existing chilled water on 11th floor mechanical room for installation of new water heaters and piping. Refer to supplemental sketch 1-M4.1

ELECTRICAL:

DRAWING ITEMS

Item E1: Drawing **1-E5**: ADD missing Keynote #7, “7. HOMERUN TO NEW CIRCUIT BREAKER REFERENCED IN KEYNOTE 1. CIRCUIT WITH 2#12, 1#12GND IN 3/4”C”. No supplemental sketch issued.

END OF MECHANICAL/ELECTRICAL/ ADDENDUM # 1

JPT/jpt

Enclosures

VA Iowa City – Reconfigure Domestic Water distribution system for legionella prevention.
VA Project # 636A8-14-001
CLH #2013-30
KJWW #14.0064.00