














SECURITY LEGEND

-  ELECTROMAGNETIC DOOR LOCKS WITH POSITION SWITCH
PRE-DRILL DOOR AND DOOR FRAMES FOR 1" SNAP FIT DOOR
CONTACTS AND MAGNETS.
-  CEILING-MOUNTED MOTION SENSOR NO PROVISIONS
REQUIRED
-  SECURITY CAMERA (W=WALL, C=CEILING) WALL AT 8" BFC.
2-GANG BACKBOX W/1-GANG PLASTER RING
-  PANIC SWITCH
-  DOOR BUZZER AT 80" AFF OR 6" BFC.
2-GANG BACKBOX W/1-GANG PLASTER RING
-  REQUEST TO EXIT DOOR RELEASE AT 48" AFF.
2-GANG BACKBOX W/1-GANG PLASTER RING
-  PIN/PROX COMBINATION KEYPAD CARDREADER AT 48" AFF.
2-GANG BACKBOX W/1-GANG PLASTER RING
-  PUSH PAD DOOR OPERATOR AT 36" AFF.
2-GANG BACKBOX W/1-GANG PLASTER RING
-  AUTOMATIC DOOR OPERATOR IN CEILING PROVIDED BY
OTHERS, POWERED BY EC
-  DOOR ALARM CONTACTS
-  SECURITY CABINET POWERED BY COR, INSTALLED BY EC
-  PUNCH CLOCK AT 48" AFF
2-GANG BACKBOX W/1-GANG PLASTER RING
-  WANDER-GUARD KEP-PAD AT 48" AFF.
2-GANG BACKBOX W/1-GANG PLASTER RING

NOTES: PROVIDE 3/4" BUSHED CONDUITS STUBBED INTO
ACCESSIBLE SPACE, AFC, WITH NYLON PULL STRING FOR ALL
WALL MOUNTED SECURITY DEVICES, UON. EXTEND CONDUIT
TO NEAREST SYSTEM WIREWAY IN INTERSTITIAL SPACE.

1



REFERENCE SHEET E-1

ELECTRICAL REVISION - 01

VE NO. #: 10487-5

DRAWING TITLE

ELECTRICAL SECURITY LEGEND

DATE
08-05-2015

SCALE
N.T.S.

DRAWN
TDH

VALLEY | ENGINEERING
IDEAS MADE REAL

3231 PEOPLES DRIVE
HARRISONBURG, VIRGINIA 22801
TELEPHONE (540) 434-6365 OR (800) 343-6365
FAX (540) 432-0685

LINEAR ACCELERATOR ADDITION

FOR
VAMC MCGUIRE
RICHMOND, VA.

DRAWING NUMBER
SKE-3