EQ. ID	EQUIPMENT DESCRIPTION	PROVIDED/ INSTALLED	WT	H	L	D	ANCHOR TYPE	DETAIL	VOLT	PHASE	AMPS	WATTS	EMERGENCY POWER	DATA	GAS REQ	MED GAS REQ	COMP AIR (PSI)	PLUMBING	Comments
A1012	TELEPHONE, WALL-MOUNTED, 1-LINE	GFGI																	
A1015	TELEPHONE, DESK, MULTIPLE LINE	GFGI																	
A1030	LOCKER, 2 PERSON, OVER/UNDER	GFCI	63	6'-0"	1'-0"	1'-6"		5/12-522											
A1120	COLUMN, SERVICE, PREFAB, SURGICAL, CEILING MOUNTED	GFCI						5/12-S920	120	1	20	2400			NITROGEN AND NITROUS OXIDE	OXYGEN, VACUUM, AND MEDICAL AIR (50 PSIG)			SPECIAL ELECTRICAL REQUIREMENTS
A1205	LIFT SYSTEM, OVERHEAD, PATIENT ROOM W/BATH	*GFGI						12-S921	120	1	5	600							SPECIAL ELECTRICAL REQUIREMENTS, WALL CEILING SUPPORT REQUIRED
A5075	DISPENSER, SOAP, DISPOSABLE	GFGI	3	11"	5"	4"													
A5080	DISPENSER, PAPER TOWEL, SS, SURFACE MOUNTED	GFGI	4	9"	1'-1"	7"													
A5107	DISPENSER, GLOVE, SURGICAL/EXAMINATION, WALL MOUNTED	GFGI	2	6"	11"	4"													
A5108	WASTE DISPOSAL UNIT, SHARPS	GFGI	2	1'-6"	1'-4"	12'-0"													
A5109	GRAB BAR, 1-1/4" DIA., SS, 2 WALL, W/C ACCESSIBLE	CFCI	7	3"	4'-9"	3"		13/12-521											
A5135	SHELF, UTILITY W/ MOP/BROOM HOLDERS, SS, SURFACE MOUNTED	GFGI	12	6"	3'-0"	10"													
A6200	UPS, THREE PHASE	GFCI																	208/220 VOLT, 3 PHASE
E0954	CART, EMERGENCY, MOBILE	GFGI	125	5'-6"	4'-4"	1'-10"													
F0500	CART, JANITOR'S	GFGI	77	3'-4"	1'-10"	4'-1"													
F0525	CART, SUPPLY	GFGI	265	5'-9"	5'-3"	2'-3"													
F2000	BASKET, WASTEPAPER, ROUND, METAL	GFGI	6	1'-6"	1'-4"	1'-4"													
F2016	WASTE RECEPTACLE, 40 GAL	GFGI	43	2'-6"	1'-7"	1'-5"													
F2017	WASTE RECEPTACLE, 24 GAL (RED)	GFGI	29	3'-0"	1'-3"	1'-3"													
F2020	CAN, TRASH, 44 GALLON	GFGI	22	3'-3"	2'-0"	2'-0"													
F3050	MAGNETIC MARKERBOARD, GLASS	CFCI		5'-7"	3'-3"	2"													SIZES MAY VARY
K1552	BREWER, COFFEE, AUTO, ELECT, 3 BURNER, FRONT/BACK	GFCI	37	1'-9"	9"	1'-10"			120	1	15	1800						YES	COLD WATER
K4660	OVEN, MICROWAVE, HEAVY DUTY, 1000 WATTS	GFGI	60	1'-3"	1'-10"	1'-10"			120	1	20	2400							SPECIAL OUTLET
L1931	ANALYZER, BLOOD GAS	GFCI	76	1'-11"	2'-4"	1'-10"			120	1	10	1200							
M0500	TELEVISION, COLOR, 20" DIAGONAL	GFGI	22	1'-6"	2'-0"	1'-5"			120	1	1	120							
M0512	TELEVISION, HDTV, LARGE SCREEN, 60"	GFGI	88	3'-4"	5'-2"	1'-5"			120	1	2	240							
M1801	COMPUTER, MICROPROCESSING, W/FLAT PANEL MONITOR	GFGI	45	1'-11"	2'-0"	1'-7"			120	1	5	600							
M1810	COPIER, FLOOR STANDING, DIGITAL	GFGI	282	3'-5"	3'-8"	2'-4"			120	1	15	1800							
M1825	PRINTER, COMPUTER	GFGI	54	1'-5"	1'-8"	1'-9"			120	1	3	690							
M2050	SHELVING, STORAGE	GFGI	147	7'-0"	3'-0"	1'-3"													
M3070	HAMPER, LINEN, MOBILE, W/LID	GFCI	25	3'-1"	2'-2"	2'-2"													
M3105	CABINET, 28-COUNT WARMER, SAGE PRODUCT	GFGI	190	3'-0"	2'-6"	2'-3"			120	1	12	1440							SPECIAL ELECTRICAL REQUIREMENTS
M3150	DISTRIBUTION SYSTEM, MEDICATION, AUTOMATIC	GFCI							120									YES	COLD WATER AND DRAIN
M7010	BED, PATIENT, ELECTRIC	GFGI	335	3'-1"	3'-6"	7'-11"			120	1	10	1200							
R4650	ICE MAKER, FLAKED, WITH DISPENSER	CFCI	585	6'-10"	3'-0"	2'-6"			120	1	20	2300						YES	COLD WATER AND DRAIN, SPECIAL OUTLET
R7250	REFRIGERATOR/FREEZER, 20 CUBIC FEET	GFGI	290	5'-9"	2'-9"	2'-10"			120	1	15	1800							
S9765	FLUSHER/DISINFECTOR, DISPOSAL, (MACERATORS-V40-310 VERNACARE)	GFGI	198	4'-7"	1'-8"	1'-11"			240	3	15	6236						YES	HOT/COLD WATER AND DRAIN, SPECIAL ELECTRICAL REQUIREMENTS, STEAM, VENT TO ATMOSPHERE
X4780	RADIOGRAPHIC UNIT, MOBILE, BATTERY	GFGI	1102	6'-5"	2'-5"	4'-11"			120	1	10	1200							
Z1004	OMNI CELL STORAGE, 2-CELL CABINET, 4'-0"	GFGI	750	6'-5 5/8"	4'-3 1/2"	2'-0 1/2"													PROVIDE POWER/DATA & SEISMIC ANCHORAGE PER PRODUCT SPECIFICATIONS. (E) TO BE RELOCATED
Z1006	OMNI CELL STORAGE, 3-CELL CABINET, 6'-0"	GFGI	1000	6'-5 5/8"	6'-4 1/4"	2'-0 1/2"													PROVIDE POWER/DATA & SEISMIC ANCHORAGE PER PRODUCT SPECIFICATIONS. (E) TO BE RELOCATED
Z3050	WHITEBOARD DRY ERASE - 3' x 4'	GFGI		3'-0"	4'-0"	2"													
Z4650	MICROWAVE, COMFORT PERSONAL CLEANSING, SAGE PRODUCTS	GFGI																	SPECIAL OUTLET
Z6200	REFRIGERATOR, DRAWER SYSTEM, RANDELL	GFGI	250	1'-4"	3'-10"	2'-5"			115		6.3								

*NOTE: CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ABOVE-CEILING SUPPORT STRUCTURE FOR PATIENT LIFTS AS SHOWN IN THESE DOCUMENTS.

EQUIPMENT SCHEDULE GENERAL NOTES
A. REFER TO EQUIPMENT PLANS 12-133A - D FOR EQUIPMENT LOCATIONS.

EQUIPMENT SCHEDULE GENERAL NOTES
12" = 1'-0"

Scale: 12" = 1'-0"

BIDDING RFI #6	8/6/2015
Revisions:	Date:

CONSULTANTS:

REGISTERED ARCHITECT — NV 6751 — 12/31/2015

ARCHITECT/ENGINEERS:

Architecture | Engineering | Planning
Hammel, Green and Abrahamson, Inc.
1410 Rocky Ridge Drive, Suite 250
Roseville, California USA 95661
Telephone 916.787.5100 Facsimile 916.784.7738
Contact: Douglas Whiteaker

Drawing Title	EQUIPMENT SCHEDULE
Approved: Project Director	
Project Title	WARD 2C REMODEL: INTENSIVE CARE UNIT
Location	975 KIRMAN AVE. RENO, NV 89520
Date	01/30/2015
Checked	Checker
Drawn	Author
Project Number	654-412
Building Number	12
Drawing Number	12-605
Dwg. of	

Office of Construction and Facilities Management

Department of Veterans Affairs

BID DOCUMENTS - FINAL

VA FORM 08-6231

VA261-15-R-0184 Amend 0004 RFI #6 Attachment