



SHELL EXHIBIT KEYNOTES

1. DASHED LINE REPRESENTS SHELL SPACE PERIMETER PARTITIONS. INSTALL ALL EQUIPMENT, BACKING, AND SERVICES WITHIN THESE PARTITIONS AS REQUIRED FOR FULL FUNCTIONALITY OF ADJACENT NON-SHELL SPACES (HATCHED). DO NOT INSTALL EQUIPMENT, LOCKERS, CASEWORK, BACKING, SERVICES, PARTITIONS, OR FINISHES, INCLUDING GYPSUM BOARD, AT SHELL SIDE OF PERIMETER PARTITIONS.
2. INSTALL DOOR AT PERIMETER OF SHELL SPACE.
3. INSTALL COMPLETE EXTERIOR WALL ASSEMBLY INCLUDING INSULATION AND GYPSUM BOARD ON INTERIOR FACE OF BUILDING. INSTALL EQUIPMENT BACKING, ELECTRICAL CONDUIT, AND OTHER ITEMS WHICH WILL BE CONCEALED WITHIN WALL FOR FUTURE USE.
4. DO NOT CORE HOLES IN SLAB FOR FUTURE PLUMBING FIXTURE.

SHELL EXHIBIT



1410 Rocky Ridge Drive, Suite 250  
Roseville, California 95661  
Telephone 916.787.5100

Office of Construction and  
Facilities Management  
Department of  
Veterans Affairs

COMM. NO. 2941-011-00  
SCALE 1/4" = 1'-0"  
DATE  
DRAWN TDUFFY

WARD 2C REMODEL:  
INTENSIVE CARE UNIT

1

00-00-00 00:00

XXXXXXXX-XXXXXXXXX.DWG

VA261-15-R-0184 Amend 0004  
RFI 14 Shell Exhibit