| Room Finish Schedule | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| ROOM NUMBER | ROOM NAME | FLOOR | | WALLS | | | | CEILING | CEILING | NOTES |
| | | FINISH | BASE | NORTH | EAST | SOUTH | WEST | MATL | FINISH | |
| FIRST FLOOR | | | | | | | | | | |
| B1149 | CONFERENCE | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | SEE NOTE 6 |
| B1150 | LOUNGE | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | SEE NOTE 6 |
| B1150A | WOMENS LOCKERS | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | SEE NOTE 6 |
| B1150B | WOMEN | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | SEE NOTE 6 |
| B1216 | OFFICE | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | SEE NOTE 6 |
| THIRD FLOOR | | | | | | | | | | |
| B3CO3 | CORRIDOR | WSF-1,2,3 | RB-1 | P-1,2,3,WR-1, 2 | P-2 | P-1, WR-1, 2 | P-1, P-2 | GWB, AT-1 | P-2 | SEE NOTES 1,2 & 5 |
| B3CO3A | ALCOVE CRASH | WSF-1 | RB-1 | ---- | WG-2/P-1, WR-2 | WG2/P-1, WR-2 | WG-2/P-1, WR-2 | GWB | P-1 | SEE NOTE 5 |
| B3CO4 | CORRIDOR | WSF-1 | RB-1 | ---- | P-1, WR-2 | ---- | P-1, WR-2 | AT-1 | ---- | SEE NOTE 5 |
| B3CO5 | CORRIDOR | WSF-1 | RB-1 | ---- | P-1, WR-2 | ---- | P-1, WR-2 | AT-1 | ---- | SEE NOTE 5 |
| B3CO5C | CORRIDOR | WSF-1 | RB-1 | ---- | P-1 | P-1 | P-1 | AT-1 | ---- | SEE NOTE 5 |
| B3CO6 | CORRIDOR | WSF-1 | RB-1 | P-1 | P-1,P-2 | P-1, P-3, WR-1,2 | P-1 | GWB, AT-1 | P-1, P-2 | SEE NOTES 1,2 & 5 |
| B3CO6A | ALCOVE STR/XRAY | WSF-1 | RB-1 | WG-2/P-1, WR-2 | ---- | WG-2/P-1, WR-2 | WG-2/P-1, WR-2 | GWB | P-1 | SEE NOTE 5 |
| B3CO7 | CORRIDOR | WSF-1 | RB-1 | P-1 | P-2 | P-3/WR-1,2 | P-1 | GWB, AT-1 | P-2 | SEE NOTES 2 & 5 |
| B3CO7A | ALCOVE CRASH | WSF-1 | RB-1 | WG-2/P-1, WR-2 | WG-2/P-1, WR-2 | ---- | WG-2/P-1, WR-2 | GWB | P-1 | SEE NOTE 5 |
| B3CO7B | ALCOVE | WSF-1 | RB-1 | WG-2/P-1, WR-2 | WG-2/P-1, WR-2 | ---- | WG-2/P-1, WR-2 | AT-1 | ---- | SEE NOTE 5 |
| B3CO8 | CORRIDOR | EXIST | EXIST | EXIST, P-3 | EXIST, P-3 | EXIST, P-3 | N/A | GWB, AT-1 | EXIST | SEE NOTE 2 |
| B3CO57 | CORRIDOR | WSF-1,2,3 | WSF-1 | P-1, WR-1, 2 | P-2 | P-1,2,3,WR-1,2 | P-1, P-2 | GWB, AT-1 | P-1, P-2 | SEE NOTES 1,2 & 5 |
| B3122 | WARD CLERK | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | |
| B3124 | HAC/EMS | WSF-1 | WSF-1 | WG-2/PE-1 | PE-1 | PE-1 | WG-2/PE-1 | GWB | PE-1 | SEE NOTE 5 |
| B3125 | NURSE SUPPLY 1/2 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3125A | NURSE 3 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | |
| B3126 | RT WORKROOM | WSF-1 | RB-1 | PE-1 | PE-1 | PE-1 | PE-1 | AT-3 | ---- | |
| B3127 | BARIATRIC PATIENT 1 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-1 | P-1, P-4, WG-1/ P-4 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | WG-2/WR-3/P-1 | GWB, AT-1 | P-1,P-2 | WT-1, SEE NOTES 1,2, 3 , 5& 9 |
| B3127A | TLT. 1 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3127B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3128 | CLEAN UTILITY | WSF-1 | WSF-1 | WG-2/PE-1 | WG-2/PE-1 | WG-2/PE-1 | WG-2/PE-1 | AT-3 | ---- | SEE NOTE 5 |
| B3129 | BARIATRIC PATIENT 2 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-1 | WG-2/WR-3/P-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | P-1, P-4, WG-1/P-4 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1,2, 3 , 5& 9 |
| B3129A | TLT. 2 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3129B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3130 | SOILED UTILITY | WSF-1 | WSF-1 | WG-2/PE-1 | WG-2/PE-1 | WG-2/PE-1 | WG-2/PE-1 | AT-3 | ---- | SEE NOTE 5 |
| B3131 | AV ITE | WSF-1 | WSF-1 | P-2 | WG-1/P-2 | P-1 | P-2 | AT-3 | ---- | SEE NOTES 2, 5 |
| B3131A | PATIENT 3 ISO | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-2 | P-1,P-4 | P-1, WG-1/P-1 | WG-2/WR-3/P-1 | GWB, AT-3 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5 & 9 |
| B3131B | TLT. 3 | ERF-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3132 | BG/RT STORAGE | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3133 | STORAGE | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3134 | NOUR. | SVT-2 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3135 | FAMILY LOUNGE / PANTRY | SVT-1,SVT-2 | RB-1 | P-1 | P-1, PPT-3 | P-1 | P-1 | GWB, AT-1 | P-2 | WT-1, SEE NOTES 1, 4 & 9 |
| B3135A | TLT. FAM. | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3136 | LINEN | WSF-1 | WSF-1 | PE-1 | PE-1 | PE-1 | PE-1 | AT-3 | ---- | |
| B3137 | (E) ELEC. | EXIST-SC | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3138 | MED. | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3139 | NURSE SUPPLY 4/5 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3140 | TEAM WORKROOM | CPT-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3141 | PATIENT 4 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-1 | P-1, P-4, WG-1/ P-4 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | WG-2/WR-3/P-1 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3141A | TLT. 4 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3141B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3143 | PATIENT 5 | WSF-1, WSF-2 | WSF-1 | P-1 | WG-2/WR-3/P-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | P-1, P-4, WG-1/P-4 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3143A | TLT. 5 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3143B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3145 | OFFICE MANAGER | CPT-1 | RB-1 | P-1 | P-1 | P-4 | P-1 | AT-1 | ---- | WT-1, SEE NOTE 9 |
| B3147 | OFFICE | CPT-1 | RB-1 | P-1 | P-1 | P-4 | P-1 | AT-1 | ---- | WT-1, SEE NOTE 9 |
| B3149 | STORAGE | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| B3151 | NURSE SUPPLY 6/7 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3153 | PATIENT 6 | WSF-1, WSF-2 | WSF-1 | WG-2/WR-3/P-1 | P-1, WG-1/P-1 | P-1, P-4, WG-1/P-4 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3153A | TLT. 6 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3153B | DS | WSF-1 | WSF-1 | P-1 | P-1, WG-1/P-1 | P-1 | P-1 | GWB | ---- | |
| B3155 | PATIENT 7 | WSF-1, WSF-2 | WSF-1 | P-1, P-4, WG-1/P-4 | P-1 | WG-2/WR-3/P-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3155A | TLT. 7 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3155B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3157 | LOCKER | SVT-2 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | WT-1, SEE NOTE 9 |
| B3157A | MENS | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3157B | WOMENS | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3157C | STAFF LOUNGE | SVT-1,SVT-2 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-2 | WT-1, SEE NOTES 1, 4 & 9 |
| B3159 | NURSE SUPPLY 8/9 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3161 | PATIENT 8 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | WG-2, WR-3/P-1 | P-1, WG-1/P-1 | P-1, P-4, WG-1/P-4 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3161A | TLT. 8 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3161B | DS | WSF-1 | WSF-1 | PT-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3163 | PATIENT 9 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | P-1, P-4, WG-1/ P-4 | P-1, WG-1/P-1 | WG-2/WR-3/P-1 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3163A | TLT. 9 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | |
| B3163B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3165 | TELEMETRY CLOSET | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3167 | IT | EXIST-SC | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1,EXIST | ---- | |
| B3169 | CONSULTATION | CPT-1 | RB-1 | P-1 | P-1, P-4 | P-1 | P-1 | AT-1 | ---- | |
| B3171 | BG/RT OFFICE | CPT-1 | RB-1 | P-1 | P-1 | P-1 | P-4 | AT-1 | ---- | |
| B3175 | AV ITE | WSF-1 | WSF-1 | P-1 | WG-1/P-2 | P-2 | P-2 | AT-3 | ---- | SEE NOTES 2, 5 |
| B3175A | PATIENT 10 ISO | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-1 | WG-1/P-4 | P-1 | WG-2, WR-3/P-1 | GWB, AT-3 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3175B | TLT. 10 | ERF-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3177 | NURSE SUPPLY 11/12 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3177A | NURSE 10 | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | GWB, AT-1 | P-1 | SEE NOTE 5 |
| B3179 | PATIENT 11 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | WG-2/WR-3/P-1 | P-1, WG-1/P-1 | P-1, P-4, WG-1/P-4 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3179A | TLT. 11 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3179B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| B3181 | PATIENT 12 | WSF-1, WSF-2 | WSF-1 | P-1, WG-1/P-4, WG-2/WR-3/P-1 | P-1, P-4, WG-1/ P-4 | P-1, WG-1/P-1 | WG-2/WR-3/P-1 | GWB, AT-1 | P-1, P-2 | WT-1, SEE NOTES 1, 2, 3, 5& 9 |
| B3181A | TLT. 12 | PPT-1 | PPT-4 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | PPT-2,3,5/P-1 | GWB | P-1 | SEE NOTE 4 |
| B3181B | DS | WSF-1 | WSF-1 | P-1 | P-1 | P-1 | P-1 | GWB | P-1 | |
| BR3173 | GAS | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |
| BR3173A | GAS | WSF-1 | RB-1 | P-1 | P-1 | P-1 | P-1 | AT-1 | ---- | |

| Room Finish Schedule | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| ROOM NUMBER | ROOM NAME | FLOOR | | WALLS | | | | CEILING | CEILING | NOTES |
| | | FINISH | BASE | NORTH | EAST | SOUTH | WEST | MATL | FINISH | |

| ROOM FINISH SCHEDULE GENERAL NOTES | |
|---|---|
| # | DESCRIPTION |
| A | REFER TO SPECIFICATION SECTION 09 06 00 SCHEDULE FOR FINISHES. REFER TO INTERIOR FINISH PLANS, ELEVATIONS AND CASEWORK DETAILS. |
| B | REFER TO FINISH PLANS AND ELEVATIONS FOR FLOOR AND WALL FINISH PATTERN LOCATIONS AT MATERIAL TRANSITIONS. |
| C | WHERE FLOORING CHANGES OCCUR BETWEEN ROOMS, TRANSITIONS TO OCCUR AT CENTERLINE OF DOOR. |
| D | ALL TRANSITIONS BETWEEN FLOOR MATERIALS SHALL BE SMOOTH AND EVEN. MAXIMUM VERTICAL CHANGE IN FLOOR LEVEL SHALL BE 1/16". REFER TO INTERIOR DETAIL SHEETS FOR TRANSITION DETAILS. |
| E | WHERE BASE IS NOTED AS WSF-1 OR WSF-2, AN INTERGRAL COVE BASE 6" A.F.F. SHALL BE USED. |
| F | INTERIOR DOOR FRAMES SHALL BE PAINTED TO MATCH ADJACENT WALL SURFACES ON WHICH THEY OCCUR U.N.O. |
| G | REFER TO REFLECTED CEILING PLANS FOR CEILING FINISH LOCATIONS AND MATERIAL TRANSITIONS. |
| H | THE BASE AT LOWER CABINETS ARE TO MATCH THE WALL BASE OF THE ROOM IN WHICH THEY OCCUR U.N.O. |
| J | ALL WOOD-LOOK PLASTIC LAMINATE ON DOORS AND CASEWORK SHALL RUN VERTICAL. |
| K | STORAGE ROOMS SHALL HAVE A BAND OF ACCENT PAINT MEASURING 18" DOWN FROM THE FINISHED CEILING OR SPRINKLER HEAD, WHICH EVER IS LOWER. PAINTED P-5 TO INDICATE NO STORAGE AREA. |
| L | PAINT REFERENCED FOR COLOR MATCH ONLY. REFER TO SPECIFICATIONS. |
| M | MISC. PANELS, FIRE EXTINGUISHER CABINETS, EXPOSED DUCTING PARTS, LOUVERS, VENTILATION COVERS, EXPOSED METAL, STEEL AND ANY EQUIMENT NOT FACTORY FINISHED INCLUDING ASSOCIATED HARDWARE SHALL BE PAINTED TO MATCH ADJACENT SURFACE. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION. |
| N | ALL EXISTING FINISHES TO BE REMOVED AND SURFACES PREPARED AS NECESSARY TO RECEIVE NEW FINISHES IN ACCORDANCE WITH FINISH PLANS AND SCHEDULE U.N.O. |
| P | ALL EXTERIOR WINDOWS SHALL RECEIVE WT-1. |
| Q | ALL EXTERIOR WINDOW SILLS TO BE SOLID SURFACE. |
| R | GROUT FOR FLOOR TILE SHALL BE GR-1. GROUT FOR WALL TILE SHALL BE GR-2 |
| S | ALL INTERIOR FINISHES SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION. THE SUB-CONTRACTOR SHALL BE APPROVED AND QUALIFIED TO INSTALL FINISH MATERIALS. INTALLERS SHALL HAVE EXPERIENCE WITH PROJECTS OF SIMILAR MAGNITUDE AND COMPLEXITY. |

| ROOM FINISH SCHEDULE SPECIFIC NOTES | |
|---|---|
| # | DESCRIPTION |
| 1 | SEE FLOOR FINISH PLAN FOR FLOOR FINISH PATTERNS |
| 2 | SEE ACCENT PAINT PLAN FOR ACCENT PAINT LOCATIONS |
| 3 | FOR FOOTWALLS WITH SOFFIT, SOFFIT TO BE P-4 . WALL ON FOOTWALL BELOW SHELF TO BE WG-1 |
| 4 | SEE ELEVATIONS FOR WALL FINISH PATTERN |
| 5 | SEE WALL PROTECTION PLANS AND ELEVATIONS FOR WALL PROTECTION TYPES AND LOCATIONS. WALL CORNER GUARDS ARE INDICATED ON WALL PROTECTION PLANS |
| 6 | PATCH AND REPAIR FINISHES TO MATCH EXISTING. PAINT NEW GWB TO MATCH EXISTING PAINT COLOR. |
| 7 | NOT USED |
| 8 | PATCH AND REPAIR, MATCH EXISTING MATERIALS UNO. |
| 9 | EXTERIOR WINDOW TO RECEIVE WT-1 |
| 10 | EXTERIOR WINDOW SILLS TO BE SOLID SURFACE |

BIDDING RFI #15 — 7/31/2015
Revisions: — Date:

CONSULTANTS:

REGISTERED ARCHITECT — NO. 6751 — 12/31/2015

ARCHITECT/ENGINEERS:


Architecture | Engineering | Planning
Hammel, Green and Abrahamson, Inc.
1410 Rocky Ridge Drive, Suite 250
Roseville, California USA 95661
Telephone 916.787.5100 Facsimile 916.784.7738
Contact: Douglas Whiteaker


Drawing Title: ROOM FINISH SCHEDULE
Approved: Project Director

Project Title: WARD 2C REMODEL: INTENSIVE CARE UNIT
Location: 975 KIRMAN AVE. RENO, NV 89520
Date: 01/30/2015 | Checked: DW | Drawn: CK

Project Number: 654-412
Building Number: 12
Drawing Number: 12-603
Dwg. of

Scale:

Office of Construction and Facilities Management
Department of Veterans Affairs

BID DOCUMENTS - FINAL

VA261-15-R-0184 Amend 0004 RFI #15