

**ADDENDUM #3****Project #516-336 Bay Pines VA Cancer Infusion Center (201144)****04/30/14**

This addendum is made and hereby becomes a part of the Construction Documents for this project dated 11/15/2013 as prepared by Long & Associates Architects/Engineers, Inc., 4525 S. Manhattan Avenue, Tampa, FL 33611.

Changes to Drawings:3.01 Refer to Drawing A0.1 Architectural Site Plan 1:

- A. Add the following note: "Delete entire scope of work (inclusive of Civil, Landscape, Irrigation, Architectural, Electrical, and Fire Protection) associated with the "Covered Drop Off" to the south of the main entry, inclusive of the vehicular drop off and the adjacent suspended canopy system. Provide a 4'0" wide eyebrow canopy braced off the main structure over the entire width of the sliding entry doors. Continue parking across both sides of former "Covered Drop Off" location. Coordinate with scope of work indicated on drawings of all disciplines."

3.02 Refer to Drawing A1.2 Enlarged Floor Plan 2:

- A. Add the following note: "Delete entire scope of work (inclusive of Civil, Architectural, Structural, Mechanical, Plumbing, Electrical, and Fire Protection) associated with the "Connector" between the new and existing buildings, remove sliding doors and associated electrical scope (power and exit signage) at west side of entry lobby and infill wall with 8" metal stud framing with exterior plywood sheathing, peel and stick membrane, paper backed metal lath and 7/8" stucco on exterior and 8" batt insulation and 5/8" painted gypsum board at the interior of the infill partition. Shift landscaping shown to south. Coordinate with scope of work indicated on drawings of all disciplines."

3.03 Refer to all Exterior Elevation Sheets and Wall Section Sheets:

- A. Add the following note: "Delete the manufactured stone veneer at all the locations interior and exterior. Replace with 7/8" stucco on metal lath at exterior locations. Replace with 5/8" painted gypsum board at interior locations (on 7/8" metal hat channels over CMU where applicable)."

Changes to Specifications:3.04 Refer to Specification Section 01 00 00 – General Requirements:

- A. At Paragraph 1.2 Statement of Bid Items DELETE the following ALTERNATES:
- B. Alternate No.1
  - C. Alternate No.2
  - G. Alternate No.7

END OF ADDENDUM #3

Paul W. Portal, A.I.A.

AR 0014412

Date: 5/5/14