



- 1 REMOVE ALL EXISTING DECKING & 2X DECK JOISTS
LEAVE ALL EXISTING DECK BEAMS IN PLACE
- 2 REMOVE ALL RUBBER, CONCRETE, AND CONCRETE BASE MATERIAL
EXCAVATE FOR NEW CONCRETE FLATWORK & BASE
- 3 REMOVE STAIR DECKING & STAIR STRINGERS
- 4 PROJECT TREE
- 5 REMOVE TREE & RETURN TREE TAG TO COR
- 6 REMOVE TREE, GRIND STUMP, RETURN TREE TAG TO COR
- 7 EXISTING MULCH TO REMAIN PROJECT EXISTING PLAY STRUCTURE
- 8 REMOVE EXISTING SAND BOX
- 9 EXISTING CONCRETE STAIRS TO REMAIN
- 10 REMOVE RUBBER SHEETING, EXISTING CONCRETE SLAB TO REMAIN
- 11 REMOVE RUBBER TILES
- 12 REMOVE ALL DECK POST, RAILINGS, GATES, AND HARDWARE
- 13 REMOVE ALL DECK SIDING
- 14 TRELLIS POST TO REMAIN, PROJECT IN PLACE
- 15 REPLACE PLAY STRUCTURE
- 16 PROJECT PLAY STRUCTURE

KEYED SHEET NOTES - INTERIOR

- A REMOVE CARPET, VINYL FLOORING AND BASE THROUGHOUT, UNO
- B REMOVE SHEET VINYL THROUGHOUT, UNO.
- C REMOVE FLOOR TILE IN BATHROOMS.
- D REMOVE ALL FLOOR MOUNTED BATHROOM FIXTURES AND SAVE FOR FUTURE RE-INSTALL AT A LATER TIME.
- E REMOVE WALLPAPER BORDER THROUGHOUT, MURAL IN HALLWAY TO REMAIN
- F REMOVE CORNER GUARDS THROUGHOUT AND SAVE FOR RE-INSTALL AT A LATER DATE.
- G REMOVE WHITEBOARDS AND TACKBOARDS THROUGHOUT AND SAVE FOR FUTURE RE-INSTALL.
- H REMOVE EXISTING LAMINATE AT COUNTER AND PREP FOR NEW LAMINATE RESURFACING.
- I PROTECT REMAINING ITEMS NOT INCLUDED IN DEMO FROM DUST AND DAMAGE.