


ISOMETRIC



- SHEET NOTES:**
- REFERENCES:
GENERAL NOTES S-001.
PLAN ELEVATION KEY S-102.
EXTERIOR GRADE ELEVATIONS CIVIL DRAWINGS.
ENTRY/EXIT PLANS ARCH. DRAWINGS.
STAIR & STAIR/ELEVATOR PLANS & DETAILS S-401.
FLOOR DRAIN LOCATIONS AND DETAILS PLUMBING DRAWINGS.
 - SLAB ON GRADE CONSTRUCTION:
PARKING AREA AND DRIVE AISLES
CONCRETE INTERIOR SLAB ON GRADE SHALL BE 5" THICK. SLAB TO BE PLACED ON 6" THICK LIME STABILIZED, SCARIFIED AND RECOMPACTED SUB-GRADE IN ACCORDANCE WITH GEOTECHNICAL REPORT. SEE DETAIL D7/S-003 FOR SLAB REINFORCEMENT. PROVIDE 1/2" JOINT FILLER AT GRADE SLAB AROUND COLUMNS, TYPICAL.
ELECTRICAL, MECHANICAL, STORAGE ROOMS, ETC.
CONCRETE SLAB ON GRADE SHALL BE 5" THICK. SLAB TO BE PLACED ON 4" THICK SAND LAYER OVER 8" LIME STABILIZED, SCARIFIED AND RECOMPACTED SUB-GRADE IN ACCORDANCE WITH GEOTECHNICAL REPORT. SEE DETAIL D7/S-003 FOR SLAB REINFORCEMENT. FOR MOISTURE PROTECTION, PLACE 6 MIL THICK POLYETHYLENE SHEETING BELOW SLAB-ON-GRADE PER MANUFACTURER RECOMMENDATIONS.
USE STRAIGHT LINE INTERPOLATION FOR FLOOR ELEVATIONS BETWEEN THOSE INDICATED.
 - DATUM ELEVATION 0'-0" = 527'-0".
 - SLAB CONSTRUCTION AND CONTROL JOINTS, SEE DETAIL C5 & C7/S-003.
 - CONTRACTOR HAS THE OPTION TO USE SAW CUT JOINTS IN LIEU OF TOOLED JOINTS, PROVIDED THAT THE 1 1/2" DEEP SAW CUT JOINTS SHALL BE SPACED AT 10 FEET ON CENTER IN EAST WEST DIRECTION, AND 12'-6" (MAX.) IN NORTH SOUTH DIRECTION. FOR ADDL. INFO. SEE SPECIFICATIONS SECTION 03300 PARAGRAPH 3.6, SUB ITEM A TO B.
 - SURFACE SEALER SHALL BE APPLIED AT SLAB-ON-GRADE WITHIN PARKING FACILITY, INCLUDING CURBS, WALKS, AND ISLANDS.
 - INDICATES (4) #4 X 8'-0" @ 4' O.C. AT SLAB MID-DEPTH.
 - FOR SLAB CORNER REINF. SEE D6/S-003.
 - TYPICAL WALL REINFORCEMENT AROUND OPENINGS, SEE DETAIL D1/S-002, & F1/S-004.
 - FLOOR DRAINS SHOWN ON THIS SHEET ARE FOR REFERENCE ONLY. FOR EXACT LOCATION OF FLOOR DRAINS, SEE PLUMBING DRAWINGS.
PREFERRED LOCATION OF DRAIN IS AT THE EDGE OF DOUBLE TEE FLANGE.
 - MASONRY WALL CONTROL JOINTS, SEE DETAILS D1 & D3/S-004.
 - INDICATES PLAN MATCH LINE.

<table><tr><th>Date</th><th>Revisions</th></tr><tr><td>2-24-14</td><td>DD2 COST ESTIMATE SET</td></tr><tr><td>3-05-14</td><td>35% CD SET - NOT FOR CONSTRUCTION</td></tr><tr><td>4-30-14</td><td>65% CD SET - NOT FOR CONSTRUCTION</td></tr><tr><td>6-03-14</td><td>95% CD SET - NOT FOR CONSTRUCTION</td></tr><tr><td>7-15-14</td><td>100% CD SET</td></tr></table> <p>PRINTED: 7/14/2014 3:27:01 PM</p>	Date	Revisions	2-24-14	DD2 COST ESTIMATE SET	3-05-14	35% CD SET - NOT FOR CONSTRUCTION	4-30-14	65% CD SET - NOT FOR CONSTRUCTION	6-03-14	95% CD SET - NOT FOR CONSTRUCTION	7-15-14	100% CD SET	<p>CONSULTANTS:</p> <div>WOOLPERT ENGINEERING 343 FOUNTAINS PARKWAY SUITE 100 FAIRVIEW HEIGHTS, IL 62208 618-632-7004 office 618-632-0100 fax</div> <div>DAVID MASON & ASSOCIATES 800 S. VANDEVENTER AVE. ST. LOUIS, MO 63110 314-534-1030 office 314-534-1053 fax</div> <div>SCI - GEOTECHNICAL 130 POINT WEST BLVD. ST. CHARLES, MO 63301 636-949-8200 636-949-8269 fax</div> <div>STATE OF TEXAS JAMES E. WARNER 104009 7-15-14</div>	<p>ARCHITECT/ENGINEERS:</p> <div>Chiodini ARCHITECTS Architecture / Interior Design / Graphics 1401 S. Brentwood Blvd. / Suite 425 / St. Louis, Missouri 63114 314-725-6988 / arch@chiodini.com</div> <div>WALKER PARKING CONSULTANTS 2525 BAY AREA BLVD. SUITE 400 HOUSTON, TX 77058 281-280-0068 office 281-280-0373 fax FIRM CERTIFICATE OF AUTHORITY NUMBER F-004168</div>	<p>Drawing Title LEVEL 1 PLAN</p> <p>Approved: Project Director</p>	<p>Project Title PATIENT PARKING GARAGE EXPANSION DEPARTMENT OF VETERANS AFFAIRS NORTH TEXAS VETERANS HEALTH CARE CENTER 4500 S. LANCASTER ROAD DALLAS, TEXAS 75216</p> <p>Location</p> <table><tr><td>Date</td><td>Checked</td><td>Drawn</td></tr><tr><td>Issue Date</td><td>JEW</td><td>SOA</td></tr></table>	Date	Checked	Drawn	Issue Date	JEW	SOA	<p>Project Number 549-906</p> <p>Building Number 80</p> <p>Drawing Number S-101</p> <p>Dwg. 49 of 93</p>	<p>Office of Construction and Facilities Management</p> <p>Department of Veterans Affairs</p>
Date	Revisions																							
2-24-14	DD2 COST ESTIMATE SET																							
3-05-14	35% CD SET - NOT FOR CONSTRUCTION																							
4-30-14	65% CD SET - NOT FOR CONSTRUCTION																							
6-03-14	95% CD SET - NOT FOR CONSTRUCTION																							
7-15-14	100% CD SET																							
Date	Checked	Drawn																						
Issue Date	JEW	SOA																						