## ELECTRICAL SYMBOLS - DIAGRAM

- DELTA CONNECTION
- MOTOR, SINGLE–PHASE
- MOTOR, THREE–PHASE
- TRANSFORMER
- WYE CONNECTION
- EARTH GROUND
- JUNCTION BOX
- PULL BOX
- NORMALLY CLOSED RELAY CONTACT
- NORMALLY OPEN RELAY CONTACT
- FUSE WITH RATING
- MOLDED CASE CIRCUIT BREAKER
- LOW–VOLTAGE DRAWOUT AIR CIRCUIT BREAKER
- SWITCH AND FUSE UNIT
- FUSED DRAWOUT POTENTIAL TRANSFORMER
- RELAY
  50 = INSTANTANEOUS OVERCURRENT OR RATE–OF–RISE
  51 = AC–TIME OVERCURRENT
  67 = AC–DIRECTIONAL OVERCURRENT
  86 LOCKING OUT
- DISCONNECT SWITCH, FUSED
- DISCONNECT SWITCH, UNFUSED
- FUSIBLE LINK
- STARTER, COMBINATION WITH DISCONNECT SWITCH
- STARTER OR MOTOR CONTROLLER
- TIME CLOCK
- GENERATOR, POWER
- BATTERY
- CAPACITOR
- POTHEAD
- STRESS CONE
- LIGHTNING ARRESTOR
- RECTIFIER, CATHODIC PROTECTION SANITARY
- METER
- AMMETER
- VOLTMETER
- WATTMETER
- WATT–HOUR METER
- PANELBOARD
- CABLE AND CONDUIT TAG
  SEE SCHEDULE
- EQUIPMENT TAG
  SEE EQUIPMENT SCHEDULE

## ELECTRICAL SYMBOLS - POWER PLAN

- MOTOR, SINGLE–PHASE
- MOTOR, THREE–PHASE
- TRANSFORMER, PLAN
- WYE CONNECTION
- EARTH GROUND
- POWER JUNCTION BOX
- DOUBLE GANG DEEP AUDIO/VISUAL JUNCTION BOX
- LADDER CABLE TRAY
- BRANCH CIRCUIT HOMERUN. LINES INDICATE NUMBER OF CIRCUITS, NEUTRAL, AND SWITCH LEG CONDUCTORS. ONE SEPARATE GREEN GROUNDING CONDUCTOR SHALL BE PROVIDED FOR EACH HOMERUN; NOT SHOWN
- PULL BOX
- WIREWAY
- RC = RIGID CONDUIT LINE
- DB = DIRECT BURIAL CABLE
- P = POWER DUCT
- SUBSTATION
- FLOOR OUTLET, DATA COMMUNICATION
- OUTLET, DATA COMMUNICATION
- PUSH BUTTON
- DISTRIBUTION PANEL
- LIGHTING PANEL
- PANELBOARD CABINET, FLUSH MOUNTED
- PANELBOARD CABINET, SURFACE MOUNTED
- RECEPTACLE, DUPLEX
- RECEPTACLE, DUPLEX ON EMERGENCY POWER
- RECEPTACLE, DUPLEX WITH GROUND FAULT CIRCUIT INTERRUPTER
- RECEPTACLE, QUADRAPLEX
- RECEPTACLE, SINGLE
- RECEPTACLE, SINGLE WITH SWITCH
- RECEPTACLE, SPECIAL PURPOSE
  A = 120V, 20A, 1 PHASE, 2–POLE, 3W, NEMA 5–20R.
  B = 208V, 20A, 1 PHASE, 2–POLE, 3W, NEMA 6–20R.
  C = 120V, 30A, 1 PHASE, 2–POLE, 3W, NEMA 5–30R.
  D = 208V, 30A, 1 PHASE, 2–POLE, 3W, NEMA 6–30R.
  E = 208V, 60A, 1 PHASE, 3–POLE, 4W, NEMA 14–60R.
  F = 208V, 30A, 3 PHASE, 3–POLE 4W, NEMA 15–30R.
  G = 208V, 50A, 3 PHASE, 3 POLE, 4W, NEMA 15–30R.
  H = 208V, 60A, 3 PHASE, 3 POLE, 4W, NEMA 15–60R.
- RECEPTACLE, SWITCHED DUPLEX
- DROP CORD, SINGLE CONVENIENCE OUTLET, 3–WIRE, GROUNDING TYPE, 20A, W/#12 CONDUCTORS IN FLEXIBLE CORD (CENTER LINE OF OUTLET: 6'–6" [1981mm] AFF. MINIMUM).
- ELECTRICAL STRIP MOLD (OUTLETS ON 2'–0" [610mm] CENTERS OR AS DESIGNATED ON DRAWINGS), MTD 3'–6" [1067mm] AFF OR AS INDICATED.
- 3–GANG COMPARTMENT BOX IN FLOOR FOR TELEPHONE, DATA & RECEPTACLE.
- RELAY; LETTER INDICATES RELAY TYPE
  50 = INSTANTANEOUS OVERCURRENT OR RATE–OF–RISE
  51 = AC–TIME OVERCURRENT
  67 = AC–DIRECTIONAL OVERCURRENT
  86 = LOCK OUT
- DISCONNECT SWITCH, FUSED
- DISCONNECT SWITCH, UNFUSED
- STARTER, COMBINATION WITH DISCONNECT SWITCH
- STARTER OR MOTOR CONTROLLER
- VARIABLE FREQUENCY DRIVE
- TIME CLOCK
- CONDUIT TERMINATED 6" [152mm] AFF IN STANDARD BOX FOR EXTENSION TO EQUIPMENT AS DIRECTED.
- CONDUIT TERMINATED W/COUPLING (FLUSH W/FINISHED FLOOR) FOR EXTENSION TO EQUIPMENT AS DIRECTED.
- SWITCH
  F = FUSED SWITCH — K = KEY OPERATED
  L = LOCK — LM= LOW VOLTAGE MASTER
  M = MANUAL MOTOR STARTING — MC= MOMENTARY CONTACT
  MP= MOTOR SNAP WITH PILOT LIGHT — P = WITH PILOT LIGHT
  (THERMAL TYPE)
  PB= PUSH BUTTON STATION — RC= REMOTE CONTROL
  WP= WEATHER PROOF — X = EXPLOSION PROOF

## ELECTRICAL SYMBOLS - LIGHTING PLAN

- SWITCH
  BLANK = SINGLE POLE — 2 = DOUBLE POLE
  3 = THREE–WAY — 4 = FOUR–WAY
  D = DOOR SWITCH
  DM= DIMMER — K = KEY OPERATED
  LV= LOW VOLTAGE — L = LOCK
  LM= LOW VOLTAGE MASTER — P = WITH PILOT LIGHT
  PB= PUSH BUTTON STATION — RC= REMOTE CONTROL
  T = TIMER OPERATED — WP= WEATHER PROOF
  X = EXPLOSION PROOF — Mo= OCCUPANCY SENSOR
- SWITCH, OCCUPANCY SENSOR REFER TO FIXTURE SCHEDULE FOR TYPE
- SWITCH, EXTERIOR PHOTO CELL FOR CONTROL OF EXTERIOR LIGHTING
- SWITCH, LAMP HOLDER POLE
- LIGHT FIXTURE RECESSED ROUND CEILING MOUNTED DOWNLIGHT
- LIGHT FIXTURE RECESSED SQUARE CEILING MOUNTED DOWNLIGHT
- LIGHT FIXTURE, RECESSED FLUORESCENT, 2'x4' [610x1220mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, RECESSED FLUORESCENT, 1'x4' [305x1220mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, RECESSED FLUORESCENT, 1'x8' [305x2439mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, SURFACE MOUNTED FLUORESCENT, 2'x4' [610x1220mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, SURFACE MOUNTED FLUORESCENT, 1'x4' [305x1220mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, SURFACE MOUNTED FLUORESCENT, 1'x8' [305x2439mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, FLUORESCENT EMERGENCY; LETTER INDICATES TYPE.
- LIGHT FIXTURE, RECESSED FLUORESCENT, 2'x2' [610x610mm]; LETTER INDICATES TYPE.
- LIGHT FIXTURE, SURFACE MOUNTED FLUORESCENT, 2'x2' [610x610mm]; LETTER INDICATES TYPE.
- LIGHT TRACK WITH HEADS AS SHOWN
- LIGHT FIXTURE, STRIP/INDUSTRIAL FLUORESCENT; LETTER INDICATES TYPE.
- LIGHT FIXTURE, WALL MOUNTED
- LIGHTING, UNDERCABINET LIGHT/COVE LIGHT
- LIGHTING, STEP LIGHT
- LIGHTING, ONE HEAD EMERGENCY BATTERY POWER
- LIGHTING, TWO HEAD EMERGENCY BATTERY POWER
- LIGHTING, THREE HEAD EMERGENCY BATTERY POWER
- STREET LIGHT WITH BRACKET
- LIGHT POLE, ONE MAST ARM, ONE LUMINAIRE
- LIGHT POLE, TWO MAST ARMS, TWO LUMINAIRES
- LIGHT POLE, POST TOP MOUNT LUMINAIRE
- LIGHT POLE, ONE LUMINAIRE
- LIGHT POLE, TWO LUMINAIRES
- LIGHTING, EXTERIOR BUILDING
- EXTERIOR FLOOD LIGHT
- EXIT SIGN, WALL MOUNTED WITH DIRECTIONAL ARROWS AND FACES AS SHOWN
- EXIT SIGN, CEILING MOUNTED WITH DIRECTIONAL ARROWS AND FACES AS SHOWN
- LIGHT FIXTURE, BOLLARD
- LIGHT FIXTURE, DIRECTIONAL
- LIGHT FIXTURE, HANDRAIL

## ELECTRONIC SAFETY AND SECURITY SYMBOLS

- CONTROL PANEL; LETTER INDICATES AS FOLLOWS:
  M=MOUNT
  C–CEILING D–DESK F–FLUSH H–HIDDEN M–MULLION
  P–PEDESTAL R–RACK S–SURFACE W–WALL
  T=TECHNOLOGY/TYPE
  B–BURGLAR D–DOOR F–FIRE P–PERIMETER
- KEYPAD DEVICE; LETTER INDICATES AS FOLLOWS:
  M=MOUNT
  C–CEILING D–DESK F–FLUSH H–HIDDEN
  M–MULLION
  P–PEDESTAL R–RACK S–SURFACE W–WALL
- SECURITY ACCESS, SWITCH, BALANCED MAGNETIC CONTROL
- SACP = SECURITY ALARM CONTROL PANEL BY ADT
- ALARM, FIRE, PANEL; LETTERS INDICATE AS FOLLOWS:
  FACC = CENTRAL CONSOLE FACP = CONTROL PANEL
  MFACP= MASTER CONTROL PANEL
  FAAP = ANNUNCIATOR PANEL
- ALARM, FIRE; LETTERS INDICATE AS FOLLOWS:
  BATT = BATTERIES CHR = CHARGER
  FAR = RECORDER
- ALARM, FIRE, POST INDICATOR VALVE.
- ALARM, TRANSPONDER OR TRANSMITTER
- ALARM, FIRE, MANUAL PULL STATION
- ALARM, HORN/LIGHT, ONE ASSEMBLY
- ALARM, SPEAKER/LIGHT, ONE ASSEMBLY
- ALARM, HORN/LIGHT, SEPARATE ASSEMBLY
- ALARM, LAMP LIGHT, SIGNAL LIGHT, STROBE
- ELECTROMAGNETIC TYPE DOOR HOLDER OUTLET
- ALARM, TAMPER SWITCH
- DETECTOR, FLOW SWITCH
  DETECTOR, HEAT; LETTER INDICATES AS FOLLOWS:
  R/T = COMBINATION F = FIXED TEMPERATURE RISE
  R/C = RATE COMPENSATION R = RATE OF RISE
- DETECTOR; LETTER INDICATES AS FOLLOWS:
  BLANK = SMOKE DETECTOR
  H = HEAT SMOKE
  I = IONIZATION SMOKE
  P = PHOTOELECTRIC SMOKE
  IH = IONIZATION AND HEAT SMOKE
  IP = IONIZATION AND PHOTOELECTRIC SMOKE
  PH = PHOTOELECTRIC AND HEAT SMOKE
  IPH = IONIZATION, PHOTOELECTRIC, AND HEAT
- DETECTOR, SMOKE, FOR DUCT
- FIRE ALARM LINE = FA
- FIRE ALARM SIGNALING DEVICE ASSOCIATED WITH SMOKE DETECTOR

## ELECTRICAL ABBREVIATIONS

| | |
|---|---|
| 1PH | SINGLE–PHASE |
| 1P | SINGLE POLE |
| 2/C | TWO–CONDUCTOR |
| 3/C | THREE–CONDUCTOR |
| 3PH | THREE–PHASE |
| 4/C | FOUR–CONDUCTOR |
| 4W | FOUR–WIRE |
| A/C UNIT | AIR CONDITIONING UNIT |
| A/E | ARCHITECT/ENGINEER |
| AAP | ALARM ANNUNCIATOR PANEL |
| AC | ALTERNATING CURRENT OR ARMORED CABLE |
| ACC | ACCESSIBLE |
| ADDL | ADDITIONAL |
| ADJ | ADJACENT, ADJOINING |
| ADO | AUTOMATIC DOOR OPENER |
| AF | AMPERE FRAME OR AMP FUSE |
| AFC | ABOVE FINISHED COUNTER, AUTOMATIC FREQUENCY CONTROL, OR AVAILABLE FAULT CURRENT |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AH | AMPERE HOUR |
| AHJ | AUTHORITY HAVING JURISDICTION |
| AIC | AMPERE INTERRUPTING CAPACITY |
| ALT | ALTERNATE |
| AMB OR A | AMBIENT |
| AMP | AMPERE |
| ARCH | ARCHITECT |
| ASC | AMPS SHORT CIRCUIT |
| AT | AMPERE TRIP |
| ATS | AUTOMATIC TRANSFER SWITCH |
| AUTO | AUTOMATIC |
| AV | AUDIO VISUAL |
| BAT | BATTERY |
| BC | BARE COPPER |
| BD | BOARD |
| BFF | BELOW FINISH FLOOR |
| BIL | BASIC INSULATION LEVEL |
| BLDG | BUILDING |
| BPIP | BOILER PLANT INSTRUMENTATION PANEL |
| BRKR | BREAKER |
| BYP | BY PASS |
| C | CONDUIT |
| CAB | CABINET |
| CALC | CALCULATE |
| CAP | CAPACITY |
| CAT | CATALOG |
| CATV | COMMUNITY ANTENNA TELEVISION |
| CCR | CONTROL CONTACTOR |
| CCTV | CLOSED CIRCUIT TELEVISION |
| cd | CANDELA |
| CD | CONSTRUCTION DOCUMENTS |
| CF | CONTRACTOR FURNISHED |
| CF/CI | CONTRACTOR FURNISHED/CONTRACTOR INSTALLED |
| CF/OI | CONTRACTOR FURNISHED/OWNER INSTALLED |
| CFE | CONTRACTOR FURNISHED EQUIPMENT |
| CHW | CHILLED WATER |
| CHWP | CHILLED WATER PUMP |
| CKT | CIRCUIT |
| CKT BRKR | CIRCUIT BREAKER |
| CLF | CURRENT LIMITING FUSE |
| CLG | CEILING |
| CMU | CONCRETE MASONRY UNIT |
| COAX | COAX CABLE |
| COMM | COMMUNICATION |
| COMPT | COMPARTMENT |
| CONC | CONCRETE |
| CONT | CONTINUE |
| CONTR | CONTRACTOR |
| COORD | COORDINATE |
| CPT | CONTROL POWER TRANSFORMER |
| CRI | COLOR RENDERING INDEX |
| CT | CURRENT TRANSFORMER |
| CTV | CABLE TELEVISION |
| CU | COPPER |
| CU FT | CUBIC FEET |
| CUR | CURRENT |
| DB | DECIBEL OR DIRECT BURIAL |
| DC | DIRECT CURRENT |
| DCP | DIMMER CONTROL PANEL |
| DEG C | DEGREES CELSIUS |
| DEG F | DEGREES FAHRENHEIT |
| DEMO | DEMOLITION |
| DIAG | DIAGRAM |
| DISC | DISCONNECT |
| DISTR | DISTRIBUTION |
| DISTR PNL | DISTRIBUTION PANEL |
| DMR SW | DIMMER SWITCH |
| DN | DOWN |
| DPDT | DOUBLE POLE, DOUBLE THROW |
| DPST | DOUBLE POLE, SINGLE THROW |
| DRSW | DOOR SWITCH |
| DS | DISCONNECT SWITCH |
| DWG | DRAWING |
| E | EXISTING TO REMAIN |
| EC | ELECTRICAL CONTRACTOR |
| EG | EQUIPMENT GROUND |
| EL | ELEVATION |
| ELEC | ELECTRIC OR ELECTRICAL |
| ELEV | ELEVATOR |
| EMCP | EMERGENCY MONITORING CONTROL PANEL |
| EMER | EMERGENCY |
| EMI | ELECTROMAGNETIC INTERFERENCE |
| EMT | ELECTRICAL METALLIC TUBING |
| ENCL | ENCLOSURE |
| EPO | EMERGENCY POWER OFF |
| EPRF | EXPLOSION PROOF |
| ESMT | EASEMENT |
| EWC | ELECTRIC WATER COOLER |
| EWH | ELECTRIC WATER HEATER |
| EXIST | EXISTING |
| FA | FIRE ALARM |
| FAAP | FIRE ALARM ANNUNCIATOR PANEL |
| FABL | FIRE ALARM BELL |
| FABX | FIRE ALARM BOX |
| FACP | FIRE ALARM CONTROL PANEL |
| FC | FOOTCANDLE |
| FI | FILM ILLUMINATOR |
| FIXT | FIXTURE |
| FLA | FULL LOAD AMPS |
| FLEX | FLEXIBLE METALLIC CONDUIT |
| FLT | FLOODLIGHT |
| FLUOR | FLUORESCENT |
| FLUOR FIX | FLUORESCENT FIXTURE |
| FOUTT | TELEPHONE FLOOR OUTLET |
| FP | FIRE PROTECTION |
| FT | FEET OR FOOT |
| FU SW | FUSED SWITCH |
| FVNR | FULL VOLTAGE NON–REVERSING |
| FVR | FULL VOLTAGE REVERSING |
| G OR GND | GROUND OR GENERATOR |
| GEN | GENERATOR |
| GFCI | GROUND FAULT CIRCUIT INTERRUPTER |
| GTB | GROUND TERMINAL BOX |
| HID | HIGH INTENSITY DISCHARGE |
| HOA | HAND–OFF–AUTOMATIC |
| HP | HORSEPOWER |
| HT | HEIGHT |
| HZ | HERTZ |
| IESNA | ILLUMINATION ENGINEERING SOCIETY OF NORTH AMERICA |
| IMC | INTERMEDIATE METAL CONDUIT |
| INCAND | INCANDESCENT |
| IR | INFRARED |
| IWH | INSTANTANEOUS WATER HEATER |
| J–BOX | JUNCTION BOX |
| kV | KILOVOLT |
| kVA | KILOVOLT AMPERE |
| kVAH | KILOVOLT AMPERE PER HOUR |
| kVAR | KILOVOLT AMPERE REACTIVE |
| kW | KILOWATT |
| kWH | KILOWATT HOUR |
| kWHM | KILOWATT HOUR METER |
| LED | LIGHT EMITTING DIODE |
| LF | LINEAR FEET (FOOT) |
| LM | LUMEN |
| LP | LIGHT POLE |
| LPS | LOW PRESSURE SODIUM |
| LRA | LOCKED ROTOR AMPS |
| LTCP | LOCAL TEMPERATURE CONTROL PANEL |
| LT | LIGHT |
| LTG | LIGHTING |
| LTG PNL | LIGHTING PANEL |
| LTNG | LIGHTNING |
| LV | LOW VOLTAGE |
| MATV | MASTER ANTENNA TELEVISION SYSTEM |
| MAX | MAXIMUM |
| MC | MECHANICAL CONTRACTOR |
| MCA | MINIMUM CIRCUIT AMPS |
| MCB | MAIN CIRCUIT BREAKER |
| MCC | MOTOR CONTROL CENTER |
| MDP | MAIN DISTRIBUTION PANEL |
| MECH | MECHANICAL |
| MG | MOTOR GENERATOR |
| MH | MANHOLE |
| MIN | MINIMUM |
| MOCP | MAXIMUM OVERCURRENT PROTECTION |
| MLO | MAIN LUGS ONLY |
| MT | MOUNT |
| MTD | MOUNTED |
| MTG | MOUNTING |
| MTS | MANUAL TRANSFER SWITCH |
| MV | MEDIUM VOLTAGE |
| MVA | MEGAVOLT–AMPERE |
| MW | MEGAWATT MICROWAVE |
| NA | NOT APPLICABLE |
| NEC | NATIONAL ELECTRICAL CODE |
| NEMA | NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION |
| NEUT OR N | NEUTRAL |
| NFPA | NATIONAL FIRE PROTECTION ASSOCIATION |
| NIC | NOT IN CONTRACT |
| NL | NIGHT LIGHT |
| NO | NORMALLY OPEN |
| NS | NO SCALE |
| NTS | NOT TO SCALE |
| OC | ON CENTER |
| OD | OUTSIDE DIAMETER |
| OL | OVERLOAD |
| P | POLE |
| PA | PUBLIC ADDRESS |
| PB | PANELBOARD, PULL BOX, OR PUSHBUTTON |
| PBPU | PREFABRICATED BEDSIDE PATIENT UNIT |
| PCB | POLYCHLORINATED BIPHENYL |
| PEC | PHOTOELECTRIC CELL |
| PED | PEDESTAL |
| PEND | PENDANT |
| PF | POWER FACTOR |
| PH | PHASE |
| PNL | PANEL |
| POD | POWER OPERATED DAMPER |
| PT | POTENTIAL TRANSFORMER |
| PTRV | POWER TYPE ROOF VENTILATION |
| PVC | POLYVINYL CHLORIDE (PLASTIC) |
| PWR | POWER |
| RCP | REFLECTED CEILING PLAN |
| REC | RECESSED |
| RECPT | RECEPTACLE |
| RGS | RIGID GALVANIZED STEEL |
| RM | ROOM |
| RMS | ROOT MEAN SQUARE |
| REQD | REQUIRED |
| SCC | SHORT CIRCUIT CAPACITY |
| SES | SERVICE ENTRANCE SECTION |
| SD | SMOKE DETECTOR |
| SF | SQUARE FOOT (FEET) |
| SHT | SHEET |
| SI | INTERNATIONAL SYSTEM OF UNITS |
| SPEC | SPECIFICATION |
| SPST | SINGLE POLE, SINGLE THROW |
| SURF | SURFACE |
| SW | SWITCH |
| SWBD | SWITCHBOARD |
| SWGR | SWITCHGEAR |
| TC | TIME CLOCK |
| TEL | TELEPHONE |
| TP | TWISTED PAIR |
| TPS | TWISTED PAIR SHIELDED |
| TTB | TELEPHONE TERMINAL BOARD |
| TV | TELEVISION |
| TYP | TYPICAL |
| UFD | UNDERFLOOR DUCT |
| UGND | UNDERGROUND |
| UL | UNDERWRITERS LABORATORY |
| UON | UNLESS OTHERWISE NOTED |
| UPS | UNINTERRUPTIBLE POWER SUPPLY |
| UTIL | UTILITY |
| V | VOLT |
| VA | VOLT AMPERE |
| VAR | VOLT AMPERE REACTIVE |
| VFD | VARIABLE FREQUENCY DRIVE |
| VOLT | VOLTAGE |
| W | WATT |
| WH | WATER HEATER |
| WP | WEATHERPROOF |
| XFER | TRANSFER |
| XFMR | TRANSFORMER |
| X | EXISTING DEVICE OR EQUIPMENT TO BE REMOVED |

ONLY APPLICABLE LEGEND AND ABBREVIATIONS USED FOR THIS PROJECT'S DRAWINGS.

FULLY SPRINKLERED

Scale: NONE

| Revisions: | Date |
|---|---|
| ISSUED FOR CONSTRUCTION DOCUMENTS (FINAL BID) | 11/26/13 |
| ISSUED FOR 100% DESIGN SUBMITTAL | 10/28/13 |
| ISSUED FOR 75% DESIGN DEVELOPMENT | 08/22/13 |

CONSULTANTS:

ARCHITECT/ENGINEERS:

EPSTEIN
600 West Fulton Street
Chicago, Illinois 60661

Drawing Title: ELECTRICAL SYMBOLS AND ABBREVIATIONS

Approved: Project Director

Project Title: REPLACEMENT OF AHU AC-30 IN BUILDING 11A

Location: 820 S. DAMEN AVE. CHICAGO, IL 60612

Date: 11/26/2013 | Checked: PD | Drawn: JF

Project Number: 537-10-122

Building Number: BUILDING 11A

Drawing Number: 11A-E-001

Dwg. 08 of 10

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231

P:\Projects\11000\11226\DISCIPLINE\Elec\Working Order #4\Sheets\AC-30\11226-E-001.dwg 11-25-13 05:00:34 PM jfarn