


# Asphalt Binder™

An Asphalt Emulsion Tack Coat Designed For Priming Oxidized Surfaces & Patchwork.



PRODUCT #	DESCRIPTION	WT.	PRICE
M1140P	5-gallon pail	46 lbs.	\$ 43.99
M1140D	55-gallon drum	515 lbs.	\$404.99
M1140B	Bulk		- quoted -

**Mixing Procedures:**

**Primer for coatings:**  
Asphalt Binder 10 gallons  
Water 80 gallons

**For use as a tack coat for patching or paving:**  
Asphalt Binder 10 gallons  
Water 10 gallons

**Material Requirements (coverage):**  
Dependant upon water dilution.

# Asphalt Binder Plus™

Polymer-Modified Asphalt Emulsion



- Asphalt Recycling Agent
- Pavement Rejuvenator/Fog Seal
- Crack Sealant For Road Application
- Tack Coat

PRODUCT #	DESCRIPTION	WT.	PRICE
M1145P	5-gallon pail	46 lbs.	\$ 52.99
M1145D	55-gallon drum	515 lbs.	\$514.99

**Mixing Procedures:**

**Recycling Agent for Infrared Patching:**  
Use as is. Dilution is not required.

**For use as a tack coat for patching or paving:**  
Dilute 1 to 1 with water. Apply by spray or brush. Apply at a rate of .06 to .10 gallons of mixed material per square yard (.03 to .05 concentrate).

**Material Requirements (coverage):**  
Reference the Material Specification Sheet.

# SealMaster® Oil Spot Primers

Seals oil, gas, and grease spots on pavement prior to sealcoating. Helps prevent oil spots from bleeding up through freshly applied pavement sealer.

Apply by Spray or Brush.



Brushes - p.57  
Chapin Sprayer - p.61

# Petro Seal™

Concentrated Oil Spot Primer

- Can be diluted up to one part Petro Seal and two parts water.
- Apply by spray or brush.



PRODUCT #	DESCRIPTION	WT.	PRICE
M1120P	5-gallon pail	47 lbs.	\$ 82.99
M1120D	55-gallon drum	520 lbs.	\$846.99

**Mixing Procedures:**

Can be diluted up to one part Petro Seal and two parts water. However, a 1 to 1 dilution rate is typically recommended. Mix thoroughly before applying.

**Material Requirements (coverage):**

One gallon of Petro Seal when mixed 1 to 1 with water will cover approximately 300-400 square feet.



# Prep Seal™

Ready To Use Oil Spot Primer

- No dilution required.
- Apply by spray or brush.
- Available in 1-gallon and 5-gallon containers.

PRODUCT #	DESCRIPTION	WT.	PRICE
M1130G	1-gallon jug	9 lbs.	\$ 13.99
M1130P	5-gallon pail	46 lbs.	\$ 33.99

**Mixing Procedures:**

Prep Seal is a ready-to-use product. Do not dilute. Use as is. Stir thoroughly before applying.

**Material Requirements (coverage):**

One gallon of Prep Seal will cover approximately 150-200 square feet.

# TarBuster™

The environmentally friendly full strength tar & asphalt remover. Non-offensive citrus aroma.

TarBuster's Industrial formulation safely penetrates, dissolves, and removes the toughest: **Oil, Asphalt, Grease, Sludge, and Asphalt Pavement Sealer** (not recommended for removal of coal tar).

- Biodegradable
- Non-Toxic
- Non-Corrosive
- Citrus Aroma

**TarBuster is FAST ACTING:**

In as little as 30 seconds you'll see how TarBuster cuts cleanup time in the toughest cleaning applications.

PRODUCT #	DESCRIPTION	WT.	PRICE
T2087	TarBuster wipes	2 lbs.	\$ 20.99
T2078	1-gallon jug	9 lbs.	\$ 49.99
T2080	1-gallon jugs (case of 4)	34 lbs.	\$ 199.99
T2082	5-gallon pail	41 lbs.	\$ 202.99
T2084	55-gallon drum	440 lbs.	\$1,493.99



# Tarpedo™

Tarpedo Destroys & Quickly Dissolves Coal Tar Sealer!

- Use on tools, equipment and vehicles.
- Rinses easily with water.
- High flash point (145°F) formula.
- Also removes asphalt and other tough substances.

PRODUCT #	DESCRIPTION	WT.	PRICE
T2090	1-gallon jug	9 lbs.	\$ 48.99
T2092	(case of 4) 1-gallon jugs	34 lbs.	\$ 195.99
T2094	5-gallon pail	41 lbs.	\$ 212.99
T2096	55-gallon drum	440 lbs.	\$1,647.99



# MasterFlo™

Pavement Sealer Remover

- Removes coal tar, asphalt, and much more from a variety of surfaces.
- Water soluble ready-to-use formula.
- Can be used as a degreaser.

PRODUCT #	DESCRIPTION	WT.	PRICE
T2060	1-pint	2 lbs.	\$ 21.99
T2050	1-gallon jug	9 lbs.	\$ 54.99
T2065	5-gallon pail	41 lbs.	\$ 194.99
T2055	55-gallon drum	440 lbs.	\$1,681.99



**Application Instructions:**

Apply to surface and allow to penetrate for 30 seconds to 2 minutes. Scrub with brush or cloth. Rinse thoroughly with water.

Prices are F.O.B. Sandusky, Ohio. Prices are subject to change.