



1. THE INTENT OF THE DEMOLITION IS THE COMPLETE REMOVAL OF EACH EXISTING BUILDING SHOWN IN THEIR ENTIRETY INCLUDING ROOFS, FOUNDATIONS AND FOOTINGS AND ALL INTERIOR WALLS, DOORS, WINDOWS, FIXTURES, CASEWORK, FLOORS, CEILING AND FINISHES - NOTHING IS TO REMAIN.
2. THE CONTRACTOR TO OBTAIN THE PRESENCE OF HAZARDOUS MATERIALS IN BUILDING B AND C PER ASBESTOS SURVEY AND HAZARDOUS BUILDING MATERIALS ASSESSMENT BY TERRACON DATE MAY 15, 2013. THIS REPORT IS NOT TO BE CONSIDERED ALL INCLUSIVE. PRIOR TO DEMOLITION AND AS PART OF THE PROJECT, THE CONTRACTOR SHALL PROVIDE A COMPREHENSIVE HAZARDOUS MATERIALS INVENTORY OF ALL THE BUILDINGS TO BE DEMOLISHED.
3. THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS AND DIMENSIONS WITHIN THE CONTRACT LIMITS AND ANY DISCREPANCIES FIRST IN THE CONTRACT AND THEN FIELD CONDITIONS. ANY DISCREPANCIES SHALL BE NECESSITATED BY FIELD CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND OWNER.
4. THE CONTRACTOR SHALL VERIFY WITH PROPER AUTHORITIES THE UTILITY LOCATIONS PRIOR TO COMMENCEMENT OF WORK.
5. ALL ADDITIONAL ASBESTOS AND INTERIOR PHOTOS; ALL SALVAGEABLE EQUIPMENT, TOOLS, MISC. STORAGE ITEMS ETC. SHALL BE REMOVED BY THE OWNER PRIOR TO DEMOLITION WORK.

BUILDING B - FARM HOUSE (1935|1996)

BASEMENT	1,164 G.S.F.
LEVEL 1	2,173 G.S.F.
<u>LEVEL 2</u>	<u>921 G.S.F.</u>
TOTAL:	4,258 G.S.F.

LEVEL 1 896 G.S.F

BUILDING D - HORSE BA

LEVEL 1 2,194 G.S.F.

LEVEL 1	2,194 G.S.F.
LEVEL 2	545 G.S.F.
<u>TOTAL:</u>	<u>2,739 G.S.F.</u>



ARCHITECT/ENGINEERS:



517 7th street
rapid city sd 57701
p 605.342.9470
f 605.342.2377
www.4front.biz

Existing Conditions Floor Plans And Photos

Rodney Duich,
P.E.

Demolition of Existing Buildings at Ft.
Scott Cemetery -1696.028

Location	816 East National
----------	-------------------

Checked
LG

Drawn
JA

789CM3914

Building Number

Building Number

Drawing Number

AD1.00

BID DOCUMENTS

NCA DESIGN
AND CONSTRUCTION
SERVICE

