

# Locker Rooms Faucets Repair

PVAMC, 3900 Baltimore AVE

Philadelphia PA 19104

Provide labor, supervision and material for each sink repair as follow:

- 1- Demolish and dispose existing faucets, traps, accessories and grid strainers for the locker rooms sinks.
- 2- Install new American Standard faucets or equivalent units with wrist blade handles, goose neck spouts and accessories.
- 3- Provide and install new 1 ½" chrome trap and 90 with grid strainer.
- 4- Total 38 sinks need to repairs listed on item 1,2 and 3:

2nd floor building 2 locker rooms.....total (9) nine sinks

4<sup>th</sup> floor building 2 locker rooms.....total (12) twelve sinks

6<sup>th</sup> floor building 2 locker rooms.....total (17) seventeen sinks

- 5- All work shall be performed during normal working hours of 7:00 AM and 4:00 PM.
- 6- All work shall be coordinated with the plumbing Foreman at 215-823-4127.
- 7- Work shall be scheduled through the plumbing foreman, for the availability of the locker room. The contractor must be aware that, work is in occupied space and rooms cannot be available certain time such as at shift change.
- 8- Job duration will be sixty (60) calendar days from contract award.
- 9- Any water shutdown must be scheduled with the plumbing foreman at 215-823-4127.
- 10- Contractor must clean the work area after complete the work on daily basis.