E3 SYSTEMS FLOOR PLAN
1/8" = 1'-0"

PLAN NORTH

PROJECT NOTE

A. PROVIDE A LIGHTNING PROTECTION SYSTEM. SEE SPECIFICATION 26 41 00 FOR REQUIREMENTS.

SYSTEMS KEYED NOTES

1. PROVIDE J-HOOKS FOR SIGNAL CABLES. SEE DATA/COMM RISER AND SPECS.
2. TELEPHONE TERMINAL BOARD. 4' WIDE X 8' TALL X 3/4" THICK PLYWOOD.
3. CONDUITS STUBBED UP FOR INCOMING TELE/DATA, CABLE TV UTILITY SERVICES.
4. 19" SERVER RACK. PROVIDE X-MARK/CDT XSL72 DATA SLIM RACK OR ENGINEER APPROVED EQUAL. PROVIDE RACK FRAME AND MOUNTING ACCESSORIES ONLY. PROVIDE TWO RACKS. SEE RISER FOR MORE DETAILS.



KEY PLAN

FULLY SPRINKLERED
100% CONSTRUCTION DOCUMENTS

Revisions:	Date

CONSULTANTS:

PETTIT & PETTIT
Consulting Engineers, Inc.
Heritage West Building, Suite 400
201 East Markham Street
Little Rock, Arkansas 72201-1631 Telephone [501] 374-3731

CORPORATE REGISTRATION PETTIT & PETTIT CONSULTING ENGINEERS, INC. No. 78 ARKANSAS ENGINEER
© 2012

STATE OF ARKANSAS REGISTERED PROFESSIONAL ENGINEER No. 12363 ANTHONY DAVID JACOBS

ARCHITECT / ENGINEERS:

TAGGART ARCHITECTS
4500 Burrow Drive
North Little Rock, AR 72116
Phone: 501-758-7443
Fax: 501-753-7309
www.taggarch.com

Drawing Title: RESIDENTIAL TREATMENT BUILDING SYSTEMS FLOOR PLAN

Approved: Project Director

Project Title: **Renovate Leroy Pond Army Reserve Center for Mental Health Residentail Rehabilitation Treatment/ Police Training**

Location: **Fayetteville, AR**

Date: 9/7/12 | Checked: ADA | Drawn: RAS

Project Number: **564-341**

Building Number:

Drawing Number: EY-105

Dwg. 115 of 126

Office of Facilities Management

DEPARTMENT OF VETERANS AFFAIRS

VA FORM 08-6231, OCT 1978