

**SECTION 09 06 00  
SCHEDULE FOR FINISHES**

Addendum 1  
October 9, 2015

**SECTION 09 06 00-SCHEDULE FOR FINISHES**

VAMC: Viera Clinic

Location: Viera VA Outpatient Clinic 2900 Veterans Way, Viera, FL 32940

Project no. and Name:675-14-150 Renovate Laboratory & Radiology Department

Submission Final

Date:07 AUG 2015

**INSTRUCTIONS FOR PREPARATON OF  
SECTION 09 06 00-SCHEDULE FOR FINISHES**

**PART I - GENERAL**

**1.1 DESCRIPTION**

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

**1.2 MANUFACTURERS**

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

**1.3 SUBMITALS**

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES provide quadruplicate samples for color approval of materials and finishes specified in this section.

**1.4 APPLICABLE PUBLICATIONS**

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

**PART 2- PRODUCTS**

**2.1 DIGITAL COLOR PHOTOS**

**2.2 DIVISION 06WOOD, PLASTICS, AND COMPOSITES**

A. SECTION 06 10 00, ROUGH CARPENTRY

Item	Finish	Color

B. SECTION 06 20 00, FINISH CARPENTRY

1. RECEPTION COUNTER					
Room No. and Name	Component	Material		Finish	Color
Reception C103	Countertop	Solid Surface (Dupont Quartz)		As Specified	Zodiaq Autumn Light
	Vertical Surface(s) Walls	Painted GW3		Eggshell	SW 6112 Biscuit
	Base	Rubber Cove		As Specified	Johnsonite 150 Wetlands

2. VANITIES (TYPES S4, S4 M)		
Room No. and Name	Component	Finish/Color
C116, C117, C119 Ultrasound	Countertop Solid Surface	Zodiaq Autumn Light

2.3 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Frame	Painted to match existing color and gloss level

Renovate Laboratory & Radiology Departments  
 Viera VA Outpatient Clinic, Viera, FL

B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	Refinish if damaged to match existing

C. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Match Existing	Match Existing
Door Closers	Match Existing	Match Existing
Closer/ Holder	Match Existing	Match Existing
Lock/ Latches	Match Existing	Match Existing
Kick Mop Plates	Metal Plastic	Match Existing

D. SECTION 09 30 13

Finish Code	Manufacturer	Mfg. Color Name/No.
Floor	Note: Owner (VA) is currently renovating existing toilet rooms in the Radiology/Lab Area. Consult VA for C.T. Materials and colors to match.	
Wall		

Addendum 1  
 October 9, 2015

E. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
	Exposed Suspension System	White	Armstrong	Prelude ML15/16" Exposed Tee
	Type III	White Non-Directional	Armstrong	Ortega T04

Renovate Laboratory & Radiology Departments  
 Viera VA Outpatient Clinic, Viera, FL

F. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
		VCT	TBD	TBD
		R	TBD	TBD

G. SECTION 09 65 16, VINYL SHEET FLOORING, HEAT WELDED SEAMS (WSF)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.

1. SECTION 09 65 16, WELDING RODS (WSF)

Finish code	Manufacturer	Mfg. Color Name/No.

2. SECTION 09 65 16, CAP STRIPS (WSF)

Finish Code	Manufacturer	Mfg. Color Name/No.

**E<sup>H</sup>**. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
	Rubber Base (RB)	4"	Johnsonite	150 Wetlands

**Addendum 1**  
**October 9, 2015**

I. SECTION 09 67 23, EPOXY RESINOUS FLOORING (ERF)

Finish Code	Manufacturer	Mfg. Name/No.
	FlowCrete	Flowfast Flakes, Desert Tan

**H<sup>J</sup>**. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P-1	Eggshell	SW	6112 Biscuit

Renovate Laboratory & Radiology Departments  
 Viera VA Outpatient Clinic, Viera, FL

**2.4 DIVISION 10 - SPECIALTIES**

A. SECTION 10 21 23, HOSPITAL CUBILCE CURTAINS AND INTRAVENOUS SUPPORT TRACKS

Finish Code	Manufacturer	Mfg. Color Name/No.

B. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards	Plastic	INPRO	Match Existing
Wall Guards and Handrail	Plastic	INPRO	Match Existing

C. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS

Sign Type	Component	Manufacturer	Mfg. Color Name/No.
Match Existing	Match Existing	Match Existing	Match Existing

D. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Methyl Methacrylate	Dupont Quartz Zodiac Autumn Light
---------------------	-----------------------------------

**2.5 DIVISION 22 - PLUMBING**

A. SECTION 22 40 00, PLUMBING FIXTURES AND TRIM

Item	Color
Lavatories	White (Solid Surface - Integral to Countertop)



*Renovate Laboratory & Radiology Departments  
Viera VA Outpatient Clinic, Viera, FL*

B. ROOM FINISH SCHEDULE

All rooms (Except as noted below and on Drawings as marked.)in project boundry to receive:

1. New paint on all wall surfaces.
2. New VCT Flooring.
3. New Base.
4. New Ceiling Grid and Tile.

Exceptions:

1. RM C207 - Pathology Lab - Replace ceiling grid and tile only.
2. Corridor C200A - Pathology Lab - Replace ceiling grid and tile only.
3. Waiting C101 and C201 - Replace carpet tile to match existing; New Paint and New Base.

--- E N D---

THIS PAGE LEFT INTENTIONALLY BLANK