

**SECTION 01 91 00**  
**GENERAL COMMISSIONING REQUIREMENTS**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

- A. This Section 01 91 00 GENERAL COMMISSIONING REQUIREMENTS shall form the basis of the construction phase commissioning process and procedures. The Commissioning Agent shall add, modify, and refine the commissioning procedures, as approved by the Department of Veterans Affairs (VA), to suit field conditions and actual manufacturer's equipment, incorporate test data and procedure results, and provide detailed scheduling for all commissioning tasks.
- B. Various sections of the project specifications require equipment startup, testing, and adjusting services. Requirements for startup, testing, and adjusting services specified in the Division 7, Division 21, Division 22, Division 23, Division 26, Division 27, Division 28, and Division 31 series sections of these specifications are intended to be provided in coordination with the commissioning services and are not intended to duplicate services. The Contractor shall coordinate the work required by individual specification sections with the commissioning services requirements specified herein.
- C. Where individual testing, adjusting, or related services are required in the project specifications and not specifically required by this commissioning requirements specification, the specified services shall be provided and copies of documentation, as required by those specifications shall be submitted to the VA and the Commissioning Agent to be indexed for future reference.
- D. Where training or educational services for VA are required and specified in other sections of the specifications, including but not limited to Division 7, Division 8, Division 21, Division 22, Division 23, Division 26, Division 27, Division 28, and Division 31 series sections of the specification, these services are intended to be provided in addition to the training and educational services specified herein.
- E. Commissioning is a systematic process of verifying that the building systems perform interactively according to the construction documents and the VA's operational needs. The commissioning process shall encompass and coordinate the system documentation, equipment startup, control system calibration, testing and balancing, performance testing

and training. Commissioning during the construction, and post-occupancy phases is intended to achieve the following specific objectives according to the contract documents:

1. Verify that the applicable equipment and systems are installed in accordance with the contract documents and according to the manufacturer's recommendations.
  2. Verify and document proper integrated performance of equipment and systems.
  3. Verify that Operations & Maintenance documentation is complete.
  4. Verify that all components requiring servicing can be accessed, serviced and removed without disturbing nearby components including ducts, piping, cabling or wiring.
  5. Verify that the VA's operating personnel are adequately trained to enable them to operate, monitor, adjust, maintain, and repair building systems in an effective and energy-efficient manner.
  6. Document the successful achievement of the commissioning objectives listed above.
- F. The commissioning process does not take away from or reduce the responsibility of the Contractor to provide a finished and fully functioning product.
- G. The Commissioning Agent, both the firm and individual designated as the Commissioning Agent, shall be certified by at least one of the following entities: the National Environmental Balancing Bureau (NEBB), the Associated Air Balance Council Commissioning Group (AABC), and the Building Commissioning Association (BCA). Certification(s) shall be valid and active. Proof of certification(s) shall be submitted to the Contracting Officer and the Resident Engineer three (3) calendar days after the Notice to Proceed.

## **1.2 CONTRACTUAL RELATIONSHIPS**

- A. For this construction project, the Department of Veterans Affairs contracts with a Contractor to provide construction services. The contracts are administered by the VA Contracting Officer and the Resident Engineer as the designated representative of the Contracting Officer. On this project, the authority to modify the contract in any way is strictly limited to the authority of the Contracting Officer and the Resident Engineer.
- B. In this structure, only two contract parties are recognized and communications on contractual issues are strictly limited to VA

Resident Engineer and the Contractor. It is the practice of the VA to require that communications between other parties to the contracts (Subcontractors and Vendors) be conducted through the Resident Engineer and Contractor. It is also the practice of the VA that communications between other parties of the project (Commissioning Agent and Architect/Engineer) be conducted through the Resident Engineer.

- C. Whole Building Commissioning is a process that relies upon frequent and direct communications, as well as collaboration between all parties to the construction process. By its nature, a high level of communication and cooperation between the Commissioning Agent and all other parties (Architects, Engineers, Subcontractors, Vendors, third party testing agencies, etc) is essential to the success of the Commissioning effort.
- D. With these fundamental practices in mind, the commissioning process described herein has been developed to recognize that, in the execution of the Commissioning Process, the Commissioning Agent must develop effective methods to communicate with every member of the construction team involved in delivering commissioned systems while simultaneously respecting the exclusive contract authority of the Contracting Officer and Resident Engineer. Thus, the procedures outlined in this specification must be executed within the following limitations:
  - 1. No communications (verbal or written) from the Commissioning Agent shall be deemed to constitute direction that modifies the terms of any contract between the Department of Veterans Affairs and the Contractor.
  - 2. Commissioning Issues identified by the Commissioning Agent will be delivered to the Resident Engineer and copied to the designated Commissioning Representatives for the Contractor and subcontractors on the Commissioning Team for information only in order to expedite the communication process. These issues must be understood as the professional opinion of the Commissioning Agent and as suggestions for resolution.
  - 3. In the event that any Commissioning Issues and suggested resolutions are deemed by the Resident Engineer to require either an official interpretation of the construction documents or require a modification of the contract documents, the Contracting Officer or Resident Engineer will issue an official directive to this effect.

4. All parties to the Commissioning Process shall be individually responsible for alerting the Resident Engineer of any issues that they deem to constitute a potential contract change prior to acting on these issues.
5. Authority for resolution or modification of design and construction issues rests solely with the Contracting Officer or Resident Engineer, with appropriate technical guidance from the Architect/Engineer and/or Commissioning Agent.

### **1.3 RELATED WORK**

- A. Section 01 00 00 GENERAL REQUIREMENTS.
- B. Section 07 08 00 FACILITY EXTERIOR CLOSURE COMMISSIONING.
- C. Section 21 08 00 COMMISSIONING OF FIRE PROTECTION SYSTEMS.
- D. Section 22 08 00 COMMISSIONING OF PLUMBING SYSTEMS.
- E. Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS.
- F. Section 26 08 00 COMMISSIONING OF ELECTRICAL SYSTEMS.
- G. Section 27 08 00 COMMISSIONING OF COMMUNICATIONS SYSTEMS.
- H. Section 28 08 00 COMMISSIONING OF ELECTRONIC SAFETY AND SECURITY SYSTEMS.
- I. Section 31 08 00 COMMISSIONING OF UTILITIES.

### **1.4 SUMMARY**

- A. This Section includes general requirements that apply to implementation of commissioning without regard to systems, subsystems, and equipment being commissioned.
- B. The commissioning activities have been developed to support the VA requirements to meet guidelines for Federal Leadership in Environmental, Energy, and Economic Performance.
- C. The commissioning activities have been developed to support the United States Green Building Council (USGBC) LEED™ rating program and to support delivery of project performance in accordance with the VA requirements developed for the project.
  1. Commissioning activities and documentation for the LEED™ section on "Energy and Atmosphere" and the prerequisite of "Fundamental Building Systems Commissioning."
  2. Commissioning activities and documentation for the LEED™ section on "Energy and Atmosphere" requirements for the "Enhanced Building System Commissioning" credit.

3. Activities and documentation for the LEED™ section on "Measurement and Verification" requirements for the Measurement and Verification credit.
- D. The commissioning activities have been developed to support the Green Buildings Initiative Green Globes rating program and to support delivery of project performance in accordance with the VA requirements developed for the project.

## 1.5 DEFINITIONS

- A. Architect: Includes Architect identified in the Contract for Construction between the Department of Veterans Affairs and Contractor, plus consultant/design professionals responsible for design of fire suppression, plumbing, HVAC, controls for HVAC systems, electrical, communications, electronic safety and security, as well as other related systems.
- B. CxA: Commissioning Agent.
- C. Commissioning Plan: a document that is an overall plan that outlines the commissioning process, commissioning team responsibilities, schedule for commissioning activities, and commissioning documents.
- D. Commissioning Issue: a condition in the installation or function of a component, piece of equipment or system that affects the system operations, maintenance, and/or repair.
- E. Commissioning Observation: a condition in the installation or function of a component, piece of equipment or system that may not be in compliance with the Contract Documents, or may not be in compliance with the manufacturer's installation instruction, or may not be in compliance with generally accepted industry standards.
- F. Systems Functional Performance Test: a test, or tests, of the dynamic function and operation of equipment and systems using manual (direct observation) or monitoring methods. Systems Functional Performance Testing is the dynamic testing of systems (rather than just components) under full operation (e.g., the chiller pump is tested interactively with the chiller functions to see if the pump ramps up and down to maintain the differential pressure setpoint). Systems are tested under various modes, such as during low cooling or heating loads, high loads, component failures, unoccupied, varying outside air temperatures, fire alarm, power failure, etc. The systems are run through all the control system's sequences of operation and components are verified to be responding as the sequences state. Traditional air or water test and

balancing (TAB) is not Systems Functional Performance Testing, in the commissioning sense of the word. TAB's primary work is setting up the system flows and pressures as specified, while System Functional Performance Testing is verifying that the system has already been set up properly and is functioning in accordance with the Construction Documents. The Commissioning Agent develops the Systems Functional Performance Test Procedures in a sequential written form, coordinates, witnesses, and documents the actual testing. Systems Functional Performance Testing is performed by the Contractor. Systems Functional Performance Tests are performed after startups, control systems are complete and operational, TAB functions and Pre-Functional Checklists are complete.

- G. System: A system is defined as the entire set of components, equipment, and subsystems which must be coordinated to work together during normal operation to produce results for which the system is designed. For example, air conditioning supply air is only one component of an entire system which provides comfort conditions for a building. Other related components are return air, exhaust air, steam supply, chilled water supply, refrigerant supply, hot water supply, controls and electrical service, etc. Another example of a system which involves several components of different disciplines is a boiler installation. Efficient and acceptable boiler operation depends upon the coordination and proper operation of the fuel supply, combustion air, controls, steam, feedwater supply, condensate return and other related components.
- H. Pre-Functional Checklist: a list of items provided by the Commissioning Agent to the Contractor that require inspection and elementary component tests conducted to verify proper installation of equipment. Pre-Functional Checklists are primarily static inspections and procedures to prepare the equipment or system for initial operation (e.g., belt tension, oil levels OK, labels affixed, gages in place, sensors calibrated, etc.). However, some Pre-Functional Checklist items entail simple testing of the function of a component, a piece of equipment or system (such as measuring the voltage imbalance on a three-phase pump motor of a chiller system). The term "Pre-Functional" refers to before Systems Functional Performance Testing. Pre-Functional Checklists augment and are combined with the manufacturer's startup checklist and the Contractor's Quality Control checklists.

- I. Seasonal Functional Performance Testing: a test or tests that are deferred until the system will experience conditions closer to their design conditions.
- J. VA: Includes the Contracting Officer, Resident Engineer, or other authorized representative of the Department of Veterans Affairs.
- K. TAB: Testing, Adjusting, and Balancing.

#### **1.6 SYSTEMS TO BE COMMISSIONED**

- A. Commissioning of a system or systems specified for this project is part of the construction process. Documentation and testing of these systems, as well as training of the VA's Operation and Maintenance personnel, is required in cooperation with the VA and the Commissioning Agent.
- B. The following systems will be commissioned as part of this project:
  - 1. Facility exterior closure (Division 7 and Division 8)
    - a. Roofs (PVC, fluid-applied, flashing & sheet metal, metal roofing, roof specialties, and roof accessories)
    - b. Curtain Wall Systems (Mullions, glazing, and sealing)
    - c. Exterior Doors
    - d. Exterior Windows (Aluminum)
    - e. Louvers and Vents
    - f. Sealants (Caulking, mechanical seals, and wind and vapor barriers)
  - 2. Fire Suppression (Division 21)
    - a. Fire Protection System (Fire pump, jockey pump, fire pump automatic transfer switch/controller, Wet-pipe fire suppression, Dry-pipe fire suppression, Pre-action fire suppression, dry system air compressors and motors, and clean agent fire suppression).
  - 3. Plumbing (Division 22)
    - a. Domestic Hot Water systems (Domestic water heaters, steam-to-hot water converters, hot water circulating pumps and motors, controls, combustion burners/fans/motors).
    - b. Medical Gas systems (Medical compressed air and air compressor, laboratory vacuum and vacuum pumps, nitrous oxide and oxygen, Medical Gas Alarm System).
    - c. Domestic Water Booster Pumps (Controls, piping, compression tanks, pumps, motors, and Variable Speed Drives).

- d. Sewage Ejection Pumps (Sump level controls, pump alternator, alarms and alarm panel, pumps and motors).
  - e. Storm Sump Pumps (Sump level controls, pump alternator, alarms and alarm panel, pumps and motors).
  - f. Domestic Water Filtration and Softener Systems (Tanks and casings, gages and instruments, controls, pumps and motors - if applicable, packaged piping, alarms).
  - g. Chemical Waste System & Equipment (Waste storage tanks or sumps, controls and alarms, pumps and motors - if applicable).
  - h. Process Water Systems (Controls, piping, tanks and casings, gages and instruments, pumps, motors, and Variable Speed Drives - if applicable for reverse osmosis (RO) and deionized water (DI) systems).
  - i. Emergency Plumbing Fixtures (Showers, eye wash stations, water tempering valves, instruments and gages).
4. HVAC (Division 23)
- a. Air Handling Systems (Fans, motors, Variable Speed Drives, cooling coils and control valves, heating coils and control valves, filters, dampers, safeties such as smoke detectors or freezestats and damper end switches, controls, gages, and vibration isolation).
  - b. Dehumidification Systems (Energy recovery devices - such as enthalpy wheels, fans, motors, Variable Speed Drives, cooling coils and control valves, heating coils and control valves, filters, dampers, safeties, controls, gages, and vibration isolation).
  - c. Heating Hot Water Systems (Boilers, controls, instrumentation and gages, flues, heating water pumps and motors, Variable Speed Drives, mixing valves).
  - d. Condensate Return Systems (Condensate receivers and transfer pumps, motors, controls, pump alternator, alarms and instrumentation, deaerators, boiler feed pumps and motors, safeties).
  - e. Chilled Water Systems (Chilled water pumps and motors, Variable Speed Drives, chiller motor/compressor, controls, instrumentation and safeties, isolation valves, blending valves, side stream water cleaners/scrubbers/filters).



- f. Condenser Water Systems for Chillers (Condenser water pumps and motors, Variable Speed Drives, cooling tower fans, cooling tower sump level controls, open-circuit water treatment system, water treatment injection pumps and motors, water treatment controls, cooling tower basin heaters and controls, side stream water cleaners/scrubbers/filters, tower bypass valves).
- g. Exhaust Fans (Fan, motor, Variable Speed Drives, controls and safeties).
- h. Steam System (Boilers, controls, gages and instrumentation, safety relief valves, combustion burners/fans/motors, fuel delivery pumps and motors, flues).
- i. Direct Digital Control System (BACnet or similar Local Area Network (LAN), Operator Work Station hardware and software, building controller hardware and software, terminal unit controller hardware and software, all sequences of operation, system accuracy and response time).
- j. Laboratory Exhaust Systems (Fume hoods, pressure controls, system alarms, fans, motors, and Variable Speed Drives).
- k. Laboratory Ventilation Systems (Supply air terminal units and controls, pressure controls and alarms, fans, motors, and Variable Speed Drives).
- l. OR Air Handling Systems (Fans, motors, Variable Speed Drives, Energy recovery devices - such as heat pipes, cooling coils and control valves, heating coils and control valves, filters, HEPA filter performance, dampers, safeties such as smoke detectors or freezestats and damper end switches, controls, gages, and vibration isolation).
- m. Radiology/Imaging Cooling Systems (Fans, motors, Variable Speed Drives, cooling coils and control valves, filters, dampers, safeties, controls, gages, and vibration isolation).
- n. Computer Room Air Conditioning Systems (CRAC units - including fans, motors, Variable Speed Drives, cooling coils and control valves, heating coils and control valves, humidifiers, compressors and liquid-cooled condensers, filters, safeties, controls, gages, vibration isolation, condensate pumps, water/leak detection system and alarms, and shunt trip shut down).

- o. Room Pressurization Equipment (Pressure sensors, terminal units/dampers, and controls and alarms).
  - p. HVAC Water Treatment Systems (Closed circuits - including shot feeders and final water analysis, open circuits - including water analysis, chemical/biocide tanks, injection piping, chemical/biocide pumps and motors, controls, water meter, and automatic blowdown).
  - q. Commercial Kitchen Hoods & Associated Fire Suppression Systems (Fans, motors, Variable Speed Drives, automatic shut down on fire suppression discharge, and gas valve operation).
  - r. Fuel Delivery and Storage Systems for Boilers and Standby Generators (Fuel level monitoring/controls/alarms, transfer pumps and motors, leak detection monitoring/alarms, and fill systems)
5. Electrical (Division 26)
- a. Utility Service Entrance Switchgear (Fuses and circuit breaker settings, metering, mimic diagram, gages, and controls).
  - b. Standby Generator Systems (Automatic transfer switches, fuel delivery pumps and motors, battery charging and instrumentation, muffler and exhaust system, and vibration isolation).
  - c. Generator Paralleling Switchboards (Automatic transfer switches, instrumentation, metering and gages, and controls).
  - d. Generator Power Distribution Systems (Fuses and circuit breaker settings, metering, gages, and controls).
  - e. Utility Power Unit Substations (Transformers and tap settings, fuses and circuit breaker settings, metering, gages, and controls).
  - f. Generator Power Unit Substations (Transformers and tap settings, fuses and circuit breaker settings, metering, gages, and controls).
  - g. Automatic Transfer Switches (Test with associated generator).
  - h. Normal Power Distribution Systems (Grounding tests, coordination study review, major circuit breaker settings, meters and gages, and controls).
  - i. Life Safety Power Distribution Systems (Automatic transfer on loss of normal power, grounding tests, coordination study review, major circuit breaker settings, meters and gages, and controls).

- j. Critical Power Distribution Systems (Automatic transfer on loss of normal power, grounding tests, coordination study review, major circuit breaker settings, meters and gages, and controls).
  - k. Essential Equipment Power Distribution Systems (Automatic transfer on loss of normal power, grounding tests, coordination study review, major circuit breaker settings, meters and gages, and controls).
  - l. Lighting Controls (Control system hardware and software, scene settings, zone settings, occupancy sensor interface, and unoccupied cycle control).
  - m. Uninterruptible Power Supply Systems and UPS Power Distribution Systems (Battery chargers, static and dynamic power generators - i.e. inverters, MG sets, metering and controls, system power displays, and distribution panel circuit breakers).
6. Communications (Division 27)
- a. Facility Telecommunications and Data Distribution Systems.
  - b. Nurse Call / Code Blue Systems (Local stations, system hardware and software, reset functions, response time per activation, and notification signals).
  - c. Public Address and Mass Notification Systems (Amplifiers and head-end hardware, speaker volume, and background noise - i.e. hiss or similar interference).
  - d. Healthcare Intercommunications and Program Systems (Local stations, system hardware and software, and notification signals).
7. Electronic Safety and Security (Division 28)
- a. Fire Detection and Alarm (Master panel and software, addressable units - i.e. pull stations, flow detectors, heat detectors, etc., controls and alarm functions, horns/bells/door releases and other output devices, and fire command center functions - stairwell communications, stairwell pressurization fan start, mechanical systems shutdowns).
8. Site Utility Systems (Division 31)
- a. Sanitary Sewage Lift Stations (Lift station sump or tank level controls, pump alternator, alarms and alarm panel, pumps and motors).

- b. Steam Condensate Pump Stations (Condensate receivers and transfer pumps, motors, controls, pump alternator, alarms and instrumentation, and safeties).
- c. Storm Drainage Pump Systems (Sump level controls, pump alternator, alarms and alarm panel, pumps and motors).

#### **1.7 COMMISSIONING TEAM**

##### **A. Members Appointed by Contractor:**

- 1. Commissioning Agent: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. The General Contractor will engage the CxA. It is the VA's intent for the scope of the contact to include full commissioning services including engagement of the commissioning agent by the Contractor.
- 2. Contractor: The designated person, company, or entity that plans, schedules and coordinates the commissioning activities for the construction team.
- 3. Contractor's Commissioning Representative(s): Individual(s), each having authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated actions. The commissioning team shall consist of, but not be limited to, representatives of Contractor, including Project Superintendent and subcontractors, installers, suppliers, and specialists deemed appropriate by the Department of Veterans Affairs (VA) and Commissioning Agent.

##### **B. Members Appointed by VA:**

- 1. Representatives of the facility user and operation and maintenance personnel.
- 2. Architect and engineering design professionals.

#### **1.8 VA'S COMMISSIONING RESPONSIBILITIES**

##### **A. Assign operation and maintenance personnel and schedule them to participate in commissioning team activities including, but not limited to, the following:**

- 1. Coordination meetings.
- 2. Training in operation and maintenance of systems, subsystems, and equipment.
- 3. Testing meetings.
- 4. Witness and assist in Systems Functional Performance Testing.
- 5. Demonstration of operation of systems, subsystems, and equipment.

- B. Provide the Construction Documents, prepared by Architect and approved by VA, to the Commissioning Agent and for use in managing the commissioning process, developing the commissioning plan, systems manuals, and reviewing the operation and maintenance training plan.

#### **1.9 CONTRACTOR'S COMMISSIONING RESPONSIBILITIES**

- A. Appoint an individual, company or firm to act as the Commissioning Agent.
- B. The Contractor shall assign a Commissioning Manager to manage commissioning activities of the Contractor, and subcontractors.
- C. The Contractor shall ensure that the commissioning responsibilities outlined in these specifications are included in all subcontracts and that subcontractors comply with the requirements of these specifications.
- D. The Contractor shall ensure that each installing subcontractor shall assign representatives with expertise and authority to act on behalf of the subcontractor and schedule them to participate in and perform commissioning team activities including, but not limited to, the following:
  - 1. Participate in commissioning coordination meetings.
  - 2. Conduct operation and maintenance training sessions in accordance with approved training plans.
  - 3. Verify that Work is complete and systems are operational according to the Contract Documents, including calibration of instrumentation and controls.
  - 4. Evaluate commissioning issues and commissioning observations identified in the Commissioning Issues Log, field reports, test reports or other commissioning documents. In collaboration with entity responsible for system and equipment installation, recommend corrective action.
  - 5. Review and comment on commissioning documentation.
  - 6. Participate in meetings to coordinate Systems Functional Performance Testing.
  - 7. Provide schedule for operation and maintenance data submittals, equipment startup, and testing to Commissioning Agent for incorporation into the commissioning plan.
  - 8. Provide information to the Commissioning Agent for developing commissioning plan.

9. Participate in training sessions for VA's operation and maintenance personnel.
10. Provide technicians who are familiar with the construction and operation of installed systems and who shall develop specific test procedures to conduct Systems Functional Performance Testing of installed systems.

#### **1.10 COMMISSIONING AGENT'S RESPONSIBILITIES**

- A. Organize and lead the commissioning team.
- B. Prepare the commissioning plan. See Paragraph 1.11-B of this specification Section for further information.
- C. Review and comment on selected submittals from the Contractor for general conformance with the Construction Documents. Review and comment on the ability to test and operate the system and/or equipment, including providing gages, controls and other components required to operate, maintain, and test the system. Review and comment on performance expectations of systems and equipment and interfaces between systems relating to the Construction Documents.
- D. At the beginning of the construction phase, conduct an initial construction phase coordination meeting for the purpose of reviewing the commissioning activities and establishing tentative schedules for operation and maintenance submittals; operation and maintenance training sessions; TAB Work; Pre-Functional Checklists, Systems Functional Performance Testing; and project completion.
- E. Convene commissioning team meetings for the purpose of coordination, communication, and conflict resolution; discuss status of the commissioning processes. Responsibilities include arranging for facilities, preparing agenda and attendance lists, and notifying participants. The Commissioning Agent shall prepare and distribute minutes to commissioning team members and attendees within five workdays of the commissioning meeting.
- F. Observe construction and report progress, observations and issues. Observe systems and equipment installation for adequate accessibility for maintenance and component replacement or repair, and for general conformance with the Construction Documents.
- G. Prepare Project specific Pre-Functional Checklists and Systems Functional Performance Test procedures.
- H. Coordinate Systems Functional Performance Testing schedule with the Contractor.

- I. Witness selected systems startups.
- J. Verify selected Pre-Functional Checklists completed and submitted by the Contractor.
- K. Witness and document Systems Functional Performance Testing.
- L. Compile test data, inspection reports, and certificates and include them in the systems manual and commissioning report.
- M. Review and comment on operation and maintenance (O&M) documentation and systems manual outline for compliance with the Contract Documents. Operation and maintenance documentation requirements are specified in Paragraph 1.25, Section 01 00 00 GENERAL REQUIREMENTS.
- N. Review operation and maintenance training program developed by the Contractor. Verify training plans provide qualified instructors to conduct operation and maintenance training.
- O. Prepare commissioning Field Observation Reports.
- P. Prepare the Final Commissioning Report.
- Q. Return to the site at 10 months into the 12 month warranty period and review with facility staff the current building operation and the condition of outstanding issues related to the original and seasonal Systems Functional Performance Testing. Also interview facility staff and identify problems or concerns they have operating the building as originally intended. Make suggestions for improvements and for recording these changes in the O&M manuals. Identify areas that may come under warranty or under the original construction contract. Assist facility staff in developing reports, documents and requests for services to remedy outstanding problems.
- R. Assemble the final commissioning documentation, including the Final Commissioning Report and Addendum to the Final Commissioning Report.

#### **1.11 COMMISSIONING DOCUMENTATION**

- A. Commissioning Agent's Certification(s): Commissioning Agent shall submit evidence of valid and current certification(s), as required in Section 1.1(G), to the Contracting Officer.
- B. Commissioning Plan: A document, prepared by Commissioning Agent, that outlines the schedule, allocation of resources, and documentation requirements of the commissioning process, and shall include, but is not limited, to the following:
  - 1. Plan for delivery and review of submittals, systems manuals, and other documents and reports. Identification of the relationship of these documents to other functions and a detailed description of

submittals that are required to support the commissioning processes. Submittal dates shall include the latest date approved submittals must be received without adversely affecting commissioning plan.

2. Description of the organization, layout, and content of commissioning documentation (including systems manual) and a detailed description of documents to be provided along with identification of responsible parties.
  3. Identification of systems and equipment to be commissioned.
  4. Schedule of Commissioning Coordination meetings.
  5. Identification of items that must be completed before the next operation can proceed.
  6. Description of responsibilities of commissioning team members.
  7. Description of observations to be made.
  8. Description of requirements for operation and maintenance training.
  9. Schedule for commissioning activities with dates coordinated with overall construction schedule.
  10. Process and schedule for documenting changes on a continuous basis to appear in Project Record Documents.
  11. Process and schedule for completing prestart and startup checklists for systems, subsystems, and equipment to be verified and tested.
  12. Preliminary Systems Functional Performance Test procedures.
- C. Systems Functional Performance Test Procedures: The Commissioning Agent will develop Systems Functional Performance Test Procedures for each system to be commissioned, including subsystems, or equipment and interfaces or interlocks with other systems. Systems Functional Performance Test Procedures will include a separate entry, with space for comments, for each item to be tested. Preliminary Systems Functional Performance Test Procedures will be provided to the VA, Architect/Engineer, and Contractor for review and comment. The Systems Performance Test Procedure will include test procedures for each mode of operation and provide space to indicate whether the mode under test responded as required. Each System Functional Performance Test procedure, regardless of system, subsystem, or equipment being tested, shall include, but not be limited to, the following:
1. Name and identification code of tested system.
  2. Test number.
  3. Time and date of test.



4. Indication of whether the record is for a first test or retest following correction of a problem or issue.
  5. Dated signatures of the person performing test and of the witness, if applicable.
  6. Individuals present for test.
  7. Observations and Issues.
  8. Issue number, if any, generated as the result of test.
- D. Pre-Functional Checklists: The Commissioning Agent will prepare *Pre-Functional Checklists*. *Pre-Functional Checklists shall be completed* and signed by the Contractor, verifying that systems, subsystems, equipment, and associated controls are ready for testing. The Commissioning Agent will spot check *Pre-Functional Checklists* to verify accuracy and readiness for testing. Inaccurate or incomplete *Pre-Functional Checklists* shall be returned to the Contractor for correction and resubmission.
- E. Test and Inspection Reports: The Commissioning Agent will record test data, observations, and measurements on Systems Functional Performance Test Procedure. The report will also include recommendation for system acceptance or non-acceptance. Photographs, forms, and other means appropriate for the application shall be included with data. Commissioning Agent Will compile test and inspection reports and test and inspection certificates and include them in systems manual and commissioning report.
- F. Corrective Action Documents: The Commissioning Agent will document corrective action taken for systems and equipment that fail tests. The documentation will include any required modifications to systems and equipment and/or revisions to test procedures, if any. The Commissioning Agent will witness and document any retesting of systems and/or equipment requiring corrective action and document retest results.
- G. Commissioning Issues Log: The Commissioning Agent will prepare and maintain Commissioning Issues Log that describes Commissioning Issues and Commissioning Observations that are identified during the Commissioning process. These observations and issues include, but are not limited to, those that are at variance with the Contract Documents. The Commissioning Issues Log will identify and track issues as they are encountered, the party responsible for resolution, progress toward resolution, and document how the issue was resolved. The Master

Commissioning Issues Log will also track the status of unresolved issues.

1. Creating an Commissioning Issues Log Entry:

- a. Identify the issue with unique numeric or alphanumeric identifier by which the issue may be tracked.
- b. Assign a descriptive title for the issue.
- c. Identify date and time of the issue.
- d. Identify test number of test being performed at the time of the observation, if applicable, for cross reference.
- e. Identify system, subsystem, and equipment to which the issue applies.
- f. Identify location of system, subsystem, and equipment.
- g. Include information that may be helpful in diagnosing or evaluating the issue.
- h. Note recommended corrective action.
- i. Identify commissioning team member responsible for corrective action.
- j. Identify expected date of correction.
- k. Identify person that identified the issue.

2. Documenting Issue Resolution:

- a. Log date correction is completed or the issue is resolved.
- b. Describe corrective action or resolution taken. Include description of diagnostic steps taken to determine root cause of the issue, if any.
- c. Identify changes to the Contract Documents that may require action.
- d. State that correction was completed and system, subsystem, and equipment are ready for retest, if applicable.
- e. Identify person(s) who corrected or resolved the issue.
- f. Identify person(s) verifying the issue resolution.

H. Final Commissioning Report: The Commissioning Agent will document results of the commissioning process, including unresolved issues, and performance of systems, subsystems, and equipment. The Commissioning Report will indicate whether systems, subsystems, and equipment have been properly installed and are performing according to the Contract Documents. This report will be used by the Department of Veterans Affairs when determining that systems will be accepted. This report will be used to evaluate systems, subsystems, and equipment and will

serve as a future reference document during VA occupancy and operation. It shall describe components and performance that exceed requirements of the Contract Documents and those that do not meet requirements of the Contract Documents. The commissioning report will include, but is not limited to, the following:

1. Lists and explanations of substitutions; compromises; variances with the Contract Documents; record of conditions; and, if appropriate, recommendations for resolution. Design Narrative documentation maintained by the Commissioning Agent.
2. Commissioning plan.
3. Pre-Functional Checklists completed by the Contractor, with annotation of the Commissioning Agent review and spot check.
4. Systems Functional Performance Test Procedures, with annotation of test results and test completion.
5. Commissioning Issues Log.
6. Listing of deferred and off season test(s) not performed, including the schedule for their completion.

I. Addendum to Final Commissioning Report: The Commissioning Agent will prepare an Addendum to the Final Commissioning Report near the end of the Warranty Period. The Addendum will indicate whether systems, subsystems, and equipment are complete and continue to perform according to the Contract Documents. The Addendum to the Final Commissioning Report shall include, but is not limited to, the following:

1. Documentation of deferred and off season test(s) results.
2. Completed Systems Functional Performance Test Procedures for off season test(s).
3. Documentation that unresolved system performance issues have been resolved.
4. Updated Commissioning Issues Log, including status of unresolved issues.
5. Identification of potential Warranty Claims to be corrected by the Contractor.

J. Systems Manual: The Commissioning Agent will gather required information and compile the Systems Manual. The Systems Manual will include, but is not limited to, the following:

1. Design Narrative, including system narratives, schematics, single-line diagrams, flow diagrams, equipment schedules, and changes made throughout the Project.
2. Reference to Final Commissioning Plan.
3. Reference to Final Commissioning Report.
4. Approved Operation and Maintenance Data as submitted by the Contractor.

#### **1.12 SUBMITTALS**

- A. Preliminary Commissioning Plan Submittal: The Commissioning Agent has prepared a Preliminary Commissioning Plan based on the final Construction Documents. The Preliminary Commissioning Plan is included as an Appendix to this specification section. The Preliminary Commissioning Plan is provided for information only. It contains preliminary information about the following commissioning activities:
1. The Commissioning Team: A list of commissioning team members by organization.
  2. Systems to be commissioned. A detailed list of systems to be commissioned for the project. This list also provides preliminary information on systems/equipment submittals to be reviewed by the Commissioning Agent; preliminary information on Pre-Functional Checklists that are to be completed; preliminary information on Systems Performance Testing, including information on testing sample size (where authorized by the VA).
  3. Commissioning Team Roles and Responsibilities: Preliminary roles and responsibilities for each Commissioning Team member.
  4. Commissioning Documents: A preliminary list of commissioning-related documents, include identification of the parties responsible for preparation, review, approval, and action on each document.
  5. Commissioning Activities Schedule: Identification of Commissioning Activities, including Systems Functional Testing, the expected duration and predecessors for the activity.
  6. Pre-Functional Checklists: Preliminary Pre-Functional Checklists for equipment, components, subsystems, and systems to be commissioned. These Preliminary Pre-Functional Checklists provide guidance on the level of detailed information the Contractor shall include on the final submission.
  7. Systems Functional Performance Test Procedures: Preliminary step-by-step System Functional Performance Test Procedures to be used

during Systems Functional Performance Testing. These Preliminary Systems Functional Performance procedures provide information on the level of testing rigor, and the level of Contractor support required during performance of system's testing.

- B. Final Commissioning Plan Submittal: Based on the Final Construction Documents and the Contractor's project team, the Commissioning Agent will prepare the Final Commissioning Plan as described in this section. The Commissioning Agent will submit three hard copies and three sets of electronic files of Final Commissioning Plan. The Contractor shall review the Commissioning Plan and provide any comments to the VA. The Commissioning Agent will incorporate review comments into the Final Commissioning Plan as directed by the VA.
- C. Systems Functional Performance Test Procedure: The Commissioning Agent will submit preliminary Systems Functional Performance Test Procedures to the Contractor, and the VA for review and comment. The Contractor shall return review comments to the VA and the Commissioning Agent. The VA will also return review comments to the Commissioning Agent. The Commissioning Agent will incorporate review comments into the Final Systems Functional Test Procedures to be used in Systems Functional Performance Testing.
- D. Pre-Functional Checklists: The Commissioning Agent will submit Pre-Functional Checklists to be completed by the Contractor.
- E. Test and Inspection Reports: The Commissioning Agent will submit test and inspection reports to the VA with copies to the Contractor and the Architect/Engineer.
- F. Corrective Action Documents: The Commissioning Agent will submit corrective action documents to the VA Resident Engineer with copies to the Contractor and Architect.
- G. Preliminary Commissioning Report Submittal: The Commissioning Agent will submit three electronic copies of the preliminary commissioning report. One electronic copy, with review comments, will be returned to the Commissioning Agent for preparation of the final submittal.
- H. Final Commissioning Report Submittal: The Commissioning Agent will submit four sets of electronically formatted information of the final commissioning report to the VA. The final submittal will incorporate comments as directed by the VA.

I. Data for Commissioning:

1. The Commissioning Agent will request in writing from the Contractor specific information needed about each piece of commissioned equipment or system to fulfill requirements of the Commissioning Plan.
2. The Commissioning Agent may request further documentation as is necessary for the commissioning process or to support other VA data collection requirements, including Construction Operations Building Information Exchange (COBIE), Building Information Modeling (BIM), etc.

**1.13 COMMISSIONING PROCESS**

- A. The Commissioning Agent will be responsible for the overall management of the commissioning process as well as coordinating scheduling of commissioning tasks with the VA and the Contractor. As directed by the VA, the Contractor shall incorporate Commissioning tasks, including, but not limited to, Systems Functional Performance Testing (including predecessors) with the Master Construction Schedule.
- B. Within 30 days of contract award, the Contractor shall designate a specific individual as the Commissioning Manager (CM) to manage and lead the commissioning effort on behalf of the Contractor. The Commissioning Manager shall be the single point of contact and communications for all commissioning related services by the Contractor.
- C. Within 30 days of contract award, the Contractor shall ensure that each subcontractor designates specific individuals as Commissioning Representatives (CR) to be responsible for commissioning related tasks. The Contractor shall ensure the designated Commissioning Representatives participate in the commissioning process as team members providing commissioning testing services, equipment operation, adjustments, and corrections if necessary. The Contractor shall ensure that all Commissioning Representatives shall have sufficient authority to direct their respective staff to provide the services required, and to speak on behalf of their organizations in all commissioning related contractual matters.

**1.14 QUALITY ASSURANCE**

- A. Instructor Qualifications: Factory authorized service representatives shall be experienced in training, operation, and maintenance procedures for installed systems, subsystems, and equipment.

- B. Test Equipment Calibration: The Contractor shall comply with test equipment manufacturer's calibration procedures and intervals. Recalibrate test instruments immediately whenever instruments have been repaired following damage or dropping. Affix calibration tags to test instruments. Instruments shall have been calibrated within six months prior to use.

#### **1.15 COORDINATION**

- A. Management: The Commissioning Agent will coordinate the commissioning activities with the VA and Contractor. The Commissioning Agent will submit commissioning documents and information to the VA. All commissioning team members shall work together to fulfill their contracted responsibilities and meet the objectives of the contract documents.
- B. Scheduling: The Contractor will work with the Commissioning Agent and the VA to incorporate the commissioning activities into the construction schedule. The Commissioning Agent will provide sufficient information on commissioning activities to allow the Contractor and the VA to schedule commissioning activities. All parties shall address scheduling issues and make necessary notifications in a timely manner in order to expedite the project and the commissioning process. The Contractor shall update the Master Construction as directed by the VA.
- C. Initial Schedule of Commissioning Events: The Commissioning Agent will provide the initial schedule of primary commissioning events in the Commissioning Plan and at the commissioning coordination meetings. The Commissioning Plan will provide a format for this schedule. As construction progresses, more detailed schedules will be developed by the Contractor with information from the Commissioning Agent.
- D. Commissioning Coordinating Meetings: The Commissioning Agent will conduct periodic Commissioning Coordination Meetings of the commissioning team to review status of commissioning activities, to discuss scheduling conflicts, and to discuss upcoming commissioning process activities.
- E. Pretesting Meetings: The Commissioning Agent will conduct pretest meetings of the commissioning team to review startup reports, Pre-Functional Checklist results, Systems Functional Performance Testing procedures, testing personnel and instrumentation requirements.
- F. Systems Functional Performance Testing Coordination: The Contractor shall coordinate testing activities to accommodate required quality

assurance and control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting. The Contractor shall coordinate the schedule times for tests, inspections, obtaining samples, and similar activities.

## **PART 2 - PRODUCTS**

### **2.1 TEST EQUIPMENT**

- A. The Contractor shall provide all standard and specialized testing equipment required to perform Systems Functional Performance Testing. Test equipment required for Systems Functional Performance Testing will be identified in the detailed System Functional Performance Test Procedure prepared by the Commissioning Agent.
- B. Data logging equipment and software required to test equipment shall be provided by the Contractor.
- C. All testing equipment shall be of sufficient quality and accuracy to test and/or measure system performance with the tolerances specified in the Specifications. If not otherwise noted, the following minimum requirements apply: Temperature sensors and digital thermometers shall have a certified calibration within the past year to an accuracy of 0.5 °C (1.0 °F) and a resolution of + or - 0.1 °C (0.2 °F). Pressure sensors shall have an accuracy of + or - 2.0% of the value range being measured (not full range of meter) and have been calibrated within the last year. All equipment shall be calibrated according to the manufacturer's recommended intervals and when dropped or damaged. Calibration tags shall be affixed or certificates readily available.

## **PART 3 - EXECUTION**

### **3.1 STARTUP, INITIAL CHECKOUT, AND PRE-FUNCTIONAL CHECKLISTS**

- A. The following procedures shall apply to all equipment and systems to be commissioned, according to Part 1, Systems to Be Commissioned.
  - 1. Pre-Functional Checklists are important to ensure that the equipment and systems are hooked up and operational. These ensure that Systems Functional Performance Testing may proceed without unnecessary delays. Each system to be commissioned shall have a full Pre-Functional Checklist completed by the Contractor prior to Systems Functional Performance Testing. No sampling strategies are used.
    - a. The Pre-Functional Checklist will identify the trades responsible for completing the checklist. The Contractor shall ensure the appropriate trades complete the checklists.



- b. The Commissioning Agent will review completed Pre-Functional Checklists and field-verify the accuracy of the completed checklist using sampling techniques.
- 2. Startup and Initial Checkout Plan: The Contractor shall develop detailed startup plans for all equipment. The primary role of the Contractor in this process is to ensure that there is written documentation that each of the manufacturer recommended procedures have been completed. Parties responsible for startup shall be identified in the Startup Plan and in the checklist forms.
  - a. The Contractor shall develop the full startup plan by combining (or adding to) the checklists with the manufacturer's detailed startup and checkout procedures from the O&M manual data and the field checkout sheets normally used by the Contractor. The plan shall include checklists and procedures with specific boxes or lines for recording and documenting the checking and inspections of each procedure and a summary statement with a signature block at the end of the plan.
  - b. The full startup plan shall at a minimum consist of the following items:
    - 1) The Pre-Functional Checklists.
    - 2) The manufacturer's standard written startup procedures copied from the installation manuals with check boxes by each procedure and a signature block added by hand at the end.
    - 3) The manufacturer's normally used field checkout sheets.
      - a) The Commissioning Agent will submit the full startup plan to the VA and Contractor for review. Final approval will be by the VA.
      - b) The Contractor shall review and evaluate the procedures and the format for documenting them, noting any procedures that need to be revised or added.
- 3. Sensor and Actuator Calibration
  - a. All field installed temperature, relative humidity, CO<sub>2</sub> and pressure sensors and gages, and all actuators (dampers and valves) on all equipment shall be calibrated using the methods described in Division 21, Division 22, Division 23, Division 26, Division 27, and Division 28 specifications.
  - b. All procedures used shall be fully documented on the Pre-Functional Checklists or other suitable forms, clearly

referencing the procedures followed and written documentation of initial, intermediate and final results.

4. Execution of Equipment Startup

- a. Four weeks prior to equipment startup, the Contractor shall schedule startup and checkout with the VA and Commissioning Agent. The performance of the startup and checkout shall be directed and executed by the Contractor.
- b. The Commissioning Agent will observe the startup procedures for selected pieces of primary equipment.
- c. The Contractor shall execute startup and provide the VA and Commissioning Agent with a signed and dated copy of the completed startup checklists, and contractor tests.
- d. Only individuals that have direct knowledge and witnessed that a line item task on the Startup Checklist was actually performed shall initial or check that item off. It is not acceptable for witnessing supervisors to fill out these forms.

**3.2 DEFICIENCIES, NONCONFORMANCE, AND APPROVAL IN CHECKLISTS AND STARTUP**

- A. The Contractor shall clearly list any outstanding items of the initial startup and Pre-Functional Checklist procedures that were not completed successfully, at the bottom of the procedures form or on an attached sheet. The procedures form and any outstanding deficiencies shall be provided to the VA and the Commissioning Agent within two days of completion.
- B. The Commissioning Agent will review the report and submit comments to the VA. The Commissioning Agent will work with the Contractor to correct and verify deficiencies or uncompleted items. The Commissioning Agent will involve the VA and others as necessary. The Contractor shall correct all areas that are noncompliant or incomplete in the checklists in a timely manner, and shall notify the VA and Commissioning Agent as soon as outstanding items have been corrected. The Contractor shall submit an updated startup report and a Statement of Correction on the original noncompliance report. When satisfactorily completed, the Commissioning Agent will recommend approval of the checklists and startup of each system to the VA.
- C. The Contractor shall be responsible for resolution of deficiencies as directed the VA.

### **3.3 PHASED COMMISSIONING**

- A. The project may require startup and initial checkout to be executed in phases. This phasing shall be planned and scheduled in a coordination meeting of the VA, Commissioning Agent, and the Contractor. Results will be added to the master construction schedule and the commissioning schedule.

### **3.4 TRENDING AND ALARMS**

- A. Trending is a method of testing as a standalone method or to augment manual testing. The Contractor shall trend any and all points of the system or systems at intervals specified below.
- B. Alarms are a means to notify the system operator that abnormal conditions are present in the system. Alarms shall be structured into three tiers - Critical, Priority, and Maintenance.
  - 1. Critical alarms are intended to be alarms that require the immediate attention of and action by the Operator. These alarms shall be displayed on the Operator Workstation in a popup style window that is graphically linked to the associated unit's graphical display. The popup style window shall be displayed on top of any active window within the screen, including non DDC system software.
  - 2. Priority level alarms are to be printed to a printer which is connected to the Operator's Work Station located within the engineer's office. Additionally Priority level alarms shall be able to be monitored and viewed through an active alarm application. Priority level alarms are alarms which shall require reaction from the operator or maintenance personnel within a normal work shift, and not immediate action.
  - 3. Maintenance alarms are intended to be minor issues which would require examination by maintenance personnel within the following shift. These alarms shall be generated in a scheduled report automatically by the DDC system at the start of each shift. The generated maintenance report will be printed to a printer located within the engineer's office.
- C. The Contractor shall provide a wireless internet network in the building for use during controls programming, checkout, and commissioning. This network will allow project team members to more effectively program, view, manipulate and test control devices while being in the same room as the controlled device.

D. The Contractor shall provide graphical trending through the DDC control system of systems being commissioned. Trending requirements are indicated below and included with the Systems Functional Performance Test Procedures. Trending shall occur before, during and after Systems Functional Performance Testing. The Contractor shall be responsible for producing graphical representations of the trended DDC points that show each system operating properly during steady state conditions as well as during the System Functional Testing. These graphical reports shall be submitted to the Resident Engineer and Commissioning Agent for review and analysis before, during dynamic operation, and after Systems Functional Performance Testing. The Contractor shall provide, but not limited to, the following trend requirements and trend submissions:

1. Pre-testing, Testing, and Post-testing - Trend reports of trend logs and graphical trend plots are required as defined by the Commissioning Agent. The trend log points, sampling rate, graphical plot configuration, and duration will be dictated by the Commissioning Agent. At any time during the Commissioning Process the Commissioning Agent may recommend changes to aspects of trending as deemed necessary for proper system analysis. The Contractor shall implement any changes as directed by the Resident Engineer. Any pre-test trend analysis comments generated by the Commissioning Team should be addressed and resolved by the Contractor, as directed by the Resident Engineer, prior to the execution of Systems Functional Performance Testing.
2. Dynamic plotting - The Contractor shall also provide dynamic plotting during Systems Functional Performance testing at frequent intervals for points determined by the Systems Functional Performance Test Procedure. The graphical plots will be formatted and plotted at durations listed in the Systems Functional Performance Test Procedure.
3. Graphical plotting - The graphical plots shall be provided with a dual y-axis allowing 15 or more trend points (series) plotted simultaneously on the graph with each series in distinct color. The plots will further require title, axis naming, legend etc. all described by the Systems Functional Performance Test Procedure. If this cannot be sufficiently accomplished directly in the Direct Digital Control System then it is the responsibility of the Contractor to plot these trend logs in Microsoft Excel.

4. The following tables indicate the points to be trended and alarmed by system. The Operational Trend Duration column indicates the trend duration for normal operations. The Testing Trend Duration column indicates the trend duration prior to Systems Functional Performance Testing and again after Systems Functional Performance Testing. The Type column indicates point type: AI = Analog Input, AO = Analog Output, DI = Digital Input, DO = Digital Output, Calc = Calculated Point. In the Trend Interval Column, COV = Change of Value. The Alarm Type indicates the alarm priority; C = Critical, P = Priority, and M = Maintenance. The Alarm Range column indicates when the point is considered in the alarm state. The Alarm Delay column indicates the length of time the point must remain in an alarm state before the alarm is recorded in the DDC. The intent is to allow minor, short-duration events to be corrected by the DDC system prior to recording an alarm.

| Dual-Path Air Handling Unit Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point   | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| OA Temperature                                  | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| RA Temperature                                  | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| RA Humidity                                     | AI   | 15 Min         | 24 hours                   | 3 days                 | P          | >60% RH           | 10 min      |
| Mixed Air Temp                                  | AI   | None           | None                       | None                   | N/A        |                   |             |
| SA Temp   | AI   | 15 Min         | 24 hours                   | 3 days                 | C          | ±5°F from SP      | 10 min      |
| Supply Fan Speed                                | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| Return Fan Speed                                | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| RA Pre-Filter Status                            | AI   | None           | None                       | None                   | N/A        |                   |             |
| OA Pre-Filter Status                            | AI   | None           | None                       | None                   | N/A        |                   |             |
| After Filter Status                             | AI   | None           | None                       | None                   | N/A        |                   |             |
| SA Flow   | AI   | 15 Min         | 24 hours                   | 3 days                 | C          | ±10% from SP      | 10 min      |
| OA Supply Temp                                  | AI   | 15 Min         | 24 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
| RA Supply Temp                                  | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| RA CHW Valve Position                           | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| OA CHW Valve Position                           | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| OA HW Valve Position                            | AI   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| OA Flow   | AI   | 15 Min         | 24 hours                   | 3 days                 | P          | ±10% from SP      | 5 min       |
| RA Flow   | AI   | 15 Min         | 24 hours                   | 3 days                 | P          | ±10% from SP      | 5 min       |
| Initial UVC Intensity (%)                       | AI   | None           | None                       | None                   | N/A        |                   |             |
| Duct Pressure                                   | AI   | 15 Min         | 24 hours                   | 3 days                 | C          | ±25% from SP      | 6 min       |
| CO2 Level                                       | AI   | 15 Min         | 24 hours                   | 3 days                 | P          | ±10% from SP      | 10 min      |
|   |      |                |                            |                        |            |                   |             |
| Supply Fan Status                               | DI   | COV            | 24 hours                   | 3 days                 | C          | Status <> Command | 10 min      |

| Dual-Path Air Handling Unit Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point   | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Return Fan Status                               | DI   | COV            | 24 hours                   | 3 days                 | C          | Status <> Command | 10 Min      |
| High Static Status                              | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 1 min       |
| Fire Alarm Status                               | DI   | COV            | 24 hours                   | 3 days                 | C          | True              | 5 min       |
| Freeze Stat Level 1                             | DI   | COV            | 24 hours                   | 3 days                 | C          | True              | 10 min      |
| Freeze Stat Level 2                             | DI   | COV            | 24 hours                   | 3 days                 | C          | True              | 5 min       |
| Freeze Stat Level 3                             | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 1 min       |
| Fire/Smoke Damper Status                        | DI   | COV            | 24 hours                   | 3 days                 | P          | Closed            | 1 min       |
| Emergency AHU Shutdown                          | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 1 min       |
| Exhaust Fan #1 Status                           | DI   | COV            | 24 hours                   | 3 days                 | C          | Status <> Command | 10 min      |
| Exhaust Fan #2 Status                           | DI   | COV            | 24 hours                   | 3 days                 | C          | Status <> Command | 10 min      |
| Exhaust Fan #3 Status                           | DI   | COV            | 24 hours                   | 3 days                 | C          | Status <> Command | 10 min      |
| OA Alarm  | DI   | COV            | 24 hours                   | 3 days                 | C          | True              | 10 min      |
| High Static Alarm                               | DI   | COV            | 24 hours                   | 3 days                 | C          | True              | 10 min      |
| UVC Emitter Alarm                               | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 10 min      |
| CO2 Alarm                                       | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 10 min      |
| Power Failure                                   | DI   | COV            | 24 hours                   | 3 days                 | P          | True              | 1 min       |
|   |      |                |                            |                        |            |                   |             |
| Supply Fan Speed                                | AO   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| Return Fan Speed                                | AO   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| RA CHW Valve Position                           | AO   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| OA CHW Valve Position                           | AO   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
| OA HW Valve Position                            | AO   | 15 Min         | 24 hours                   | 3 days                 | N/A        |                   |             |
|   |      |                |                            |                        |            |                   |             |

| Dual-Path Air Handling Unit Trending and Alarms |      |                |                            |                        |            |             |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------|-------------|
| Point   | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range | Alarm Delay |
| Supply Fan S/S                                  | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
| Return Fan S/S                                  | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
| Fire/Smoke Dampers                              | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
| Exhaust Fan S/S                                 | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
| Exhaust Fan S/S                                 | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
| Exhaust Fan S/S                                 | DO   | COV            | 24 hours                   | 3 days                 | N/A        |             |             |
|   |      |                |                            |                        |            |             |             |
| AHU Energy                                      | Calc | 1 Hour         | 30 day                     | N/A                    | N/A        |             |             |
|   |      |                |                            |                        |            |             |             |



| Terminal Unit (VAV, CAV, etc.) Trending and Alarms |      |                |                            |                        |            |               |             |
|--|------|----------------|----------------------------|------------------------|------------|---------------|-------------|
| Point  | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range   | Alarm Delay |
| Space Temperature                                  | AI   | 15 Min         | 12 hours                   | 3 days                 | P          | ±5°F from SP  | 10 min      |
| Air Flow   | AI   | 15 Min         | 12 hours                   | 3 days                 | P          | ±5°F from SP  | 10 min      |
| SA Temperature                                     | AI   | 15 Min         | 12 hours                   | 3 days                 | P          | ±5°F from SP  | 10 min      |
| Local Set-point                                    | AI   | 15 Min         | 12 hours                   | 3 days                 | M          | ±10°F from SP | 60 min      |
| Space Humidity                                     | AI   | 15 Min         | 12 hours                   | 3 days                 | P          | > 60% RH      | 5 min       |
|  |      |                |                            |                        |            |               |             |
| Unoccupied Override                                | DI   | COV            | 12 hours                   | 3 days                 | M          | N/A           | 12 Hours    |
| Refrigerator Alarm                                 | DI   | COV            | 12 hours                   | 3 days                 | C          | N/A           | 10 min      |
|  |      |                |                            |                        |            |               |             |
| Damper Position                                    | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |               |             |
| Heating coil Valve Position                        | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |               |             |

| 4-Pipe Fan Coil Trending and Alarms |      |                |                            |                        |            |                   |             |
|-------------------------------------|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                               | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Space Temperature                   | AI   | 15 Minutes     | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
| SA Temperature                      | AI   | 15 Minutes     | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
| Pre-Filter Status                   | AI   | None           | None                       | None                   | M          | > SP              | 1 hour      |
|                                     |      |                |                            |                        |            |                   |             |
| Water Sensor                        | DI   | COV            | 12 hours                   | 3 days                 | M          | N/A               | 30 Min      |
|                                     |      |                |                            |                        |            |                   |             |
| Cooling Coil Valve Position         | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Heating coil Valve Position         | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Fan Coil ON/OFF                     | DO   | COV            | 12 hours                   | 3 days                 | M          | Status <> Command | 30 min      |

| 2-Pipe Fan Coil Unit Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                    | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Space Temperature                        | AI   | 15 Minutes     | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
| SA Temperature                           | AI   | 15 Minutes     | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
| Pre-Filter Status                        | AI   | None           | None                       | None                   | M          | > SP              | 1 hour      |
|  |      |                |                            |                        |            |                   |             |
| Water Sensor                             | DI   | COV            | 12 hours                   | 3 days                 | M          | N/A               | 30 Min      |
|  |      |                |                            |                        |            |                   |             |
| Cooling Coil Valve Position              | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Fan Coil ON/OFF                          | DO   | COV            | 12 hours                   | 3 days                 | M          | Status <> Command | 30 min      |

| Unit Heater Trending and Alarms |      |                |                            |                        |            |                   |             |
|---------------------------------|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                           | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Space Temperature               | AI   | 15 Minutes     | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 min      |
|                                 |      |                |                            |                        |            |                   |             |
| Heating Valve Position          | AO   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
|                                 |      |                |                            |                        |            |                   |             |
| Unit Heater ON/OFF              | DO   | COV            | 12 hours                   | 3 days                 | M          | Status <> Command | 30 min      |

| Steam and Condensate Pumps Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point  | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Steam Flow (LB/HR)                             | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Condensate Pump Run Hours                      | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Water Meter (GPM)                              | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Electric Meter (KW/H)                          | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Irrigation Meter (GPM)                         | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Chilled Water Flow (TONS)                      | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
| Condensate Flow (GPM)                          | AI   | 15 Minutes     | 12 hours                   | 3 days                 | N/A        |                   |             |
|  |      |                |                            |                        |            |                   |             |
| High Water Level Alarm                         | DI   | COV            | 12 hours                   | 3 days                 | C          | True              | 5 Min       |
|  |      |                |                            |                        |            |                   |             |
| Condensate Pump Start/Stop                     | DO   | COV            | 12 hours                   | 3 days                 | P          | Status <> Command | 10 min      |

| Domestic Hot Water Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                  | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Domestic HW Setpoint WH-1              | AI   | 15 Minute      | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Domestic HW Setpoint WH-2              | AI   | 15 Minute      | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Domestic HW Temperature                | AI   | 15 Minute      | 12 Hours                   | 3 days                 | C          | > 135 °F          | 10 Min      |
| Domestic HW Temperature                | AI   | 15 Minute      | 12 Hours                   | 3 days                 | P          | ±5°F from SP      | 10 Min      |
|  |      |                |                            |                        |            |                   |             |
| Dom. Circ. Pump #1 Status              | DI   | COV            | 12 Hours                   | 3 days                 | M          | Status <> Command | 30 min      |
| Dom. Circ. Pump #2 Status              | DI   | COV            | 12 Hours                   | 3 days                 | M          | Status <> Command | 30 min      |
|  |      |                |                            |                        |            |                   |             |
| Dom. Circ. Pump #1 Start/Stop          | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Dom. Circ. Pump #2 Start/Stop          | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Domestic HW Start/Stop                 | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Hydronic Hot Water Trending and Alarms      |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                       | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| System HWS Temperature                      | AI   | 15 min         | 12 hours                   | 3 days                 | C          | ±5°F from SP      | 10 Min      |
| System HWR Temperature                      | AI   | 15 min         | 12 hours                   | 3 days                 | M          | ±15°F from SP     | 300 Min     |
| HX-1 Entering Temperature                   | AI   | 15 min         | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 Min      |
| HX-2 Entering Temperature                   | AI   | 15 min         | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 Min      |
| HX-2 Leaving Temperature                    | AI   | 15 min         | 12 hours                   | 3 days                 | P          | ±5°F from SP      | 10 Min      |
|   |      |                |                            |                        |            |                   |             |
| System Flow (GPM)                           | AI   | 15 min         | 12 hours                   | 3 days                 | N/A        |                   |             |
| System Differential Pressure                | AI   | 15 min         | 12 hours                   | 3 days                 | P          | ±10% from SP      | 8 Min       |
|   |      |                |                            | 3 days                 |            |                   |             |
| HW Pump 1 Status                            | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| HW Pump 2 Status                            | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
|   |      |                |                            |                        |            |                   |             |
| HW Pump 1 VFD Speed                         | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| HW Pump 2 VFD Speed                         | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Steam Station #1 1/3 Control Valve Position | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Steam Station #1 2/3 Control Valve Position | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Steam Station #2 1/3 Control Valve Position | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Steam Station #2 2/3 Control Valve Position | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Steam Station Bypass Valve Position         | AO   | 15 Min         | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Hydronic Hot Water Trending and Alarms |      |                |                            |                        |            |             |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------|-------------|
| Point                                  | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range | Alarm Delay |
|  |      |                |                            |                        |            |             |             |
| HW Pump 1 Start/Stop                   | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| HW Pump 2 Start/Stop                   | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| HWR #1 Valve                           | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| HWR #2 Valve                           | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |

| Chilled Water System Trending and Alarms |      |                |                            |                        |            |              |             |
|--|------|----------------|----------------------------|------------------------|------------|--------------|-------------|
| Point                                    | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range  | Alarm Delay |
| Chiller 1 Entering Temperature           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 1 Leaving Temperature            | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5°F from SP | 10 Min      |
| Chiller 1 Flow                           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 1 Percent Load                   | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 1 KW Consumption                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 1 Tonnage                        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 2 Entering Temperature           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 2 Leaving Temperature            | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5°F from SP | 10 Min      |
| Chiller 2 Flow                           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 2 Percent Load                   | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 2 KW Consumption                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Chiller 2 Tonnage                        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Primary Loop Decoupler Flow              | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Primary Loop Flow                        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Primary Loop Supply Temperature          | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Secondary Loop Differential Pressure     | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5% from SP  | 10 Min      |
| Secondary Loop Flow                      | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Secondary Loop Supply Temperature        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |
| Secondary Loop Return Temperature        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |              |             |



| Chilled Water System Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                    | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Secondary Loop Tonnage                   | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
|  |      |                |                            |                        |            |                   |             |
| Primary Loop Pump 1 Status               | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Primary Loop Pump 2 Status               | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Secondary Loop Pump 1 Status             | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Secondary Loop Pump 2 Status             | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Chiller 1 Status                         | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Chiller 1 Evaporator Iso-Valve           | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 1 Evaporator Flow Switch         | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 1 Unit Alarm                     | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 10 Min      |
| Chiller 2 Status                         | DI   | COV            | 12 Hours                   | 3 days                 | C          | Status <> Command | 30 min      |
| Chiller 2 Evaporator Iso-Valve           | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 2 Evaporator Flow Switch         | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 2 Unit Alarm                     | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 10 Min      |
| Refrigerant Detector                     | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 10 Min      |
| Refrigerant Exhaust Fan Status           | DI   | COV            | 12 Hours                   | 3 days                 | M          | Status <> Command | 30 min      |
| Emergency Shutdown                       | DI   | COV            | 12 Hours                   | 3 days                 | P          | True              | 1 Min       |
|  |      |                |                            |                        |            |                   |             |
| Primary Loop Pump 1 VFD Speed            | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Chilled Water System Trending and Alarms |      |                |                            |                        |            |             |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------|-------------|
| Point                                    | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range | Alarm Delay |
| Primary Loop Pump 2 VFD Speed            | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |             |             |
| Secondary Loop Pump 1 VFD Speed          | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |             |             |
| Secondary Loop Pump 2 VFD Speed          | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |             |             |
|  |      |                |                            |                        |            |             |             |
| Primary Pump 1 Start / Stop              | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Primary Pump 2 Start / Stop              | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Secondary Pump 1 Start / Stop            | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Secondary Pump 2 Start / Stop            | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Chiller 1 Enable                         | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Chiller 1 Iso-Valve Command              | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Chiller 2 Enable                         | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Chiller 2 Iso-Valve Command              | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |
| Refrigerant Exhaust Fan Start / Stop     | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |             |             |

| Condenser Water System Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                      | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Chiller 1 Condenser Entering Temp          | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 1 Condenser Leaving Temp           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 2 Condenser Entering Temp          | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 2 Condenser Leaving Temp           | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Supply Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Return Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Basin Temp                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | < 45 °F           | 10 Min      |
| Cooling Tower 2 Supply Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Return Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Basin Temp                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | < 45 °F           | 10 Min      |
| Condenser Water Supply Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Condenser Water Return Temp                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Outdoor Air Wet Bulb                       | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
|  |      |                |                            |                        |            |                   |             |
| Cooling Tower 1 Fan Status                 | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
| Cooling Tower 1 Basin Heat                 | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Heat Trace                 | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Fan Status                 | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
| Cooling Tower 2 Basin Heat                 | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Heat Trace                 | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Condenser Water System Trending and Alarms |      |                |                            |                        |            |                   |             |
|--|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                      | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Chiller 1 Isolation Valve                  | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
| Chiller 2 Isolation Valve                  | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
| Condenser Water Pump 1 Status              | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
| Condenser Water Pump 2 Status              | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 1 min       |
|  |      |                |                            |                        |            |                   |             |
| Chiller 1 Condenser Bypass Valve           | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Chiller 2 Condenser Bypass Valve           | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Bypass Valve               | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 1 Fan Speed                  | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Bypass Valve               | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Fan Speed                  | AO   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
|  |      |                |                            |                        |            |                   |             |
| Cooling Tower 1 Fan Start / Stop           | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Cooling Tower 2 Fan Start / Stop           | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Condenser Water Pump 1 Start / Stop        | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Condenser Water Pump 2 Start / Stop        | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Steam Boiler System Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                   | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Boiler 1 Steam Pressure                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5% from SP       | 10 Min      |
| Boiler 1 Steam Temperature              | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Fire Signal                    | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Steam Pressure                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5% from SP       | 10 Min      |
| Boiler 2 Steam Temperature              | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Fire Signal                    | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| System Steam Pressure                   | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5% from SP       | 10 Min      |
|   |      |                |                            |                        |            |                   |             |
| Boiler 1 Enable                         | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Status                         | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Boiler 1 Alarm                          | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 1 Min       |
| Boiler 1 on Fuel Oil                    | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Low Water Alarm                | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 5 Min       |
| Boiler 1 High Water Alarm               | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 5 Min       |
| Boiler 1 Feed Pump                      | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Enable                         | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Status                         | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Boiler 2 Alarm                          | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 1 Min       |
| Boiler 2 on Fuel Oil                    | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Low Water Alarm                | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 5 Min       |
| Boiler 2 High Water Alarm               | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 5 Min       |

| Steam Boiler System Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                   | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Boiler 2 Feed Pump                      | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Combustion Damper Status                | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 5 min       |
| Condensate Recovery Pump Status         | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 5 min       |
|   |      |                |                            |                        |            |                   |             |
| Boiler 1 Feed Pump Start / Stop         | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Start / Stop                   | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Combustion Damper Command               | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Condensate Recovery Pump Start / Stop   | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Hot Water Boiler System Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                       | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Outside Air Temperature                     | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Fire Signal                        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Entering Water Temperature         | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Leaving Water Temperature          | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Fire Signal                        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Entering Water Temperature         | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Leaving Water Temperature          | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Hot Water Supply Temperature                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | P          | ±5 °F from SP     | 10 Min      |
| Hot Water Return Temperature                | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Secondary Loop Differential Pressure        | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | C          | ±5% from SP       | 10 Min      |
| Lead Boiler                                 | AI   | 15 Minutes     | 12 Hours                   | 3 days                 | N/A        |                   |             |
|   |      |                |                            |                        |            |                   |             |
| Boiler 1 Enable                             | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Status                             | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Boiler 1 Isolation Valve                    | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 on Fuel Oil                        | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 1 Alarm                              | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 1 Min       |
| Boiler 2 Enable                             | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Status                             | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Boiler 2 Isolation Valve                    | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |

| Hot Water Boiler System Trending and Alarms |      |                |                            |                        |            |                   |             |
|---|------|----------------|----------------------------|------------------------|------------|-------------------|-------------|
| Point                                       | Type | Trend Interval | Operational Trend Duration | Testing Trend Duration | Alarm Type | Alarm Range       | Alarm Delay |
| Boiler 2 on Fuel Oil                        | DI   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Boiler 2 Alarm                              | DI   | COV            | 12 Hours                   | 3 days                 | C          | True              | 1 Min       |
| Combustion Dampers Open                     | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Primary Pump 1 Status                       | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Primary Pump 2 Status                       | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Secondary Pump 1 Status                     | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
| Secondary Pump 2 Status                     | DI   | COV            | 12 Hours                   | 3 days                 | P          | Status <> Command | 10 min      |
|   |      |                |                            |                        |            |                   |             |
| Primary Pump 1 VFD Speed                    | AO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Primary Pump 2 VFD Speed                    | AO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Secondary Pump 1 VFD Speed                  | AO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Secondary Pump 2 VFD Speed                  | AO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
|   |      |                |                            |                        |            |                   |             |
| Hot Water System Enable                     | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Combustion Dampers Command                  | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Primary Pump 1 Start / Stop                 | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Primary Pump 2 Start / Stop                 | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Secondary Pump 1 Start / Stop               | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |
| Secondary Pump 2 Start / Stop               | DO   | COV            | 12 Hours                   | 3 days                 | N/A        |                   |             |



E. The Contractor shall provide the following information prior to Systems Functional Performance Testing. Any documentation that is modified after submission shall be recorded and resubmitted to the Resident Engineer and Commissioning Agent.

1. Point-to-Point checkout documentation;
2. Sensor field calibration documentation including system name, sensor/point name, measured value, DDC value, and Correction Factor.
3. A sensor calibration table listing the referencing the location of procedures to following in the O&M manuals, and the frequency at which calibration should be performed for all sensors, separated by system, subsystem, and type. The calibration requirements shall be submitted both in the O&M manuals and separately in a standalone document containing all sensors for inclusion in the commissioning documentation. The following table is a sample that can be used as a template for submission.

| <b>SYSTEM</b>             |                              |  |
|---------------------------|------------------------------|--|
| <b>Sensor</b>             | <b>Calibration Frequency</b> | <b>O&amp;M Calibration Procedure Reference</b> |
| Discharge air temperature | Once a year                  | Volume I Section D.3.aa                        |
| Discharge static pressure | Every 6 months               | Volume II Section A.1.c                        |

4. Loop tuning documentation and constants for each loop of the building systems. The documentation shall be submitted in outline or table separated by system, control type (e.g. heating valve temperature control); proportional, integral and derivative constants, interval (and bias if used) for each loop. The following table is a sample that can be used as a template for submission.

| <b>AIR HANDLING UNIT AHU-1</b> |                              |                          |                            |                 |
|--------------------------------|------------------------------|--------------------------|----------------------------|-----------------|
| <b>Control Reference</b>       | <b>Proportional Constant</b> | <b>Integral Constant</b> | <b>Derivative Constant</b> | <b>Interval</b> |
| Heating Valve Output           | 1000                         | 20                       | 10                         | 2 sec.          |

### 3.5 SYSTEMS FUNCTIONAL PERFORMANCE TESTING

- A. This paragraph applies to Systems Functional Performance Testing of systems for all referenced specification Divisions.
- B. Objectives and Scope: The objective of Systems Functional Performance Testing is to demonstrate that each system is operating according to the Contract Documents. Systems Functional Performance Testing facilitates bringing the systems from a state of substantial completion to full dynamic operation. Additionally, during the testing process, areas of noncompliant performance are identified and corrected, thereby improving the operation and functioning of the systems. In general, each system shall be operated through all modes of operation (seasonal, occupied, unoccupied, warm-up, cool-down, part- and full-load, fire alarm and emergency power) where there is a specified system response. The Contractor shall verify each sequence in the sequences of operation. Proper responses to such modes and conditions as power failure, freeze condition, low oil pressure, no flow, equipment failure, etc. shall also be tested.
- C. Development of Systems Functional Performance Test Procedures: Before Systems Functional Performance Test procedures are written, the Contractor shall submit all requested documentation and a current list of change orders affecting equipment or systems, including an updated points list, program code, control sequences and parameters. Using the testing parameters and requirements found in the Contract Documents and approved submittals and shop drawings, the Commissioning Agent will develop specific Systems Functional Test Procedures to verify and document proper operation of each piece of equipment and system to be commissioned. The Contractor shall assist the Commissioning Agent in developing the Systems Functional Performance Test procedures as requested by the Commissioning Agent i.e. by answering questions about equipment, operation, sequences, etc. Prior to execution, the Commissioning Agent will provide a copy of the Systems Functional Performance Test procedures to the VA, the Architect/Engineer, and the Contractor, who shall review the tests for feasibility, safety, equipment and warranty protection.
- D. Purpose of Test Procedures: The purpose of each specific Systems Functional Performance Test is to verify and document compliance with the stated criteria of acceptance given on the test form.

Representative test formats and examples are found in the Commissioning Plan for this project. (The Commissioning Plan is issued as a separate document and is available for review.) The test procedure forms developed by the Commissioning Agent will include, but not be limited to, the following information:

1. System and equipment or component name(s)
  2. Equipment location and ID number
  3. Unique test ID number, and reference to unique Pre-Functional Checklists and startup documentation, and ID numbers for the piece of equipment.
  4. Date
  5. Project name
  6. Participating parties
  7. A copy of the specification section describing the test requirements
  8. A copy of the specific sequence of operations or other specified parameters being verified
  9. Formulas used in any calculations
  10. Required pretest field measurements
  11. Instructions for setting up the test.
  12. Special cautions, alarm limits, etc.
  13. Specific step-by-step procedures to execute the test, in a clear, sequential and repeatable format
  14. Acceptance criteria of proper performance with a Yes / No check box to allow for clearly marking whether or not proper performance of each part of the test was achieved.
  15. A section for comments.
  16. Signatures and date block for the Commissioning Agent. A place for the Contractor to initial to signify attendance at the test.
- E. Test Methods: Systems Functional Performance Testing shall be achieved by manual testing (i.e. persons manipulate the equipment and observe performance) and/or by monitoring the performance and analyzing the results using the control system's trend log capabilities or by standalone data loggers. The Contractor and Commissioning Agent shall determine which method is most appropriate for tests that do not have a method specified.
1. Simulated Conditions: Simulating conditions (not by an overwritten value) shall be allowed, although timing the testing to experience actual conditions is encouraged wherever practical.

2. Overwritten Values: Overwriting sensor values to simulate a condition, such as overwriting the outside air temperature reading in a control system to be something other than it really is, shall be allowed, but shall be used with caution and avoided when possible. Such testing methods often can only test a part of a system, as the interactions and responses of other systems will be erroneous or not applicable. Simulating a condition is preferable. e.g., for the above case, by heating the outside air sensor with a hair blower rather than overwriting the value or by altering the appropriate setpoint to see the desired response. Before simulating conditions or overwriting values, sensors, transducers and devices shall have been calibrated.
  3. Simulated Signals: Using a signal generator which creates a simulated signal to test and calibrate transducers and DDC constants is generally recommended over using the sensor to act as the signal generator via simulated conditions or overwritten values.
  4. Altering Setpoints: Rather than overwriting sensor values, and when simulating conditions is difficult, altering setpoints to test a sequence is acceptable. For example, to see the Air Conditioning compressor lockout initiate at an outside air temperature below 12 C (54 F), when the outside air temperature is above 12 C (54 F), temporarily change the lockout setpoint to be 2 C (4 F) above the current outside air temperature.
  5. Indirect Indicators: Relying on indirect indicators for responses or performance shall be allowed only after visually and directly verifying and documenting, over the range of the tested parameters, that the indirect readings through the control system represent actual conditions and responses. Much of this verification shall be completed during systems startup and initial checkout.
- F. Setup: Each function and test shall be performed under conditions that simulate actual conditions as closely as is practically possible. The Contractor shall provide all necessary materials, system modifications, etc. to produce the necessary flows, pressures, temperatures, etc. necessary to execute the test according to the specified conditions. At completion of the test, the Contractor shall return all affected building equipment and systems, due to these temporary modifications, to their pretest condition.

- G. Sampling: No sampling is allowed in completing Pre-Functional Checklists. Sampling is allowed for Systems Functional Performance Test Procedures execution. The Commissioning Agent will determine the sampling rate. If at any point, frequent failures are occurring and testing is becoming more troubleshooting than verification, the Commissioning Agent may stop the testing and require the Contractor to perform and document a checkout of the remaining units, prior to continuing with Systems Functional Performance Testing of the remaining units.
- H. Cost of Retesting: The cost associated with expanded sample System Functional Performance Tests shall be solely the responsibility of the Contractor. Any required retesting by the Contractor shall not be considered a justified reason for a claim of delay or for a time extension by the Contractor.
- I. Coordination and Scheduling: The Contractor shall provide a minimum of 7 days notice to the Commissioning Agent and the VA regarding the completion schedule for the Pre-Functional Checklists and startup of all equipment and systems. The Commissioning Agent will schedule Systems Functional Performance Tests with the Contractor and VA. The Commissioning Agent will witness and document the Systems Functional Performance Testing of systems. The Contractor shall execute the tests in accordance with the Systems Functional Performance Test Procedure.
- J. Testing Prerequisites: In general, Systems Functional Performance Testing will be conducted only after Pre-Functional Checklists have been satisfactorily completed. The control system shall be sufficiently tested and approved by the Commissioning Agent and the VA before it is used to verify performance of other components or systems. The air balancing and water balancing shall be completed before Systems Functional Performance Testing of air-related or water-related equipment or systems are scheduled. Systems Functional Performance Testing will proceed from components to subsystems to systems. When the proper performance of all interacting individual systems has been achieved, the interface or coordinated responses between systems will be checked.
- K. Problem Solving: The Commissioning Agent will recommend solutions to problems found, however the burden of responsibility to solve, correct and retest problems is with the Contractor.

### 3.6 DOCUMENTATION, NONCONFORMANCE AND APPROVAL OF TESTS

- A. Documentation: The Commissioning Agent will witness, and document the results of all Systems Functional Performance Tests using the specific procedural forms developed by the Commissioning Agent for that purpose. Prior to testing, the Commissioning Agent will provide these forms to the VA and the Contractor for review and approval. The Contractor shall include the filled out forms with the O&M manual data.
- B. Nonconformance: The Commissioning Agent will record the results of the Systems Functional Performance Tests on the procedure or test form. All items of nonconformance issues will be noted and reported to the VA on Commissioning Field Reports and/or the Commissioning Master Issues Log.
  - 1. Corrections of minor items of noncompliance identified may be made during the tests. In such cases, the item of noncompliance and resolution shall be documented on the Systems Functional Test Procedure.
  - 2. Every effort shall be made to expedite the systems functional Performance Testing process and minimize unnecessary delays, while not compromising the integrity of the procedures. However, the Commissioning Agent shall not be pressured into overlooking noncompliant work or loosening acceptance criteria to satisfy scheduling or cost issues, unless there is an overriding reason to do so by direction from the VA.
  - 3. As the Systems Functional Performance Tests progresses and an item of noncompliance is identified, the Commissioning Agent shall discuss the issue with the Contractor and the VA.
  - 4. When there is no dispute on an item of noncompliance, and the Contractor accepts responsibility to correct it:
    - a. The Commissioning Agent will document the item of noncompliance and the Contractor's response and/or intentions. The Systems Functional Performance Test then continues or proceeds to another test or sequence. After the day's work is complete, the Commissioning Agent will submit a Commissioning Field Report to the VA. The Commissioning Agent will also note items of noncompliance and the Contractor's response in the Master Commissioning Issues Log. The Contractor shall correct the item of noncompliance and report completion to the VA and the Commissioning Agent.

- b. The need for retesting will be determined by the Commissioning Agent. If retesting is required, the Commissioning Agent and the Contractor shall reschedule the test and the test shall be repeated.
- 5. If there is a dispute about item of noncompliance, regarding whether it is an item of noncompliance, or who is responsible:
  - a. The item of noncompliance shall be documented on the test form with the Contractor's response. The item of noncompliance with the Contractor's response shall also be reported on a Commissioning Field Report and on the Master Commissioning Issues Log.
  - b. Resolutions shall be made at the lowest management level possible. Other parties are brought into the discussions as needed. Final interpretive and acceptance authority is with the Department of Veterans Affairs.
  - c. The Commissioning Agent will document the resolution process.
  - d. Once the interpretation and resolution have been decided, the Contractor shall correct the item of noncompliance, report it to the Commissioning Agent. The requirement for retesting will be determined by the Commissioning Agent. If retesting is required, the Commissioning Agent and the Contractor shall reschedule the test. Retesting shall be repeated until satisfactory performance is achieved.
- C. Cost of Retesting: The cost to retest a System Functional Performance Test shall be solely the responsibility of the Contractor. Any required retesting by the Contractor shall not be considered a justified reason for a claim of delay or for a time extension by the Contractor.
- D. Failure Due to Manufacturer Defect: If 10%, or three, whichever is greater, of identical pieces (size alone does not constitute a difference) of equipment fail to perform in compliance with the Contract Documents (mechanically or substantively) due to manufacturing defect, not allowing it to meet its submitted performance specifications, all identical units may be considered unacceptable by the VA. In such case, the Contractor shall provide the VA with the following:
  - 1. Within one week of notification from the VA, the Contractor shall examine all other identical units making a record of the findings.

The findings shall be provided to the VA within two weeks of the original notice.

2. Within two weeks of the original notification, the Contractor shall provide a signed and dated, written explanation of the problem, cause of failures, etc. and all proposed solutions which shall include full equipment submittals. The proposed solutions shall not significantly exceed the specification requirements of the original installation.
3. The VA shall determine whether a replacement of all identical units or a repair is acceptable.
4. Two examples of the proposed solution shall be installed by the Contractor and the VA shall be allowed to test the installations for up to one week, upon which the VA will decide whether to accept the solution.
5. Upon acceptance, the Contractor shall replace or repair all identical items, at their expense and extend the warranty accordingly, if the original equipment warranty had begun. The replacement/repair work shall proceed with reasonable speed beginning within one week from when parts can be obtained.

E. Approval: The Commissioning Agent will note each satisfactorily demonstrated function on the test form. Formal approval of the Systems Functional Performance Test shall be made later after review by the Commissioning Agent and by the VA. The Commissioning Agent will evaluate each test and report to the VA using a standard form. The VA will give final approval on each test using the same form, and provide signed copies to the Commissioning Agent and the Contractor.

### **3.7 DEFERRED TESTING**

- A. Unforeseen Deferred Systems Functional Performance Tests: If any Systems Functional Performance Test cannot be completed due to the building structure, required occupancy condition or other conditions, execution of the Systems Functional Performance Testing may be delayed upon approval of the VA. These Systems Functional Performance Tests shall be conducted in the same manner as the seasonal tests as soon as possible. Services of the Contractor to conduct these unforeseen Deferred Systems Functional Performance Tests shall be negotiated between the VA and the Contractor.
- B. Deferred Seasonal Testing: Deferred Seasonal Systems Functional Performance Tests are those that must be deferred until weather



conditions are closer to the systems design parameters. The Commissioning Agent will review systems parameters and recommend which Systems Functional Performance Tests should be deferred until weather conditions more closely match systems parameters. The Contractor shall review and comment on the proposed schedule for Deferred Seasonal Testing. The VA will review and approve the schedule for Deferred Seasonal Testing. Deferred Seasonal Systems Functional Performances Tests shall be witnessed and documented by the Commissioning Agent. Deferred Seasonal Systems Functional Performance Tests shall be executed by the Contractor in accordance with these specifications.

### **3.8 OPERATION AND MAINTENANCE TRAINING REQUIREMENTS**

- A. Training Preparation Conference: Before operation and maintenance training, the Commissioning Agent will convene a training preparation conference to include VA's Resident Engineer, VA's Operations and Maintenance personnel, and the Contractor. The purpose of this conference will be to discuss and plan for Training and Demonstration of VA Operations and Maintenance personnel.
- B. The Contractor shall provide training and demonstration as required by other Division 21, Division 22, Division 23, Division 26, Division 27, Division 28, and Division 31 sections. The Training and Demonstration shall include, but is not limited to, the following:
  - 1. Review the Contract Documents.
  - 2. Review installed systems, subsystems, and equipment.
  - 3. Review instructor qualifications.
  - 4. Review instructional methods and procedures.
  - 5. Review training module outlines and contents.
  - 6. Review course materials (including operation and maintenance manuals).
  - 7. Review and discuss locations and other facilities required for instruction.
  - 8. Review and finalize training schedule and verify availability of educational materials, instructors, audiovisual equipment, and facilities needed to avoid delays.
  - 9. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.
- C. Training Module Submittals: The Contractor shall submit the following information to the VA and the Commissioning Agent:

1. Instruction Program: Submit two copies of outline of instructional program for demonstration and training, including a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module. At completion of training, submit two complete training manuals for VA's use.
2. Qualification Data: Submit qualifications for facilitator and/or instructor.
3. Attendance Record: For each training module, submit list of participants and length of instruction time.
4. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.
5. Demonstration and Training Videotapes: Submit two copies within seven days of end of each training module.
  - a. Identification: On each copy, provide an applied label with the following information:
    - 1) Name of Project.
    - 2) Name and address of photographer
    - 3) Name of Contractor.
    - 4) Date videotape was recorded.
    - 5) Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
6. Transcript: Prepared on 8-1/2-by-11-inch paper, punched and bound in heavy-duty, 3-ring, vinyl-covered binders. Mark appropriate identification on front and spine of each binder. Include a cover sheet with same label information as the corresponding videotape. Include name of Project and date of videotape on each page.

D. QUALITY ASSURANCE

1. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
2. Instructor Qualifications: A factory authorized service representative, complying with requirements in Division 01 Section "Quality Requirements," experienced in operation and maintenance procedures and training.

3. Photographer Qualifications: A professional photographer who is experienced photographing construction projects.

E. COORDINATION

1. Coordinate instruction schedule with VA's operations. Adjust schedule as required to minimize disrupting VA's operations.
2. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
3. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by the VA.

F. INSTRUCTION PROGRAM

1. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections, and as follows:
  - a. Fire protection systems, including fire alarm, fire pumps, and fire suppression systems.
  - b. Intrusion detection systems.
  - c. Conveying systems, including elevators, wheelchair lifts, escalators, and automated materials handling systems.
  - d. Medical equipment, including medical gas equipment and piping.
  - e. Laboratory equipment, including laboratory air and vacuum equipment and piping.
  - f. Heat generation, including boilers, feedwater equipment, pumps, steam distribution piping, condensate return systems, heating hot water heat exchangers, and heating hot water distribution piping.
  - g. Refrigeration systems, including chillers, cooling towers, condensers, pumps, and distribution piping.
  - h. HVAC systems, including air handling equipment, air distribution systems, and terminal equipment and devices.
  - i. switchgear, transformers, switchboards, panelboards, uninterruptible power supplies, and motor controls.
  - j. Packaged engine generators, including synchronizing switchgear/switchboards, and transfer switches.
  - k. Lighting equipment and controls.
  - l. Communication systems, including intercommunication, surveillance, nurse call systems, public address, mass

evacuation, voice and data, and entertainment television equipment.

- m. Site utilities including lift stations, condensate pumping and return systems, and storm water pumping systems.

G. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participants are expected to master. For each module, include instruction for the following:

- 1. Basis of System Design, Operational Requirements, and Criteria:

Include the following:

- a. System, subsystem, and equipment descriptions.
- b. Performance and design criteria if Contractor is delegated design responsibility.
- c. Operating standards.
- d. Regulatory requirements.
- e. Equipment function.
- f. Operating characteristics.
- g. Limiting conditions.
- h. Performance curves.

- 2. Documentation: Review the following items in detail:

- a. Emergency manuals.
- b. Operations manuals.
- c. Maintenance manuals.
- d. Project Record Documents.
- e. Identification systems.
- f. Warranties and bonds.
- g. Maintenance service agreements and similar continuing commitments.

- 3. Emergencies: Include the following, as applicable:

- a. Instructions on meaning of warnings, trouble indications, and error messages.
- b. Instructions on stopping.
- c. Shutdown instructions for each type of emergency.
- d. Operating instructions for conditions outside of normal operating limits.
- e. Sequences for electric or electronic systems.
- f. Special operating instructions and procedures.

- 4. Operations: Include the following, as applicable:

- a. Startup procedures.
  - b. Equipment or system break-in procedures.
  - c. Routine and normal operating instructions.
  - d. Regulation and control procedures.
  - e. Control sequences.
  - f. Safety procedures.
  - g. Instructions on stopping.
  - h. Normal shutdown instructions.
  - i. Operating procedures for emergencies.
  - j. Operating procedures for system, subsystem, or equipment failure.
  - k. Seasonal and weekend operating instructions.
  - l. Required sequences for electric or electronic systems.
  - m. Special operating instructions and procedures.
5. Adjustments: Include the following:
- a. Alignments.
  - b. Checking adjustments.
  - c. Noise and vibration adjustments.
  - d. Economy and efficiency adjustments.
6. Troubleshooting: Include the following:
- a. Diagnostic instructions.
  - b. Test and inspection procedures.
7. Maintenance: Include the following:
- a. Inspection procedures.
  - b. Types of cleaning agents to be used and methods of cleaning.
  - c. List of cleaning agents and methods of cleaning detrimental to product.
  - d. Procedures for routine cleaning
  - e. Procedures for preventive maintenance.
  - f. Procedures for routine maintenance.
  - g. Instruction on use of special tools.
8. Repairs: Include the following:
- a. Diagnosis instructions.
  - b. Repair instructions.
  - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - d. Instructions for identifying parts and components.
  - e. Review of spare parts needed for operation and maintenance.
- H. Training Execution:

1. Preparation: Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a combined training manual. Set up instructional equipment at instruction location.
2. Instruction:
  - a. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Department of Veterans Affairs for number of participants, instruction times, and location.
  - b. Instructor: Engage qualified instructors to instruct VA's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
    - 1) The Commissioning Agent will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
    - 2) The VA will furnish an instructor to describe VA's operational philosophy.
    - 3) The VA will furnish the Contractor with names and positions of participants.
3. Scheduling: Provide instruction at mutually agreed times. For equipment that requires seasonal operation, provide similar instruction at start of each season. Schedule training with the VA and the Commissioning Agent with at least seven days' advance notice.
4. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of an oral, or a written, performance-based test.
5. Cleanup: Collect used and leftover educational materials and remove from Project site. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

I. Demonstration and Training Recording:

1. General: Engage a qualified commercial photographer to record demonstration and training. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice. At beginning of each training module, record each chart containing learning objective and lesson outline.
2. Video Format: Provide high quality color DVD color on standard size DVD disks.
3. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.
4. Narration: Describe scenes on videotape by audio narration by microphone while demonstration and training is recorded. Include description of items being viewed. Describe vantage point, indicating location, direction (by compass point), and elevation or story of construction.

----- END -----