

SECTION 09 06 00
SCHEDULE FOR FINISHES

ADDENDUM ITEMS NOTED IN BOLD AND DIFFERENT FONT

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: VHSO Fayetteville Station

Location: Fayetteville, Arkansas

Project No. and Name: Project No. 564-341 - Renovate Leroy Pond Army Reserve Center for Mental Health
Residential Rehabilitation Treatment / Police Training.

Submission: 100% Construction Documents

Date: August 17, 2012

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations. It also reflects the Basis of Design for Products Specified.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed **which are "Or Equal"** and meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1.4 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)
 - 2001.....Architectural Painting Specification Manual

PART 2- PRODUCTS

2.1 COLOR SLIDES

- A. Size 24 x 35 mm.
- B. Labeled for:
 - 1. Building name and Number.
 - 2. Room Name and Number.

2.2 DIVISION 31 - EARTHWORK

A. SECTION 32 31 13, CHAIN LINK FENCES AND GATES

Finish Chain Link Fabric	Finish Posts and Rails	Manufacturer	Mfg. Color Name/No.
Galvanized	Galvanized	ANPING	Galvanized

B. SECTION 32 14 16, DETECTABLE WARNING PAVERS.

Size	Pattern	Manufacturer	Mfg. Color Name/No.
12" X 12" X 2" ADA Warning Pavers	Raised Discs	Hanover	Thin=Set / Charcoal

C. SECTION 32 17 23, PAVEMENT MARKINGS.

Color	Manufacturer	MFG. Color Name/No.
Yellow	N/A	
White	N/A	

2.3 DIVISION 03 - CONCRETE

A. SECTION 03 30 00, CAST IN PLACE CONCRETE

Surface	Finish Description
Interior and Exterior Exposed Areas	Coating to Match Masonry Mortar

2.4 DIVISION 04 - MASONRY

A. Section 04 05 13, MASONRY MORTARING and Section 04 05 16, MASONRY GROUTING

Finish Code	Manufacturer	Mfg. Color Name
N/A	Spec Mix	Standard Gray

B. Section 04 20 00, UNIT MASONRY (Design Intent to Match Existing Brick)

1. FACE BRICK (FB)				
Finish Code	Size	Pattern	Manufacturer	Mfg. Color Name/No.
Smooth Texture	Modular	Running Bond	Acme - Tulsa Plant	50% Blend 2 50% Blend 3 Mingle
Adjustable Veneer Anchors	Varies	N/A	Hohman & Barnard	HB-200 Achors with "U" - Shaped Pintels

2. CONCRETE MASONRY UNIT (CMU)				
Type	Size	Pattern	Finish	Mfg. Color Name/No.
CMU Standard	8 x 8 x 16	Running Bond	Standard	Arkola - Gray

C. Section 047200 Cast Stone

Manufacturer	Texture	Finish	Finish Color	
Rock Cast	Smooth	Smooth	Limestone	

2.5 DIVISION 05 - METALS

A. SECTION 05 12 00, STRUCTURAL STEEL FRAMING

Component	Finish	Color
Tubes, Beams, Angles	Painted	Concealed - Primed / Exposed - To Match Limestone Color

B. SECTION 05 21 00, STEEL JOIST FRAMING

Finish	Color
Painted	Concealed - Primed / Exposed - To Match Limestone Color

C. SECTION 05 31 00, STEEL DECKING

Finish	Color
Painted	Concealed - Primed / Exposed - To Match Limestone Color

D. SECTION 05 40 00, COLD-FORMED METAL FRAMING

Finish	Color
Galvanized	Galvanized

E. SECTION 05 50 00, METAL FABRICATION

Item	Finish
Channel Door Frames	Painted
Cast Iron Covers and Frames for Pits and Trenches	Cast Iron
Cast Iron Gratings	Cast Iron
Loose Lintels	Painted
Steel Plate Door Sill	Painted
Aluminum Plate Door Sill	Aluminum
Steel Pipe Railings and Gates (not on Steel Stairs)	Painted

2.6 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

A. SECTION 06 20 00, FINISH CARPENTRY

1. RECEPTION (NURSE 133) COUNTER PUBLIC AND PATIENT SIDE			
Component	Material	Manufacturer	Finish / Color
Countertop	Quartz Material	Zodiaq	Astral Pearl
Vertical Surface(s)	Laminate	Wilsonart	7946-38 / Brazilwood
Reveal	Laminate	Wilsonart	7960K-18 / Studio Teak

2. VANITIES (TYPES S4, S4 M)				
Finish Code	Component	Material	Manufacturer	Finish/Color
S-1	Countertop	Solid Surface	Corian	Witch Hazel
S-1	Trim	Solid Surface	Corian	Witch Hazel

3. Counters - Millwork w/Base and Wall Cabinets				
Finish Code	Component	Material	Manufacturer	Finish/Color

2.7 DIVISION 07 - THERMAL AND MOISTURE PROTECTION

A. SECTION 07 27 20, FLUID APPLIED PERMEABLE MEMBRANE AIR BARRIERS & ENGINEERED TRANSITION ASSEMBLY

Item	Material	Manufacturer
Fluid Applied Permeable Membrane Air Barrier	EXOAIR 230.U-V Resistant	Tremco
Engineered Transition Assembly	Proglaze ETA System 3	Tremco

B. SECTION 07 40 00, SIDING & SOFFIT PANELS

Type	Shape	Ext. Finish	Int. Finish	Manufacturer	Mfg. Color Name/No.
Horizontal - CS-660 - Concept Series Wall Panel	Ribs @ 4" o.c.. Concealed Fasteners	Kynar 500	Painted	Centria	Equal to Zinc-Cote Color Premium Color
Concealed Fastener Soffit Panel IW - 14A	"V" JT. Grooves @ 3" o.c.	Kynar 500	Painted	Centria	Equal to Zinc-Cote color Premium Color

C. SECTION 07 41 50 COMPOSITE METAL BUILDING PANELS

Manufacturer	Material	Color
Reynobond	Aluminum Composite Panel	Natural Brushed Aluminium with Durabrite C clear protective sealant. Coil coated per AAMA 620 Durabrite C high-performance sealant that will not yellow under UV light exposure, and impedes the staining and corrosion consistent with anodized and bare aluminum surfaces.

D. SECTION 07 42 17, INSULATED - CORE METAL WALL BACKUP PANEL SYSTEM

Manufacturer	Product	Finish / Color
Centria	Metalwrap 100 Series, 2" thick	Embossed Metallic - Coated Steel

E. SECTION 07 60 00, FLASHING AND SHEET METAL

Item / Manufacturer	Material	Finish
Roof Trim by Centria	Aluminum	Kynar - Medium Bronze
Hanging Gutters and Downspouts by Centria	Aluminum	Kynar - Zinc-Cote Premium Color

Rake and Fascia by Centria	Aluminum	Kynar - Zinc-Cote
Gravel Stops by Centria	Aluminum	Kynar - Medium Bronze

O. SECTION 07 61 16, BATTEN SEAM SHEET METAL ROOFING

Material	Finish/Color
High Seam Standing Seam Tee Panel by Centria	Kynar - Medium Bronze (SRI-32 or higher)
Polycarbonate Ice / Snow Cleats by Berger Brothers	RTCLSM - Clear Polycarbonate, SB190 Sealant.

Q. SECTION 07 71 00 / 07 72 00, ROOF SPECIALITIES AND ACCESSORIES

Item	Material	Finish	Manufacturer	Manufacturer/Color Name/Number.
Roof Expansion Joint Covers	Extruded Aluminum	Medium Bronze at Metal Roof	Bilco	Medium Bronze

R. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
MASONRY EXPANSION JOINTS	Grey to Match Mortar	3M	Verify
CMU CONTROL JOINTS	Grey to Match Mortar	3M	Verify
PRECAST CONCRETE PANELS	Grey to Match Mortar	3M	Verify
NEW TO EXISTING WALLS	Grey to Match Mortar	3M	Verify
BUILDING EXPANSION JOINTS	Grey to Match Mortar	3M	Verify
MASONRY SEALED JOINTS	Grey to Match Mortar	3M	Verify
STONE SEALED JOINTS	Grey to Match Mortar	3M	Verify

S. SECTION 07 95 13, EXPANSION JOINT COVER ASSEMBLIES

	Material	Finish	Manufacturer	Mfg. Color Name/No.
Floor Component Cover Plate Frame Casket or Sealant (interior only)	Floor/Floor SGR- Series	Aluminum (Clear anodized)/Floor finish	Construction Specialties	Aluminum (Clear Anodized)/Floor finish
Wall Component Cover Plate Frame Casket or Sealant (interior only)	Floor/Floor GFR- Series	Aluminum (Clear anodized)/Floor finish	Construction Specialties	Aluminum (Clear Anodized)/Floor finish
Ceiling Component Cover Plate, Gasket or Sealant (interior only)	FCF-Series	Extruded Seal	Construction Specialties	White
Exterior Wall Cover Plate Frame Thermoplastic Joint	KC-Series	Extruded Seal	Construction Specialties	Aluminum
Exterior Roof/Roof	Exterior Roof/Roof RJ-Series	Aluminum	Construction Specialties	Aluminum
Exterior Roof/Roof	Exterior Roof - SRJ Series	Aluminum	Construction Specialties	Aluminum
Exterior Wall/Roof	Exterior Wall/Roof - SRJW Series	Aluminum	Construction Specialties	Aluminum
Wall/Wall	Wall/Wall - SGW Series	Extruded Seal	Construction Specialties	White
Wall/Wall	Wall/Wall - FWF Series	Extruded Seal	Construction Specialties	White

2.8 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	Interior - P-7 Gloss Level 5 Exterior - To match Limestone Color
Frame	Interior - P-7 Gloss Level 5 Exterior - To match Limestone Color
Window frame	P-7 Gloss Level 5

B. SECTION 08 14 00, WOOD DOORS

Component	Manufacturer	Finish/Color
Doors	Marshfield	Please Pre-Finished TRE-6 Finish on White Oak

C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Paint to Match Adjacent Surface.
Stainless steel	

D. SECTION 08 41 13, ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

Material	Finish	Manufacturer	Series
Aluminum	Clear Anodized	EFCO	Series 406 2" x 6-1/2"
Aluminum Sunshades	Clear Anodized	EFCO	E-Shade (36" x 6" x Length.
Aluminum Rotating Vent	Clear Anodized	EFCO`	Series 700, 4" roto-vent.

E. WINDOW STOOLS

Manufacturer	Material	Finish / Color
Corian	Solid Surface	S-1 - Witch Hazel

U. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges		Exterior : 626 or 630 Interior: 652
Door Closers		689
Closer/ Holder		689
Door Holders		689
Lock/ Latches		630
Armor Plates	Metal	630
Kick Mop Plates	Metal	630
Door Edging		630
Exit Device		626
Flush Bolts		626
Door Pulls		630
Push Plates		630
Combination Push Pull Plate		630

Coordinators		600
Weather Strip		628
Threshold		628

V. SECTION 08 71 13, AUTOMATIC DOOR OPERATORS

Manufacturer	Type / Model	Mfg. Color
Stanley	Dura-Storm Hurricane Impact Door 3000 S	Clear Anodized

W. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
GL-1	Old Castle Glass	¼" Vision Glass, clear, tempered
GL-2	Old Castle Glass	¼" Clear Laminated
GL-3	Old Castle Glass	¼" one-way mirror glass, laminated
GL-4	Old Castle Glass	Sun Glass 1" Laminated/Tempered, Solar Control Low "E", Insulated Glass
GL-5	Old Castle Glass	¼" laminated to match color of GL-4
GL-6	Old Castle Glass	¼" Laminated Fire Glass

X. SECTION 08 90 00, LOUVERS AND VENTS

Manufacturer	Model No.	Material	Finish / or
C/S Group Louvers	PC-5304	AA	AA
Hohmann & Bernard Brick Bent	CA-847	AA	AA

2.9 DIVISION 09 - FINISHES

A. SECTION 09 01 90, CONCRETE COATINGS

Manufacturer	Product	Color
Thoro	Thorocoat	To be determined

B. SECTION 09 30 13, PORCELAIN CERAMIC TILING

1. SECTION 09 30 13, PORCELAIN CERAMIC TILE		
Finish Code	Manufacturer	Mfg. Color Name/No
PT	DalTile	12" x 12" Continental Slate Egyptian Beige C550

2. SECTION 09 30 13, PORCELAIN TILE GROUT		
Finish Code	Manufacturer	Mfg. Color Name/No.
G	Laticrete	17 Marble Beige

3. SECTION 09 30 13, PORCELAIN PAVER TILE GROUT		
Finish Code	Manufacturer	Mfg. Color Name/No.
P&G	Laticrete	61 Parchment

4. SECTION 09 30 13, MARBLE THRESHOLDS		
Marble Type	Manufacturer	Mfg. Color Name/No.
		To be determined

5. SECTION 09 30 13, METAL DIVIDER STRIPS		
Size	Material	Manufacturer
As Required	Stainless Steel	Schluter

B. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
AT-1	Type III	White Beveled Tegular 2 x 2	Armstrong	589 Cirrus with 9/16" Superfine 2 x 2 Grid (White)

C. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
VCT	12 x 12	VCT	Armstrong	Imperial Texture 51850 Standard Excelon - Sandrift White
LVT	18 x 18	LVT	Armstrong	Natural Creations Earth Cuts Pompeian Stone Venuvius TP534
LVP	4 x 36	LVP	Armstrong	Natural Creations Arbor Art TPO35

D. SECTION 09 65 16, **WELDED SHEET FLOORING (WSF)**

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
WSF	Medintone	Armstrong	H8312 Natural

1. SECTION 09 68 00, CARPET EDGE STRIP			
Finish Code	Material	Manufacturer	Mfg. Color Name/No.
Carpet Ro Resilient	Rubber	Johnsonite	Slim Line Transition SLT - XX C 280 Shoreline.

2. SECTION 09 68 00, BASE		
Material	Manufacturer	Mfg. Color Name/No.
4" Rubber Cove Base	Johnsonite 4" Rubber Cover Base	280 Shoreline
4" Rubber Profile Base	Johnsonite 4" Millwork	Siloutte MW-XX-J Lok Light Oak WB

E. SECTION 09 68 00, CARPET TILE (CPT)

Finish Code	Size	Pattern direction	Manufacturer	Mfg. Color Name/No.
CPT	24" x 24"	BRICK ASHLAR	Lee's Contract	DESIGN FRAME 346 ARTIFACT

F. SECTION 09 67 23, EPOXY RESINOUS FLOORING (ERF)

Finish code	Manufacturer	Mfg. Color Name/No.
ERF	DESCO	Trowel on Quartz Cremona Semes Color DB-311

T. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-a velvet-like finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P-1	4	Sherwin Williams	SW6149 Relaxed Khaki
P-2	4	Sherwin Williams	SW6198 Sensible Hue
P-3	4	Sherwin Williams	SW7702 Spiced Cider
P-4	4	Sherwin Williams	SW6128 Blonde
P-5	4	Sherwin Williams	SW7733 Bamboo Shoot
P-6	4	Sherwin Williams	SW6221 Moody Blue
P-7	5	Sherwin Williams	SW6151 Quiver Tan
P-8	4	Sherwin Williams	SW7006 Extra White

2.10 DIVISION 10 - SPECIALTIES

A. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards	Vinyl	Inpro Corporation	150 Hight Impact Corner Guard / Color - Pyramid 0275
Wall Guards and Handrail	Vinyl	Inpro Corporation	1200 Handrail / Color - Pyramid 0275

B. SECTION 10 28 00 / 10 14 00 / 11 17 36, MISCELLANEOUS SPECIALITIES

Item	Finish	Manufacturer	Mfg. Color Name/No.
Mop racks	SS	Bobrick	B-224 x 36

C. SECTION 10 14 00, EXTERIOR SIGNS

Component	Finish	Manufacturer	Mfg. Color Name/No.
Per VHSO	Per VHSO	Per VHSO	Per VHSO

D. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS

Sign Type	Component	Manufacturer	Mfg. Color Name/No.
Per VHSO	Per VHSO	Per VHSO	Per VHSO

E. SECTION 10 21 16, PREFABRICATED TOILET, SHOWER AND DRESSING COMPARTMENTS

Room No and Name	Material	Manufacturer	Manufacturer Color Name / No
Men's Locker Room 118	Solid Plastic	Scranton Products - Hinyhider	Parchment
Women's Locker Room 119	Solid Plastic	Scranton Products - Hinyhider	Parchment

F. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
Refer to Specifications	Stainless Steel	Bobrick	Refer to Specifications

G. SECTION 10 51 13, LOCKERS

Locker Type	Material	Manufacturer	Mfg. Color Name/No.
2 Tier 12" x 12" x 36" Vented	Painted Steel	Republic	TBD

H. SECTION 10 99 00, MISCELLANEOUS SPECIALTIES

Item	Material	Manufacturer	Mfg. Color Name/No.
Outdoor Basketball Goal	Galvanized Steel Pole / Steel Painted Backboard	Spalding	White / OP1B
Bicycle Rack	Galvanized Steel	Ribbon Rack	Galvanized / RB-09

2.11 DIVISION II - EQUIPMENT

2.13 DIVISION 13 - SPECIAL CONSTRUCTION

2.14 DIVISION 14 - CONVEYANCES

2.15 DIVISION 22 - PLUMBING

2.16 DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

A. SECTION 23 38 16 - COMMERCIAL KITCHEN HOODS

Item	Material	Manufacturer	Mfg. Color Name/No.
Refer to Specifications	Type 304 stainless steel with a #3 finish	CaptiveAire, model # ND-2-PSP-FB	Refer to Specifications

--	--	--	--

2.17 DIVISON 26 - ELECTRICAL

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Access Flooring	AF
Accordion Folding Partition	AFP
Acoustical Ceiling	AT
Acoustical Ceiling, Special Faced	AT (SP)
Acoustical Metal Pan Ceiling	AMP
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Concrete	C
Concrete Masonry Unit	CMU
Divider Strips Marble	DS MB
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E

Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Grout	G
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Material	MAT
Mortar	M
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	LAM
Porcelain Ceramic Tile	PT

Porcelain Tile Grout	PTG
Profile Rubber Base	PRB
Radiant Ceiling Panel System	RCP
Resinous Flooring	RES
Rubber Base	RB
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC
Suspension Decorative Grids	SDG
Solid Surface	S
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC

Veneer Plaster	VP
Vinyl Base	VB
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD
Porcelan Tile	PT
Luxury Vinyl Tile	LVT
Luxury Vinyl Plank	LVP
Corner Guard	CG
Handrail	HR

3.2 FINISH SCHEDULE SYMBOLS

Symbol Definition

- ** Same finish as adjoining walls
- No color required
- E Existing
- XX To match existing
- EFTR Existing finish to remain
- RM Remove

--- E N D ---