

**SECTION 10 11 23**  
**TACKBOARDS**

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

- A. This section specifies tackboards (bulletin boards) and glass door bulletin boards and related items.
- B. Boards may be either factory or field assembled.
- C. Where shown, assemble both chalkboards and tackboards into a single unit.

**1.2 RELATED WORK**

Color of aluminum anodic coating tackboard: Section 09 06 00, SCHEDULE FOR FINISHES

**1.3 QUALITY ASSURANCE**

Boards shall be the products of one manufacturer.

**1.4 SUBMITTALS**

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.
- B. Shop Drawings: Identifying all parts by name and material and showing design, construction, installation, anchorage and relation to adjacent construction.
- C. Manufacturer's Literature and Data:
  - 1. Bulletin board.
- D. Samples:
  - 1. Tackboard, 300 by 300 mm (six by six inches), each color, mounted on backing.
  - 2. Integrally colored anodized aluminum, 300 mm (six inch) length.
  - 3. Cork filled map rail, 300 mm (six inch) length.
  - 4. Each accessory (after approval, may be used in the work).

**1.5 APPLICABLE PUBLICATIONS**

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. National Association of Architectural Metal Manufacturers (NAAMM):
  - AMP 500 Series.....Metal Finishes Manual
  - AMP 501.....Finishes for Aluminum
- C. American National Standards (ANSI):

Z97.1-04.....Safety Glazing Materials Used in Buildings -  
Safety Performance Specifications and Methods  
of Test

D. American Society for Testing and Materials (ASTM):

B221/B221M-06.....Aluminum and Aluminum Alloy Extruded Bars,  
Rods, Wire, Shapes and Tubes

C1036-06.....Flat Glass

C1048-04.....Heat-Treated Flat Glass-Kind HS, Kind FT Coated  
and Uncoated Glass

F104-03.....Nonmetallic Gasket Materials

E. Composite Panel Association (CPA):

A208.1-06.....Particleboard

A135.4-04.....Basic Hardboard

## **PART 2 - PRODUCTS**

### **2.1 BULLETIN BOARD**

Bulletin board shall consist of a tackboard, snap on aluminum frame,  
grounds and other items specified and shown.

### **2.2 FABRICATION**

A. Materials:

1. Aluminum, extruded: ASTM B221.
2. Cork: ASTM F104, Type II, mildew resistant, Class 2.
3. Backing: Hardboard, AHBA A135.4 or particleboard, CPA A208.1.

B. Components:

1. Tackboard: Cork face, 6 mm (1/4-inch) thick factory laminated to a hardboard or particleboard backing of thickness required so that the face of the cork will be in the same plane as the face of the chalkboard writing surface, 6 mm to 9 mm (1/4 to 3/8-inch) thick.
2. Frames (Trim): Extruded aluminum, 1.5 mm (0.060-inch) thick, snap-on type, approximate face width 44 mm (1-3/4 inch), depth and configuration as required to return to wall and engage clips.

C. Bulletin boards 3660 mm (12 feet) or less in length shall be in one piece.

D. Finish exposed aluminum surfaces as follows:

1. AA 45 chemically etched medium matte, with clear anodic coating Class II Architectural, 0.4 mils thick (AA-M12C22A32).
2. AA 45 chemically etched medium matte, with integrally colored anodic coating, Class II Architectural, 0.4 mils thick (AA-M12C22A32, of color to match approved sample).

## **PART 3 - EXECUTION**

### **3.1 INSTALLATION, GENERAL**

- A. Install units in accordance with the manufacturer's installation instructions, use concealed fasteners.
- B. Inspect surfaces and related construction to receive units. Partitions shall have reinforcing to receive fasteners. Verify type and placement of reinforcement.
- C. Do not proceed with the installation until reinforcement is in place and surfaces are flat.
- D. Assemble units as specified by the manufacturer.

### **3.2 INSTALLATION OF BULLETIN BOARD:**

- A. Bulletin Boards:
  - 1. Mount bulletin boards with adhesive and blocking pads spaced 16 inches on center each way.
  - 2. Miter trim at corners, conceal fasteners. Modify trim as required to conform to surrounding construction details.

- - - E N D - - -