

SECTION 12 48 16
ENTRANCE GRILLES

PART 1 - GENERAL

1.1 DESCRIPTION

Provide entrance grilles where indicated.

1.2 SUBMITTALS

- A. In accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, furnish the following:
- B. Manufacturers' Literature and Data: Showing details of construction and hardware for entrance grilles.

PART 2 - PRODUCTS

2.1 MATERIALS

Entrance and Floor Mats must be the industrial type, rubber-tire fabric mats that have uniform-size links a minimum of 5/8 inch thick, and made from recycled selected truck and bus tires. Links must be woven in a herringbone design on galvanized spring-steel wire. Mats must have approximately 2 inch wide beveled nosing for surface use.

PART 3 - EXECUTION

3.1 INSTALLATION

Install entrance mats according to manufacturer's instructions after painting and finishing operations are complete.

- - - E N D - - -