FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL	CEILING	CEILING HEIGHT	AREA	NOTES
101	ENTRY VESTIBULE	WOM	NA	GWB	GWB	10'-0"	C	
102	WAIT	LVP	PRB	GWB-W	AT	10'-0"	C	
103	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
104	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
105	ADMIN	CPT	RB	GWB	AT	9'-4"	C	6
106	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
107	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
108	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
109	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
110	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
111	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
112	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
113	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	C	3
114	EVIDENCE	VCT	RB	GWB	AT	9'-0"	C	
115	WEAPONS	VCT	RB	GWB	AT	9'-0"	C	
116	OFFICE	CPT	RB	GWB	AT	9'-0"	C	6
117	MEETING RM/TRAINING	LVP	PRB	GWB	AT	10'-0"	C	
118	MEN LOCKER/ TOILET	ERF	ERF	PT	GWB (SC)	9'-0"	C	1, 5 ,7
119	WOMEN LOCKER/ TOILET	ERF	ERF	PT	GWB (SC)	9'-0"	C	1, 5, 7
120	VISITOR	ERF	ERF	PT	AT	10'-0"	C	1, 5 ,7
121	STAFF MEN	ERF	ERF	PT	AT	10'-0"	C	1, 5 ,7
122	STAFF WOMEN	ERF	ERF	PT	AT	10'-0"	C	1, 5, 7
123	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	C	3
124	ELECT.	SC	RB	GWB	EXP	-	C	
125	STORAGE	VCT	RB	GWB	AT	9'-0"	C	
126	OBSERVATION	VCT	RB	GWB	AT	9'-0"	C	
127	TOILET	ERF	ERF	PT	AT	10'-0"	C	1, 5, 7
128	EXAM	LVP	PRB	GWB	AT	10'-0"	C	
129	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	C	
130	PHARMACY	VCT	RB	GWB	AT	10'-0"	C	
131	MED ROOM	VCT	RB	GWB	AT	10'-0"	C	
132	EXAM	LVP	PRB	GWB	AT	10'-0"	C	
133	NURSE	LVP	PRB	GWB	AT	10'-0"	C	2
133A	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	C	
134	OFFICE	CPT	RB	GWB	AT	9'-4"	C	6
135	CORRIDOR	LVP/LVT	PRB	GWB	AT	10'-0"	B	3
135A	COURTYARD	NA	NA	NA	NA	-	B	
136	OUTPATIENT DAYROOM 2	LVP	PRB	GWB	AT	10'-0"	B	
136A	STORAGE	VCT	RB	GWB	GWB	9'-0"	B	
137	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	3
137A	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	3
138	AIDS LINEN	WSF	WSF	GWB(SC)	AT(SP)	9'-0"	B	
139	RECYCLE	WSF	RB	GWB	AT	9'-0"	B	
140	TRASH	WSF	RB	GWB	AT	9'-0"	B	
141	DIRTY UTLITY	VCT	RB	GWB	AT	9'-0"	B	
142	BREAK ROOM	LVP	RB	GWB	AT	9'-0"	B	
143	PHYSICAL THERAPY	LVP	PRB	GWB	AT	10'-0"	B	
143A	STOR	VCT	RB	GWB	GWB	9'-0"	B	
144	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	3
145	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	3
146	MECH.	SC	RB	GWB	EXP	-	B	
147	ELECT.	SC	RB	GWB	EXP	-	B	
148	DATA/ TELE	SC	RB	GWB	EXP	-	B	
149	MECH.	SC	RB	GWB	EXP	-	B	
150	RECREATIONAL THERAPY	LVP	PRB	GWB-W	AT	10'-0"	B	
151	REC. THERAPY OFFICE	CPT	RB	GWB	AT	10'-0"	B	6
152	R.T. STORAGE	VCT	RB	GWB	AT	10'-0"	B	
153	DAYROOM 1	LVP	PRB	GWB	AT	10'-8"	B	
153A	DAYRM KIT.	LVP	PRB	GWB	AT	10'-8"	B	
154	LAUNDRY	WSF	WSF	GWB	AT	10'-0"	B	
155	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	
155A	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	
156	VENDING	VCT	RB	GWB	AT	10'-0"	B	
157	CLEAN LINEN	WSF	WSF	GWB(SC)	AT(SP)	9'-0"	B	
158	JANITOR	WSF	WSF	GWB(SC)	AT(SP)	9'-0"	B	
159	CORR	LVP	PRB	GWB	AT	10'-0"	B	
159A	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	
160	FEMALE	LVP	PRB	GWB	AT	10'-0"	B	
161	MEN	ERF	ERF	PT	AT	10'-0"	B	1, 5 ,7

FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL	CEILING	CEILING HEIGHT	AREA	NOTES
162	WOMEN	ERF	ERF	PT	AT	10'-0"	B	1, 5 ,7
163	OCCUPATIONAL	LVP	PRB	GWB	AT	10'-0"	B	
163A	STORAGE	VCT	RB	GWB	AT	10'-0"	B	
164	JOB DEVELOPMENT	LVP	PRB	GWB	AT	10'-0"	B	
164A	STORAGE	VCT	RB	GWB	AT	10'-0"	B	
165	IN-PATIENT GRP ACT. RM	LVP	PRB	GWB	AT	10'-8"	B	
166	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	B	
167	GROUP	LVP	PRB	GWB	AT	10'-0"	B	
167A	STOR	VCT	RB	GWB	GWB	10'-0"	B	
168	QUIET ROOM	CPT	RB	GWB-W	AT	10'-0"	B	6
169	COMPUTER ROOM	LVP	PRB	GWB	AT	10'-0"	B	
170	CORR	LVP	PRB	GWB	AT	10'-0"	A	
170A	RESIDENT SUITE	LVP	PRB	GWB	AT	10'-0"	A	
171	BATH	ERF	ERF	PT	GWB (SC)	9'-0"	A	1, 5, 7
172	KITCHEN	LVP	PRB	GWB	AT	9'-0"	A	
173	EXERCISE	LVP	PRB	GWB	AT	10'-0"	A	
175	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
175A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
176	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
176A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
177	CORRIDOR	LVP/LVT	PRB	GWB	AT	10'-0"	A	2, 3
177A	COVERED PORCH	MED. BROOM FIN. CONC.	NA	BRICK	PREFIN. MTL.	10'-10"	A	
178	MECHANICAL	SC	RB	GWB	EXP	-	A	
179	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	
179A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
180	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
180A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5 ,7
181	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
181A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
182	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
182A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
183	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
183A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
184	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
184A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
185	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
185A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
186	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
186A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
187	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
187A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
188	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
188A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
189	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
189A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
190	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
190A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
191	CORRIDOR	LVP	PRB	GWB	AT	10'-0"	A	
192	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
192A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
193	PRIVATE BED	SC	PRB	GWB	GWB	9'-4"	A	2
193A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
194	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
194A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
195	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
195A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
196	PRIVATE BED	LVP	PRB	GWB	GWB	9'-4"	A	2
196A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
197	PRIVATE BED BARIATRIC	LVP	PRB	GWB	GWB	9'-4"	A	2
197A	BATH	ERF	ERF	PT	GWB	9'-0"	A	1, 5, 7
198	ELECT.	SC	RB	GWB	EXP	-	A	
199	JANITOR	WSF	WSF	GWB(SC)	AT(SP)	9'-0"	A	
200	LUGGAGE	VCT	RB	GWB	AT	9'-0"	A	
201	CLEAN LINEN	WSF	WSF	GWB(SC)	AT(SP)	9'-0"	A	

FINISH SCHEDULE

1. PORCELAIN TILE TO EXTEND TO CEILING.
2. SEE AE109 FOR ACCENTWALL LOCATIONS.
3. PROVIDE RUBBER WALL GUARDS AND CORNER GUARDS.
4. NOT USED
5. PROVIDE RESINOUS FLOORING IN ALL SHOWER / TOILET AREAS.
6. CARPET TO BE LAID MONOLITHIC.
7. PORCELAIN TILE ON CONCRETE BACKER BOARD.

FINISH LEGEND

WOM = WALK OFF MAT
LVP = LUXURY VINYL PLANK
CPT = CARPET TILE
VCT = VINYL COMPOSITION TILE
ERF = EPOXY RESIN FLOORING
WSF = WELDED SHEET VINYL FLOORING
SC = SEALED CONCRETE
PT = PORCELAIN CERAMIC TILE
RB = RUBBER BASE
PRB = PROFILE RUBBER BASE
GWB(SC)= GYPSUM WALL BOARD WITH HIGH GLAZED COATING
GWB = GYPSUM WALL BOARD
AT = ACOUSTICAL TILE CEILING
AT – SP = ACOUSTICAL TILE CEILING – SPECIAL FACED

FULLY SPRINKLERED
100% CONSTRUCTION DOCUMENTS

Revisions:	Date

CONSULTANTS:

09/07/2012

TAGGART ARCHITECTS REGISTERED ARCHITECTS License Number 04230 STATE OF TEXAS

ARCHITECT / ENGINEERS:

TAGGART ARCHITECTS

4500 Burrow Drive
North Little Rock, AR 72116
Phone: 501-758-7443
Fax: 501-753-7309
www.taggarch.com

Drawing Title: FINISH SCHEDULE

Approved: Project Director

Project Title: **Renovate Leroy Pond Army Reserve Center for Mental Health Residential Rehabilitation Treatment/ Police Training**

Location: **Fayetteville, AR**

Date: 9/7/12 | Checked: SG | Drawn: ACH

Project Number: **564-341**

Building Number:

Drawing Number: AE601

Dwg. 80 of 126

Office of Facilities Management

DEPARTMENT OF VETERANS AFFAIRS

VA FORM 08-6231, OCT 1978