



LEGEND:

- COURTYARD, 6" REINFORCED COLORED CONCRETE WITH BRICK SOLIDER COURSE EDGING. (SEE DETAIL 5/LS102). #4 REBAR AT 24" SPACING. (COORDINATE WITH CIVIL/GRADING SHEETS). CROSS CHECK ALL CIVIL DRAWING TYPES AND DIMENSIONS)
- CONCRETE CURB EDGER, TYPICAL. (SEE DETAIL 5-LS101)
- 8" FENCE. (SEE DETAILS 4-LS101, 5-LS101 AND 6-LS101)
- GATE FOR MOWER ACCESS. (SEE DETAIL 4-LS102)
- BRICK VENEERED COLUMN, TYPICAL. (SEE DETAIL 6-LS101)
- RAINWATER BASIN WITH STORM WATER INLET, TYPICAL TO BE LEFT UNDISTURBED.
- Area has existing sprinklers, 3 ft clearance has been left around the transformer for fence. Contractor must locate and repair any damaged sprinklers and grass.
- EXISTING 6" REINFORCED COLORED CONCRETE, #4 REBAR AT 24" SPACING ON CENTER
- 1" concrete edge on building see detail 1 page LS101. Special down spool diverters see detail page LS101. Don't demo any existing concrete or rebar. If existing concrete is damaged, repair to match existing. If existing concrete is damaged, repair to match existing. If existing concrete is damaged, repair to match existing.
- N/A
- BUILDING SIGN, (SEE DETAIL 4-LS102)
- ADA ACCESS, (COORDINATE WITH CIVIL/GRADING SHEETS)
- N/A
- ELECTRICAL TRANSFORMER FENCE SCREENING WITH GATE. (SEE DETAIL 1-LS102)
- 4" STANDARD SIDEWALK. (COORDINATE WITH CIVIL/GRADING SHEETS)
- "FLAT" CONCRETE CURB TO FACILITATE DRAINAGE INTO WATER GARDENS. (SEE DETAIL 3-LS101) TO BE LEFT UNDISTURBED.



CALL BEFORE YOU DIG  
ONE-CALL OF WYOMING  
1-800-440-2476  
811  
STATE AGENCY OFFICE OF PUBLIC

CONSULTANTS:

ARCHITECT/ENGINEERS:

Drawing Title  
Landscape Site Plan

Project Title  
SHERIDAN VAMC LANDSCAPING  
FOR BUILDING 87

Approved Project Director

Location  
Sheridan, Wyoming

Date  
9 / 14 / 2014

Checked  
CLC

Drawing Number  
LS100  
Dwg 9 of 16

Office of  
Construction  
and Facilities  
Management

