



BLANK MEMORIAL WALL MARKER



PROFILE



		GENERAL NOTES FOR MARBLE AND GRANITE MEMORIAL WALL MARKERS: 1. SMALL CAPITAL LETTERS WILL BE USED FOR ANY LETTER IN THE INSCRIPTION SHOWN IN LOWER CASE. 2. APPLY BLACK LITHICHROME TO ALL INSCRIBED AREAS IN GRANITE. UNLESS INSTRUCTED OTHERWISE, DO NOT APPLY LITHICHROME TO INSCRIPTIONS IN MARBLE. 3. CHARACTERS SMALLER THAN L-5 ARE NOT AUTHORIZED. 4. INSCRIBED LINES MUST BE HORIZONTALLY CENTERED. 5. WHEN TWO EMBLEMS OF BELIEF ARE REQUIRED, THE VETERAN'S EMBLEM IS PLACED ON THE LEFT AND DEPENDENT EMBLEMS TO THE RIGHT. 6. PROVIDE SMOOTH 1/8" ROUNDED EDGES ALONG BOTH FRONT AND BACKSIDES. ROUNDING MUST BE CONSISTENT. 7. PROVIDE CONSISTENT, HONED, 80 GRIT FINISH ON ALL SIX SIDES. 8. DEFLECTION FROM TRUE PLANE MUST BE LESS THAN 1/32". 9. DO NOT INSCRIBE WITHIN 1/2" MARGIN FROM EITHER SIDES OR TOP. 10. EMBLEMS MUST BE TWO (2) INCHES FROM LARGEST POINT TO POINT MEASUREMENT INCLUSIVE OF ANY SURROUNDING CIRCLES. 11. TOLERANCE FOR LENGTH, WIDTH, AND THICKNESS IS +/- 1/32". 12. SURNAME LINE WITH 5/8" (L7) INSCRIPTIONS IS GENERALLY LIMITED TO NOT MORE THAN 15 CHARACTERS AND SPACES. 13. LINES WITH 7/16" (L5) INSCRIPTIONS ARE GENERALLY LIMITED TO NOT MORE THAN 25 CHARACTERS AND SPACES.		 <div>NATIONAL CEMETERY ADMINISTRATION</div>		<div>Drawing Title MEMORIAL WALL MARKER</div> <div>Approved: Director, Memorial Programs Service Signed</div> <div>Approved: Chief of Operations, Memorial Programs Service Signed</div>		<div>Project Title GOVERNMENT HEADSTONES AND MARKERS</div> <div>Marker Type: A1 (marble) C1 (granite)</div> <div>Checked KEE/KS</div> <div>Drawn MLT SYSTEMS</div> <div>Location Digital File A-MW-1.DWG 24" x 36" SHEET</div>		<div>Date JULY 2, 2013</div> <div>Project No.</div> <div>DRAWING NO. A-MW-1</div> <div>Sheet 1 Of 3</div>	
A		ADDS THIRD SHEET FOR BLANK MARKER, REARRANGE SHEET NUMBER ORDER, UPDATED DIMENSIONS/FINISHES/DEFLECTION		7-2-13							
Revisions				Date							