LEGEND

SYMBOL	DESCRIPTION
℄	CENTERLINE FOR HORIZONTAL LAYOUT
	SECTION SETBACK LINE (VARIES)
	LIMIT OF CONSTRUCTION
	FENCE
	METAL LANDSCAPE EDGING
	GRAVESITE GRID CONTROL MARKERS (42' X 80' GRID. TYP.)
	SECTION MARKER
83	COORDINATE POINT – REFER TO SHEET L–204 FOR COORDINATE TABLE.
	GRAVEL MULCH WITH WEED CONTROL FABRIC UNDERLAYMENT
	GRAVEL MULCH TOPDRESSING OVER GRAVEL BASE – ACCESS PATH

CUL-DE-SAC (TEMPORARY):

- BASE BID: AGGREGATE ROAD PAVING -18" DEPTH
- ADD. ALT. #1: ASPHALT PAVING WITH CURBS AND CENTER CIRCLE LANDSCAPING

CRYPT DEVELOPMENT SUMMARY:

SECTION 21
REGULAR (DOUBLE-DEPTH) CRYPTS: 3,370
PERIMETER (DOUBLE DEPTH) CRYPTS: 630
TOTAL BURIAL SITES: 4,000

TOTAL CRYPTS INSTALLED FOR PROJECT: 4,000

SITE LEGEND

KEY	SITE ELEMENT	DETAIL REFERENCE
A	Lawn Crypts – Regular 3' x 8' Plot	F5/500
B	Lawn Crypts – Perimeter Crypt – 3' x 8'	F5/500
C	10' Wide Access Path – 3" Gravel Mulch Topdressing, 9" Crushed Gravel Subbase with Fines	
D	Gravesite Control Marker Monument	D5/500
E	Section Marker	F8/500
F	Watering Station	B1/500
G	Gravel Mulch – Depth 3" – With Weed Control Fabric Underlayment	
H	Fence to Match Existing (Wood Post and Barbed Wire)	
I	Metal Landscape Edging at Turf Edge	B2/600
J	10' Wide Access Path – 3" Gravel Top Dressing, 9" Gravel Base from Existing Stockpiled Gravel Removed from this Area. See Sheet D–1, Note F.	E6/600
K	Irrigation Aisle, Typ.	
L	Access Road – 3" AC/14" AB – See Plan/Profile Sheet L–400	C1/500
M	Curb & Gutter	A1/500
N	Curb & Gutter – Reverse Gutter Pan	A1/500
O	Curb Cut – 4' Wide Transition from Curb & Gutter to Reverse Gutter Pan in 5 feet.	F1/500
P		
Q	Aggregate Road Paving – 18" Depth (Base Bid) in Cul–de–Sac (Temporary)	E1/500
R	Vee Gutter with 5' Transition Each Side	A1/500
S	Riprap	F1/500

ENLARGEMENT PLAN OF
ADD-ALTERNATE #1
CUL-DE-SAC (TEMPORARY)

SECTION 21

SECTION 20

GRAVESITE ORIENTATION

TRES CERRITOS BOULEVARD

SOUTH LOOP ROAD

FUTURE ROADWAY PER MASTER PLAN

ADD. ALTERNATE #1 LIMITS – SEE ENLARGEMENT PLAN THIS SHEET

END/CONNECT TO EXISTING

SECTION SETBACK

LIMIT OF CONSTRUCTION

MATCH EXISTING

MATCH EXIST.

END CURB

TOP

TOE

NORTH

0 20 40

GRAPHIC SCALE: 1" = 20'

CONSTRUCTION DOCUMENTS

CONSTRUCTION DOCUMENTS

Revisions:	Date

CONSULTANTS:

SURVEYOR
BLAIR, CHURCH, & FLYNN
451 CLOVIS AVENUE, SUITE 200
CLOVIS, CA 93612
(559) 326–1400 PHONE

GEOTECHNICAL ENGINEER
STEVENS, FERRONE, & BAILEY
1600 WILLOW PASS COURT
CONCORD, CA 94520
(925) 688–1001 PHONE

COST ESTIMATING
SIERRA WEST GROUP, LLC
9700 BUSINESS PARK DRIVE, SUITE 102
SACRAMENTO, CA 95827
(916) 925–4000 PHONE

LICENSED LANDSCAPE ARCHITECT
REBECCA MCNEIL FREEMAN
No. 4639
Signature
03/31/17
Renewal Date
Date
STATE OF CALIFORNIA

ARCHITECT/ENGINEERS:

JACOBS
Jacobs Engineering Group Inc.
Consultants in Architecture, Engineering, Planning, and the Environment
Sacramento Office
1050 20th Street, Suite 200
Sacramento, California 95811
(916) 929–3323 Fax (916) 929–1772

Drawing Title: SITE LAYOUT PLAN

Approved: Project Director

Project Title: SAN JOAQUIN VALLEY NATIONAL CEMETERY PRE-PLACED CRYPTS IN SECTION 21

Location: SAN JOAQUIN VALLEY NATIONAL CEMETERY SANTA NELLA, CALIFORNIA

Date: 09/28/2015 | Checked: MIS | Drawn: RJM

Project Number: 913CM3012

Building Number:

Drawing Number: L-200

Dwg. 8 of 25

NATIONAL CEMETERY ADMINISTRATION DESIGN AND CONSTRUCTION SERVICE

Department of Veterans Affairs

VA FORM 08–6231

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
SACTL03\Production\Projects\73980746 VA 1002 SJVNC Crypts\drawings\000000_LDPV_01-CD\08-LAYOUT.dwg 9-22-15 02:46:55 PM mcneilfreeman