

(Continuation of Item 3)

L. Controls: Factory **or Field**-Installed Fan Coil Open Controller: BACnet based communicating controller with pre-programmed control algorithms; including factory **or field**-installed 24-v transformer, relay board, supply air sensor, return air sensor and changeover sensor (as required). Provides automatic fan speed control based on demand. **Factory or Field-Installed controls and components shall be coordinated by the Contractor to ensure a complete and working system."**

4. Where ever appearing in the solicitation Bid Item 3 is corrected to read as follows:

BID ITEM 3 (Alternate Deduct 2):

Same as BID ITEM 1 (Base Bid), except DELETE all work as specified in BID ITEM 2 and DELETE all labors and materials associated with the demolition and new work in the north west wing of Building 31 First floor lab area. See sheets H1-07, H1-09, H2-07 and H2-09 for further clarification. If this is accepted, 31-AC2(DD) on sheet H1-09, and all associated terminal boxes and steam radiators shown on H1-07 (V-AC2D-x) will remain unchanged **and corresponding new air handler 31-AC5 shown on H2-09 and corresponding terminal boxes and steam radiators shown on H2-07 will not be provided or installed.** Refer to bid items noted on the drawings. Work to be completed within 420 calendar days after receipt of Notice to Proceed.

5. Where ever appearing in the solicitation Bid Item 4 is corrected to read as follows:

BID ITEM 4 (Alternate Deduct 3):

Same as BID ITEM 1 (Base Bid), except DELETE all work as specified in BID ITEM 2 and 3 and DELETE all labors and materials associated with the demolition and new work in the South west wing of Building 31 First floor lab areas and Basement floor. See sheets H1-06, H1-07, H1-09, H2-06, H2-07 and H2-09 for further clarification. If this is accepted, 31-AC1(DD) on sheet H1-09, and all associated terminal boxes and steam radiators shown on H1-06 and H1-07 (V-AC1D-x) will remain unchanged **and corresponding new air handler 31-AC4 shown on H2-09 and corresponding terminal boxes and steam radiators shown on H2-06 and H2-07 will not be provided or installed.** Refer to bid items noted on the drawings. Work to be completed within 420 calendar days after receipt of Notice to Proceed.

END OF AMENDMENT