

PROJECT DIRECTORY

ARCHITECT/ENGINEER:

CONTACT: DIANE GLARROW

DRAWING INDEX	
SHEET #	SHEET NAME
MECHANICAL	
H001	HVAC SYMBOLS, ABBREVIATIONS AND GENERAL NOTES
H100	HVAC BASEMENT, SITE AND CRAWLSPACE/BASEMENT OF BUILDING 364
H101A	FIRST FLOOR AREA 'A' - DUCTWORK PLAN
H101B	FIRST FLOOR AREA 'B' - DUCTWORK PLAN
H102A	FIRST FLOOR AREA 'A' - HVAC PIPING PLAN
H102B	FIRST FLOOR AREA 'B' - HVAC PIPING PLAN
H103	ATTIC - HVAC DUCTWORK AND PIPING
H201	ENLARGED HVAC PLANS
H301	FIRST FLOOR - HVAC SECTION CALLOUTS
H302	HVAC SECTIONS
H401	HVAC PIPING DIAGRAMS
H501	HVAC DETAILS
H502	HVAC DETAILS
H503	HVAC DETAILS
H504	HVAC DETAILS
H505	HVAC DETAILS
H506	HVAC DETAILS
H601	HVAC CONTROLS
H602	HVAC CONTROLS
H701	HVAC SCHEDULES
H702	HVAC SCHEDULES
ELECTRICAL	
E001	SCHEDULES, SYMBOLS & NOTES
E101A	FIRST FLOOR LIGHTING PLAN - AREA A
E101B	FIRST FLOOR LIGHTING PLAN - AREA B
E102A	FIRST FLOOR LIGHTING CONTROL PLAN - AREA A
E102B	FIRST FLOOR LIGHTING CONTROL PLAN - AREA B
E201A	FIRST FLOOR POWER PLAN - AREA A
E201B	FIRST FLOOR POWER PLAN - AREA B
E500	ELECTRICAL DETAILS
E501	LIGHTING DETAILS
E600	ELECTRICAL RISER DIAGRAMS
E700	ELECTRICAL SCHEDULES
E701	ELECTRICAL SCHEDULES
E800	GROUNDING DETAILS
E801	LIGHTNING PROTECTION PLAN
E900	ELECTRICAL SITE PLAN
E901	ELECTRICAL SITE DETAILS
FIRE ALARM	
EF001	FIRE ALARM SYMBOLS AND NOTES
EF201A	FIRST FLOOR FIRE ALARM PLAN - AREA A
EF201B	FIRST FLOOR FIRE ALARM PLAN - AREA B
EF202A	ATTIC FIRE ALARM PLAN - AREA A
EF202B	ATTIC FIRE ALARM PLAN - AREA B
SECURITY	
ES001	SECURITY SYMBOLS AND ABBREVIATIONS
ES201A	FIRST FLOOR SECURITY PLAN - AREA A
ES201B	FIRST FLOOR SECURITY PLAN - AREA B
TELECOMMUNICATIONS	
ET001	TELECOMMUNICATIONS SYMBOLS AND NOTES
ET201A	FIRST FLOOR SYSTEMS PLAN - AREA A
ET201B	FIRST FLOOR SYSTEMS PLAN - AREA B
ET500	TELECOMMUNICATION DETAILS

SITESITE

PROJECT NORTH

TRUE NORTH

FULLY SPRINKLERED
100% CONSTRUCTION DOCUMENTS

**Office of
Construction
and Facilities
Management**

Department of
Veterans Affairs

[illegible]

9



CONSULTANTS:



HOPE FURRER
Associates, Inc.



SITE RESOURCES
Comprehensive Land Planning & Site Design Services



leeandassociatesinc

AE Works Project Number: 12028

 Department of
Veterans Affairs



ALTERNATE #1
ELIMINATE ELEVATOR. FILL IN DOOR
OPENINGS WITH CONSTRUCTION TO MATCH
ADJACENT WALLS. BASEMENT AND
ELEVATOR SHAFT TO REMAIN.

ALTERNATE #2

DELETE 4 BATHROOMS

CONSTRUCT BASE BID BUILDING ENVELOPE W/ COMPACTED GRAVEL BASE.

INSULATE GYPSUM BATHROOM WALL, AS REQUIRED TO MAINTAIN R-VALUE.

PLUMBING DEDUCTIONS

FIXTURES - DO NOT INSTALL. (4) WATER CLOSETS, (4) LAVATORIES, (4) SHOWER UNITS, (4) FLOOR DRAINS W/ TRAP PIPINGS IN ROOMS B-06, B-07. PROVIDE ROUGH-INS FOR PLUMBING FIXTURES IN FLOOR SLAB.

SANITARY - 6" MAIN SANITARY LINE WILL REMAIN AS SHOWN IN ITS CURRENT LOCATION. BRANCH PIPING TO 4 BATHROOMS IN THIS WING WILL NOT BE INSTALLED.

VENT - DELETE BRANCH VENT PIPING ABOVE CEILING IN (4) BEDROOMS. VENT THRU ROOF TERMINALS WILL REMAIN IN THE LOCATIONS SHOWN.

DOMESTIC WATER SUPPLY PIPING - 2-1/2" COLD WATER - 1-1/4" HOT WATER AND 3/4" HOT WATER RADIANT WILL BE DOWNSIZED TO 2" COLD WATER - 1" HOT WATER AND 3/4" HOT WATER RETURN.

FIRE PROTECTION

DELETE APPROXIMATELY (33) UPRIGHT TYPE SPRINKLER HEADS IN LIEU OF SEMI-RECESSED TYPE SPRINKLER HEADS.

HVAC

DELETE VAV BOXES, 1-2 THRU 1-6 AND 1-7 THRU 1-11 AND ASSOCIATED SUPPLY DUCTWORK, SUPPLY DIFFUSERS, DUCT ACCESSORIES, HEATING HOT WATER PIPING AND THERMOSTATS.

DELETE 10 RETURN GRILLES AND ASSOCIATED RETURN DUCTWORK.

DELETE 4 EXHAUST GRILLES AND ASSOCIATED EXHAUST DUCTWORK.

DELETE 10 RADIANI PANELS AND ASSOCIATED PIPING.

CAP SUPPLY, RETURN AND EXHAUST DUCTS 5 FEET SOUTH OF BATHROOM B138 AND BATHROOM B153.

ADD (1) 300 CFM VAV BOX TO THE END OF THE SUPPLY DUCT.

ELECTRICAL

DELETE RECEPTACLES

DELETE LIGHT FIXTURES, ASSOCIATED LIGHT SWITCHES, EXIT SIGNS, AND OCCUPANCY SENSORS.

DELETE (2) WIRELESS ACCESS POINTS (WAP)

DELETE (2) FIRE ALARM SPEAKERS/STROBES, (1) WILL REMAIN IN SHELL SPACE.

DELETE SMOKE DETECTORS IN ROOMS

THE SECURITY CAMERA REMAINS

THE DOOR CONTACT AND LOCAL ALARM WILL REMAIN ON THE EXTERIOR DOOR.

FIRE ALARM PULL STATION WILL MOVE TO DOOR ENTERING SHELL SPACE.

PROVIDE (6) LED STRIP LIGHTS AND A LIGHT SWITCH FOR TEMPORARY LIGHTING OF THE SHELL SPACE.

ALTERNATE #3

ARCHITECTURAL REVISIONS
DELETE BEDROOM WING IN IT'S ENTIRETY.

CONSTRUCT NEW EXTERIOR WALL TO MATCH BUILDING ENVELOPE.

PLUMBING REVISIONS

1. FIXTURES - DO NOT PROVIDE AND: INSTALL (4) BATH CLOSETS (4) LAVATORIES (4) SHOWER UNITS (4) FLOOR DRAINS W/ TRAP PRIMERS IN ROOMS 5-10WING

2. SANITARY - 6" MAIN SANITARY LINE WILL EXIT BUILDING OUT OF THE CENTER OF THE CORRIDOR IN SIMILAR LOCATION. APPROXIMATELY 80' OF 6" CAST IRON SANITARY PIPING WILL NOT BE INSTALLED.

3. VENT - VENT TERMINAL WILL BE LOCATED IN BEDROOM B154 AND EXTENDED THRU THE ROOF IN THIS LOCATION. BRACH PIPING NOT INSTALLED.

4. DOMESTIC WATER SUPPLY PIPING - 2-1/2" COLD WATER - 1-1/4" HOT WATER AND 1/2" HOT WATER RETURN WILL NOT BE INSTALLED.

FIRE PROTECTION

1. DO NOT INSTALL (4) DRY SPRINKLER HEADS AND (33) SEMI RECESSED HEADS. SUBSEQUENT REVISION REQUIRED.

2. HVAC
YES/ASME AS DEDUCT #2 BUT DO NOT ADD NEW 300 CFM VAV BOX.

3. CAP SUPPLY, RETURN AND EXHAUST DUCTS 1 FOOT NORTH OF BATHROOM B138 AND BATHROOM B153'S SQUAT WALL.

ELECTRICAL


ALL ELECTRICAL AND SYSTEMS DEVICE ARE REMOVED.

THE DOOR CONTACT AND LOCAL ALARM REMAIN ON THE NEW EXTERIOR DOOR.

THE FIRE ALARM PULL STATION WILL BE MOVED TO THE NEW EXTERIOR DOOR.

THE SECURITY CAMERA REMAINS AND IS RELOCATED.

THE OUTSIDE GFI RECEPTACLE REMAINS AND IS RELOCATED.



**FULLY SPRINKLERED
100% CONSTRUCTION DOCUMENTS**

[illegible]

CONSULTANTS:



SEAL

ARCHITECTS/ENGINEERS:



6587 Hamilton Avenue
Pittsburgh, Pennsylvania 15206
Ph: 412.287.7333 Fax: 412.287.7333
www.ae-works.com

AE Works Project Number: 12028

Drawing Title	DEDUCT ALTERNATE OPTION
---------------	-------------------------

Approved: Project Director

Project Title:
Construct a New Residential
Rehabilitation Treatment Program
(RRTP) Building

Location: Perry Point VA Medical Center
Perry Point, MD 21902

Date:

Checked

Checked

Project Number
512-531

Building Number

Drawing Number

G003

**Office of
Construction
and Facilities
Management**

