



2	ROSETTES REMOVED AND ADDITIONAL DIMENSIONS	11-26-13
1	SIZE AND LOCATION OF PREDRILLED HOLES REVISED AS SHOWN	03-01-07
---	SUPERSEDES DRAWING NC-1 DATED 1 OCT 1995	6-5-03
Revisions	Date	

- GENERAL NOTES:**
- ALL DIMENSIONAL TOLERANCES FOR LENGTH, WIDTH, AND THICKNESS ARE $\pm 1/16"$ UNLESS OTHERWISE SPECIFIED.
 - DEFLECTION SHALL NOT BE GREATER THAN $\pm 1/32"$ ALONG EITHER THE BACK OR FACE.
 - SPAWLING (PUNCH OUT) AROUND HOLES AT BACK SIDE MUST NOT EXCEED MORE THAN $1/4"$ BEYOND WALLS OF BORING NOR BE MORE THAN $3/32"$ DEEP.

CONVERSION TABLE			
ENGLISH/ U.S. STANDARD	METRIC	ENGLISH/ U.S. STANDARD	METRIC
42"	106.68 cm	2"	5.08 cm
24"	60.96 cm	1 5/8"	4.13 cm
14 1/2"	36.83 cm	1"	2.54 cm
13"	33.02 cm	3/4"	1.90 cm
4"	10.16 cm	5/8"	1.59 cm
3"	7.62 cm	1/2"	1.27 cm
2 1/2"	6.35 cm	1/4"	.64 cm



NATIONAL
CEMETERY
ADMINISTRATION

Drawing Title NICHE COVER, BLANK MARBLE/GRANITE	Project Title GOVERNMENT HEADSTONES AND MARKERS	Date NOVEMBER 11, 2013
Approved: Director, Memorial Programs Service	Marker Type I1/H1	Checked KEE/KS
Signed	Drawn MLT SYSTEMS	DRAWING NO. A-BNC-1
Approved: Chief of Operations, Memorial Programs Service	Location	Sheet 1 of 1
Signed	Digital File A-BNC-1.DWG 24" x 36" SHEET	