



1. REFERENCE SCHEDULE "E" OF THE SFO PART II FINISH AND DOOR INFORMATION.
2. COORDINATE ALL WALL & FLOOR OUTLETS AND DATA/TELECOM PORTS WITH EQUIPMENT & FURNITURE LOCATIONS.
4. ALL CONSTRUCTION MUST COMPLY WITH ALL LOCAL BUILDING CODES.
5. PROVIDE WALL PROTECTION AS OUTLINED IN THE SFO PART I OR PROVIDE WALL PROTECTION AS REQUIRED.
6. PROVIDE FLOOR DRAINS IN ALL TOILET ROOMS.
7. PROVIDE FIRE EXTINGUISHER CABINETS AS REQUIRED BY CODE.
8. COORDINATE ALL BUILDING ENTRIES WITH SITE GRADE.
9. PROVIDE BACKING AND STRUCTURAL SUPPORT FOR ALL CEILING MOUNTED EQUIPMENT, WALL MOUNTED EQUIPMENT AND PASS-THROUGH BOXES WITH FINAL EQUIPMENT LIST BY OWNER.
10. PROVIDE LEAD-LINE OR RF SHIELDING IN PARTITIONS, DOORS, AND BORROW LIGHTS IN ROOMS WITH IMAGING EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS AND SHIELDING PHYSICIST'S REPORT.

- 1 BARIATRIC TOILETS
- 2 COILING SECURITY DOOR (FROM CEILING TO COUNTERTOP).
- 3 SYSTEMS FURNITURE. COORD. DATA & POWER REQUIREMENTS.
- 4 CURTAIN & TRACK @ CEILING ABOVE. TYP
- 5 CEILING HUNG STAINLESS STEEL TOILET PARTITION.
- 6 PREFINISHED ALUMINUM STOREFRONT W/ CLEAR GLASS AND CAPTURED VERTICAL MULLIONS.
- 7 BUILT-IN CUSTOM CASEWORK
- 8 BABY CHANGING STATION.
- 9 LINE OF CLERESTORY WINDOW ABOVE.
- 10 PREFINISHED ALUMINUM STOREFRONT W/ CLEAR BUTT GLAZING. PROVIDE GLASS WITH FRIT PATTERN.
- 11 LOCKERS
- 12 ACOUSTICAL PERFORMATED PANELS.
- 13 FREE-FORM BENCH.
- 14 DOCK LEVELER.
- 15 DOCK BUMPER.
- 16 CUSTOM MILLWORK - REGISTRATION/ PHARMACY STATION W/ PRIVACY PANELS.
- 17 CUSTOM MILLWORK - INFORMATION DESK.
- 18 CUSTOM MILLWORK - SHELVEYING.
- 19 ACOUSTICAL WOOD PANEL SYSTEM (LAYERED DESIGN).
- 20 LOCKABLE, PASS-THRU WINDOW
- 21 PROVIDE PLUMBING ROUGH-IN FOR FUTURE SINK INSTALLATION

	2 HR FIRE RATED FIRE-BARRIER
	1 HR FIRE RATED FIRE-BARRIER
	SHIELDED WALL
	FLOOR DRAIN
	ELECT. DUPLEX
	ELECT. DUPLEX, G.F.I.
	ELECT. QUADRUPLUX
	PHONE/DATA OUTLET
	SPECIAL PURPOSE RECEPTACLE
	CARD READER
	TYPICAL ROOM LAYOUT OF PLAN

A	B	C
D	E	F

Office of
Construction
and Facilities
Management

 Department of
Veterans Affairs

The LA Group
40 Long Alley
Saratoga Springs, NY 12866
P: 518.587.8100
www.thelagroup.com

CANNONDESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© CannonDesign 2015
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by the Cannon Corporation

Project Title	VA OUTPATIENT CLINIC
Location	TYLER, TX

Date	Checked	Drawn
DEC 16, 2015	SDM	JR

Project Number
CANNON DESIGN PROJECT NO. 3640.46
Building Number
Drawing Number
A0201.2
Dwg. 6 of 14