



1. REFERENCE SCHEDULE "E" OF THE SFO PART II FINISH AND DOOR INFORMATION.
2. COORDINATE ALL WALL & FLOOR OUTLETS AND DATA/TELECOM PORTS WITH EQUIPMENT & FURNITURE LOCATIONS.
3. ALL CONSTRUCTION MUST COMPLY WITH ALL LOCAL BUILDING CODES.
5. PROVIDE WALL PROTECTION AS OUTLINED IN THE SFO PART I OR PROVIDE WALL PROTECTION AS REQUIRED.
6. PROVIDE FLOOR DRAINS IN ALL TOILET ROOMS.
7. PROVIDE FIRE EXTINGUISHER CABINETS AS REQUIRED BY CODE.
8. COORDINATE ALL BUILDING ENTRIES WITH SITE GRADE.
9. PROVIDE BACKING AND STRUCTURAL SUPPORT FOR ALL CEILING MOUNTED EQUIPMENT. PROVIDE MOUNTING EQUIPMENT AND PASS-THROUGH BOXES WITH FINAL EQUIPMENT LIST BY OWNER.
10. PROVIDE LEAD-LINED OR RF SHIELDING IN PARTITIONS, DOORS, AND BORROW LIGHTS IN ROOMS WITH IMAGING EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS AND SHIELDING PHYSICIST'S REPORT.

- 1 BARIATRIC TOILETS
- 2 COILING SECURITY DOOR (FROM CEILING TO COUNTERTOP).
- 3 SYSTEMS FURNITURE. COORD. DATA & POWER REQUIREMENTS.
- 4 CURTAIN & TRACK @ CEILING ABOVE, TYP
- 5 CEILING HUNG STAINLESS STEEL TOILET PARTITION.
- 6 PREFINISHED ALUMINUM STOREFRONT W/ CLEAR GLASS AND CAPTURED VERTICAL MULLIONS.
- 7 BUILT-IN CUSTOM CASKWORK.
- 8 BABY CHANGING STATION.
- 9 LINE OF CLERESTORY WINDOW ABOVE.
- 10 PREFINISHED ALUMINUM STOREFRONT W/ CLEAR BUTT GLAZING. PROVIDE GLASS WITH FRIT PATTERN.
- 11 LOCKERS
- 12 ACOUSTICAL PERFORMATED PANELS.
- 13 FREE-FORM BENCH.
- 14 DOCK LEVELER.
- 15 DOCK BUMPERS.
- 16 CUSTOM MILLWORK - REGISTRATION/ PHARMACY STATION W/ PRIVACY PANELS.
- 17 CUSTOM MILLWORK - INFORMATION DESK.
- 18 CUSTOM MILLWORK - SHELVING.
- 19 ACOUSTICAL WOOD PANEL SYSTEM (LAYERED DESIGN).
- 20 LOCKABLE, PASS-THRU WINDOW
- 21 PROVIDE PLUMBING ROUGH-IN FOR FUTURE SINK INSTALLATION

	2 HR FIRE RATED FIRE-BARRIER
	1 HR FIRE RATED FIRE-BARRIER
	SHIELDED WALL
	FLOOR DRAIN
	ELECT. DUPLEX
	ELECT. DUPLEX, G.F.I.
	ELECT. QUADRUPLUX
	PHONE/DATA OUTLET
	SPECIAL PURPOSE RECEPTACLE
	CARD READER

## KEY PLAN



Department of  
Veterans Affairs

Dwg. 8 of 14