




GENERAL NOTES:

1. REFER TO M0.01 FOR MECHANICAL LEGEND, ABBREVIATIONS AND GENERAL NOTES.
2. AS APPLICABLE, REMOVE ANY FIRE SPRINKLER PIPING LOCATED WITHIN THE ABANDONED P2 ELEVATOR MACHINE ROOM IN THE SUB-BASEMENT.

DRAWING NOTES:

- ① MOUNT CONDENSING UNIT ON EXTERIOR WALL (MINIMUM 2'-0" ABOVE GRADE). PROVIDE SUPPORTS AS REQUIRED.
- ② SIZE AND INSTALL REFRIGERANT PIPING PER MANUFACTURER'S RECOMMENDATIONS.
- ③ REMOVE AND REPLACE EXISTING SUMP PUMP AND ASSOCIATED CONTROLS. REFER TO DETAIL 1/M001 FOR SUMP PUMP INSTALLATION. CONNECT 2" PUMPED DISCHARGE TO EXISTING PIPING IN THIS AREA.
- ④ REMOVE EXISTING EXHAUST FAN AND ASSOCIATED LOUVER. PATCH EXTERIOR WALL TO MATCH EXISTING.
- ⑤ REWORK SPRINKLER PIPING IN THIS ROOM TO ACCOMMODATE ARCHITECTURAL LAYOUT.
- ⑥ REWORK SPRINKLER PIPING AND SPRINKLER HEAD CONFIGURATION TO PROVIDE NFPA 13 COMPLIANT SPRINKLER COVERAGE IN THE ELEVATOR PIT FOR ELEVATOR P1.
- ⑦ REFRIGERENT PIPING UP TO FIRST FLOOR. REFER TO 2/M101.
- ⑧ REFRIGERENT PIPING DOWN TO BASEMENT. REFER TO 1/M101.
- ⑨ ROUTE CONDENSATE PIPING TO BUILDING EXTERIOR.



Revisions	Date	<p>Consultants</p> <p>RICKERT ENGINEERING, INC.</p> <p>STRUCTURAL ENGINEERING 8813 WALTHAM WOODS ROAD, SUITE 301 BALTIMORE, MARYLAND 21234 410.663.5110 — FAX 410.663.5114</p> <p>ROBERT L. SEYMOUR ASSOCIATES</p> <p>AUTOMATIC TRANSPORT ENGINEERING 182 THOMAS JOHNSON DR. SUITE 200 FREDERICK, MARYLAND 21702 301.662.8112 — FAX 301.662.8117</p>	<p>BURDETTE KOEHLER MURPHY & ASSOCIATES, INC.</p> <p>MECHANICAL / ELECTRICAL / FIRE PROTECTION / TELECOMMUNICATIONS 1416 CLARKVIEW ROAD BALTIMORE, MARYLAND 21210 410.323.0600 — FAX 410.377.2543</p> <p>BUILDING COST CONSULTANTS, INC.</p> <p>COST ESTIMATING 123917 — 30TH AVENUE PLATTSMOUTH, NEBRASKA 68048 402.298.8260 — FAX 402.298.8290</p>	Seal	<p>DERBY</p>  <p>ARCHITECTURE PLANNING ENGINEERING</p> <p>2215 Conowingo Rd., Suite 100 Bel Air, Maryland 21015-1436 410.803.0009 fax 410.830.6611</p>	<p>Drawing Title</p> <p>BASEMENT FLOOR PLAN MECHANICAL — NEW WORK</p> <p>Approved: Chief Engineering Services</p> <p>Approved: Medical Center Director</p>	<p>Project Title</p> <p>REPLACE BUILDING 9 ELEVATORS</p> <p>Building Number 9</p> <p>Checked MAF</p> <p>Drawn ERS</p> <p>Location COATESVILLE, PENNSYLVANIA</p>	<p>Date 26, September 2014</p> <p>Project No. 542-08-110</p> <p>DRAWING NO. M101</p> <p>Dwg. — Of xx</p>	 <p>DEPARTMENT OF TRANSPORTATION</p>