

ASBESTOS BULK SAMPLE LOG

COC# 103630 & 103663

Fibertec IHS Project #: 28315-145

DATE: 7/30/10 **BUILDING:** VAMC, Building #145 **INSPECTOR:** K. Peterson & J. Suty

HA #	TOTAL FOOTAGE	MATERIAL TYPE	MATERIAL CONDITION	F/NF	MATERIAL ACM (Y/N)	ASBESTOS DETECTED (Y/N)	SAMPLE #	SAMPLE LOCATION
13	109 s.f.	MM	U	NF	No	No	13-1	Room 111G, near south door.
HA DESCRIPTION: 4" brown cove molding and associated mastic					NOTES: Mastic is also non asbestos containing			
14	3,264 s.f.	MM	U	NF	Yes	Yes	14-1	Room 111G, near south door.
HA DESCRIPTION: 1' x 1' beige/brown streaked floor tile and associated mastic					NOTES: Mastic is asbestos containing floor tile is not			
15	2 s.f.	MM	U	NF	No	No	15-1	Room 111E.
HA DESCRIPTION: Interior gray window caulk					NOTES:			
16	7 s.f.	MM	U	NF	No	No	16-1	Soiled Area, northeast door.
HA DESCRIPTION: Interior gray door caulk					NOTES:			
17	2 s.f.	MM	U	NF	No	No	17-1	Soiled Area, 10' north of Room 111E.
HA DESCRIPTION: Black vibration cloth					NOTES:			
18	1 s.f.	MM	U	NF	No	No	18-1	Room 111A, south wall.
HA DESCRIPTION: 3" black cove molding and associated mastic					NOTES: Mastic is also non asbestos containing			

ASBESTOS BULK SAMPLE LOG

COC# 103630 & 103663

Fibertec IHS Project #: 28315-145

DATE: 7/30/10 **BUILDING:** VAMC, Building #145 **INSPECTOR:** K. Peterson & J. Suty

HA #	TOTAL FOOTAGE	MATERIAL TYPE	MATERIAL CONDITION	F/NF	MATERIAL ACM (Y/N)	ASBESTOS DETECTED (Y/N)	SAMPLE #	SAMPLE LOCATION
19	38 s.f.	MM	U	NF	No*	Yes	19-1	Room 111A, near door.
HA DESCRIPTION:					NOTES:			
12" x 12" light brown floor tile with brown and black streaks and associated mastic					Floor tile contains <1% asbestos, no asbestos detected in mastic			
20	22 ct.	TSI	U	NF	No	No	20-1	Room 112.
HA DESCRIPTION:					NOTES:	No	20-2	Room 112.
Mud joints on fiberglass line						No	20-3	Room 112.
21	780 s.f.	MM	U	NF	Assumed			
HA DESCRIPTION:					NOTES:			
New ceramic wall tile bedding compound and grout					No sample collected			
22	322 s.f.	MM	U	NF	Assumed			
HA DESCRIPTION:					NOTES:			
New ceramic floor tile bedding compound and grout					No sample collected			
23	108 s.f.	MM	U	NF	No	No	23-1	Room 112, at Soiled Area door.
HA DESCRIPTION:					NOTES:			
4" black cove molding and associated mastic					Mastic is also non asbestos containing			
24	1 ct.	MM	U	NF	Yes	Yes	24-1	Room 112.
HA DESCRIPTION:					NOTES:			
White sink undercoating								

ASBESTOS BULK SAMPLE LOG

COC# 103630 & 103663

Fibertec IHS Project #: 28315-145

DATE: 7/30/10 **BUILDING:** VAMC, Building #145 **INSPECTOR:** K. Peterson & J. Suty

HA #	TOTAL FOOTAGE	MATERIAL TYPE	MATERIAL CONDITION	F/NF	MATERIAL ACM (Y/N)	ASBESTOS DETECTED (Y/N)	SAMPLE #	SAMPLE LOCATION
25	384 s.f.	MM	U	NF	No*	Yes	25-1	Lobby, at front door.
HA DESCRIPTION:					NOTES:			
12" x 12" brown floor tile and associated mastic					Floor tile contains <1% asbestos, no asbestos detected in mastic			
26	464 s.f.	MM	U	NF	No	No	26-1	Room 104, at west door.
HA DESCRIPTION:					NOTES:			
Vinyl wall covering and paste								
27	658 s.f.	SM	U	NF	No	No	27-1	Room 105, above door to Room 103.
HA DESCRIPTION:					NOTES:	No	27-2	Room 105, northeast corner.
Hard plaster						No	27-3	Hallway, outside Room 105.
28	5 s.f.	MM	U	NF	No	Yes	28-1	C11, 3' from Room 110.
HA DESCRIPTION:					NOTES:			
Dark brown door and building caulk					Sample contains less than 1% asbestos			
29	195 s.f.	MM	U	NF	No	No	29-1	Room 106, behind door.
HA DESCRIPTION:					NOTES:			
6" black cove molding and associated mastic					Mastic is also non asbestos containing			
30	3 ct.	TSI	U	NF	No	No	30-1	Center of Room 107, on collar.
HA DESCRIPTION:					NOTES:	No	30-2	Center of Room 107, on joint.
Roof drain pipe joint insulation						No	30-3	Center of Room 107, on joint.

ASBESTOS BULK SAMPLE LOG

COC# 103630 & 103663

Fibertec IHS Project #: 28315-145

DATE: 7/30/10 **BUILDING:** VAMC, Building #145 **INSPECTOR:** K. Peterson & J. Suty

HA #	TOTAL FOOTAGE	MATERIAL TYPE	MATERIAL CONDITION	F/NF	MATERIAL ACM (Y/N)	ASBESTOS DETECTED (Y/N)	SAMPLE #	SAMPLE LOCATION
31	2 s.f.	MM	U	NF	Assumed			
HA DESCRIPTION:					NOTES:			
White vibration collar					No sample collected			
32	6 s.f.	MM	U/SD	F & NF	No	No	32-1	Loading Dock, southeast windows.
HA DESCRIPTION:					NOTES:			
Interior white window glazing								
33	68 s.f.	MM	U	NF	No	No	33-1	Room 108A, near Room 112 door.
HA DESCRIPTION:					NOTES:			
6" brown cove molding and associated mastic					Mastic is also non asbestos containing			
34	2 s.f.	MM	U	NF	Assumed			
HA DESCRIPTION:					NOTES:			
Gray vibration cloth					No sample collected			
35	140 s.f.	MM	U	F	No	No	35-1	Room 108G, above door.
HA DESCRIPTION:					NOTES:			
2' x 2' white drop-in ceiling tile with pin holes and texture								
36	3 s.f.	MM	U	NF	No	No	36-1	Warehouse, Mezzanine Level.
HA DESCRIPTION:					NOTES:			
Red fire stop caulk								